



Thienes Engineering, Inc.
CIVIL ENGINEERING • LAND SURVEYING

PRELIMINARY HYDROLOGY CALCULATIONS

FOR

**HARLEY KNOX COMMERCE CENTER
NANCE STREET
PERRIS, CA**

PREPARED FOR

HARLEY KNOX 2021, LLC
11777 SAN VICENTE BOULEVARD, SUITE 780
LOS ANGELES, CA 90049
PHONE: (310) 979-8000
FAX: ((310) 979-7772

DECEMBER 1, 2021

JOB NO. 3951

PREPARED BY

THIENES ENGINEERING
14349 FIRESTONE BLVD.
LA MIRADA, CALIFORNIA 90638
PHONE: (714) 521-4811
FAX: (714) 521-4173

**PRELIMINARY HYDROLOGY
CALCULATIONS**

FOR

HARLEY KNOX COMMERCE CENTER

PREPARED UNDER
THE SUPERVISION OF

REINHARD STENZEL
R.C.E. 56155
EXP. 12/31/2022

DATE:

INTRODUCTION

A: PROJECT LOCATION

The project site is located on the west side of Redlands Avenue, north of Nance Street, and south of Harley Knox Boulevard in the City of Perris, California. Please see the following page for a vicinity map.


B: STUDY PURPOSE

The purpose of this study is to determine the existing condition and proposed condition 100-year peak flow rates from the project site that drains toward Nance Street.

C: PROJECT STAFF:

Thienes Engineering staff involved in this study include:

Reinhard Stenzel
Brian Weil
Tony Nuñez



DISCUSSION

Project Description

The project site encompasses approximately 6.45 acres. Proposed improvements to the site include a single commercial/warehouse type building that is approximately 156,094 square feet. There will be a truck dock along the westerly side of the building, vehicle parking will be located west and east of the building, and landscape areas will be street adjacent and throughout the site.

Existing Conditions

Under existing conditions, the site is mostly vacant with natural grasses and sparse vegetation throughout. There are foundations from residential buildings in the southeast and southwest sections of the site. The site generally drains from north to south toward Nance Street. The existing condition 100-year peak flow rates that surface drains to the south is approximately 2.7 cfs from the westerly 2.15 acres (nodes 100-101) and 5.6 cfs from the easterly 4.30 acres (nodes 110-111). The total existing condition 100-year peak flow rate that surface drains to the street is approximately 8.3 cfs (2.7 cfs + 5.6 cfs).

See Appendix “B” for the existing condition hydrology calculations and Appendix “C” for an existing condition hydrology map.

Offsite Hydrology

The site may accept offsite runoff from a portion of the neighboring site to the west. Potential runoff from the west will continue to surface drain onto the project site along the westerly property line, join the onsite system, and discharge from the site via a proposed storm drain system.

Proposed Conditions

In the proposed condition, runoff from the westerly portion of the building, the truck yard, and the southwesterly and northwesterly parking lots will surface drain to several catch basins located within the truck yard (nodes 100-132). Flow from the easterly portion of the building and the parking lot to the east will surface drain to two catch basins within the parking lot (nodes 140-152). Proposed storm drain systems, Lines A and B, will convey stormwater to the south and discharge into a proposed public storm drain system in Nance Street. The southerly and northerly street adjacent landscaping will surface drain directly into the respective street (nodes 160 and 170, respectively). The total proposed condition 100-year peak flow rate is approximately 22.0 cfs (15.6 cfs from the westerly truck yard + 4.6 cfs from the easterly parking lot + 0.9 cfs from the southerly landscaping + 0.9 cfs from the northerly landscaping).

The project site and the westerly neighboring site are modeled as commercial and tabled to an existing 54" RCP, Lateral D-3, in Redlands Avenue per the Hydrology and Hydraulic Analysis report dated August 2013 by Albert A. Webb Associates (WEBB). A proposed public storm drain system in Nance Street will convey stormwater from the site and ultimately discharge to Lateral D-3. The public storm drain system will be sized to adequately convey runoff from the project site and the future development of the adjacent property to the west. The storm drain will convey flows from the project site to the east and connect to an existing 54" R.C.P. in Redlands Avenue. A catch basin is proposed in Nance Street along with street improvements for the development of the project site. The proposed onsite and the master plan storm drain facilities are designed for a 100-year storm frequency and do not negatively affect downstream facilities.

See Appendix "B" for the proposed condition hydrology calculations and Appendix "C" for a proposed condition hydrology map.

Methodology

Hydrology calculations were computed using Riverside County rational method program (by AES software). The soil type is "C" per Riverside County Hydrology Manual.

See Appendix "A" for referenced materials.

Water Quality

The project proposes to use underground retention facilities. Roof and surface runoff will sheet flow into inlets where stormwater will be intercepted and diverted into the perforated CMPs for water quality treatment. These systems will utilize infiltration as their primary form of treatment. These systems store stormwater runoff until it gradually exfiltrates into the underlying soil. Pollutant removal occurs through the infiltration of runoff and the adsorption of pollutants into the soil. This practice has high pollutant removal efficiency and can also help recharge groundwater, thus helping to maintain low flows in stream systems. See separate WQMP report, prepared by Thienes Engineering, for more information.

APPENDIX

DESCRIPTION

A

REFERENCE MATERIAL

B


HYDROLOGY CALCULATIONS

C

HYDROLOGY MAPS

APPENDIX A

REFERENCE MATERIAL




SITE

NOTES:
 Isohyets based on NOAA Atlas 2,
 Volume XI - California, 1973

RCFC & WCD
 HYDROLOGY MANUAL

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT		
2-YEAR — 1-HOUR PRECIPITATION		
APPROVED	DRAWN BY	SHEET NO.
DATE	CHIEF ENGINEER R.E. NO. 8832	DR. NO.
PLATE D-43		




SITE

NOTES:
1. Isohyets based on NOAA Atlas 2,
Volume XI - California, 1973.

RCFC & WCD
HYDROLOGY MANUAL

0.80"

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT		
2-YEAR — 3-HOUR PRECIPITATION		
APPROVED: _____ DATE: _____	DRAWN BY: <i>R.A.S.</i>	SHEET NO. _____
PLATE E-5.1		DR. NO. _____




SITE

NOTES:
 1. Isohyets from NOAA Atlas 2
 Volume XI - California, 1973

RCFC & WCD
 HYDROLOGY MANUAL

1.00" RIVER-SIDE, CA

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT		
2-YEAR — 6-HOUR PRECIPITATION		
APPROVED: CHIEF ENGINEER R.E. NO. 882	DRAWN BY:	SHEET NO.
DATE:	PLATE E-5.3	DN. NO.




SITE

NOTES:
 1. Isohyets from NOAA Atlas 2
 Volume XI - California, 1973.

RCFC & WCD
 HYDROLOGY MANUAL

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT		
2-YEAR — 24-HOUR PRECIPITATION		
APPROVED: CHIEF ENGINEER R.E. NO. 8822	DRAWN BY: R.A.S.	SHEET NO.
DATE:	PLATE E-5.5	DR. NO.




SITE

NOTES:
 Isohyets based on NOAA Atlas
 Volume XI - California, 1973

RCFC & WCD
 HYDROLOGY MANUAL
 1.20"

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT		
100-YEAR — 1-HOUR PRECIPITATION		
APPROVED: _____ CHIEF ENGINEER P.E. NO. 4822	DRAWN BY: <i>C.A.S.</i>	SHEET NO. _____
DATE: _____	PLATE D-4.4	Dr. No. _____




SITE

NOTES:
 1. Isohyets based on NOAA Atlas 2
 Volume XI - California, 1973



RCFC & WCD
 HYDROLOGY MANUAL
 1.87"

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT		
100-YEAR — 3-HOUR PRECIPITATION		
APPROVED: <i>[Signature]</i> DATE:	DRAWN BY: <i>[Signature]</i> PLATE E-5.2	SHEET NO. DR. NO.




SITE

NOTES:
 Isohyets from NOAA Atlas 2,
 Volume XI - California, 1973



RCFC & WCD
 HYDROLOGY MANUAL

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT	
100-YEAR — 6-HOUR PRECIPITATION	
APPROVED: CHIEF ENGINEER P.E. NO. 8822	DRAWN BY: <i>R.A.A.</i>
DATE	SHEET NO.
	PLATE E-5.4



SITE


NOTES:
 1. Isohyets from NOAA Atlas 2,
 Volume XI - California, 1973.

RCFC & WCD
 HYDROLOGY MANUAL

4.00"


RIVERSIDE COUNTY FLOOD CONTROL
 AND
 WATER CONSERVATION DISTRICT
**100-YEAR — 24-HOUR
 PRECIPITATION**


APPROVED: CHIEF ENGINEER R.E. NO. 8822	DRAWN BY:	SHEET NO.
DATE	PLATE E-5.6	DR. NO.



SOIL GROUP C

<p>LEGEND</p> <p>— SOILS GROUP BOUNDARY</p> <p>A SOILS GROUP DESIGNATION</p> <p>RCFC & WCD</p> <p>HYDROLOGY MANUAL</p>	<p>HYDROLOGIC SOILS GROUP MAP</p> <p>FOR</p> <p>PERRIS</p>
--	---





SITE

NOTES:
 1. Slope of Intensity-Duration Curve Based on District analysis of automatic recording rain-gage records.

RCFC & WCD
 HYDROLOGY MANUAL
 0.50

RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT		
SLOPE OF INTENSITY DURATION CURVE		
APPROVED: CHIEF ENGINEER DATE	DRAWN BY: P.A.S.	SHEET NO. PLATE D-4.6 Dr. No.

**HYDROLOGY & HYDRAULIC
ANALYSIS
PERRIS VALLEY MDP
PORTION OF STORM DRAIN LINE D,
LATERAL D-2, & LATERAL D-3**

**CITY OF PERRIS
COUNTY OF RIVERSIDE
CALIFORNIA**

**PREPARED FOR:
Stratford Ranch Partners, LLC
3649 Mission Inn Avenue
Riverside, CA 92501
Phone: (951) 778-2999 – Fax: (951) 778-0889**

PREPARED BY:

A L B E R T A .

WEBB

A S S O C I A T E S

**3788 McCray Street
Riverside, CA 92506
Phone: (951) 686-1070 – Fax: (951) 788-1256**

DATE PREPARED:

May 30, 2008

March 2013

April 2013

June 2013

REVISED: August 2013

**W.O.:
2012-0072**

**HYDROLOGY & HYDRAULIC ANALYSIS
FOR PORTION OF STORM DRAIN LINE D,
LATERAL D-2, & LATERAL D-3**

**CITY OF PERRIS
COUNTY OF RIVERSIDE
CALIFORNIA**

**PREPARED FOR:
Stratford Ranch Partners, LLC
3649 Mission Inn Avenue
Riverside, CA 92501
Phone: (951) 778-2999 – Fax: (951) 778-0889**

PREPARED BY:




**3788 McCray Street
Riverside, CA 92506
Phone: (951) 686-1070
Fax: (951) 788-1256**

This report has been prepared by or under the direction of the following registered civil engineer who attests to the technical information contained herein. The register engineer has also judged the qualifications of any technical specialists providing engineering data upon which recommendations, conclusions and decisions are based.

**Joseph C. Caldwell, P.E.
Senior Engineer
Albert A. Webb Associates**

Date

Stamp





Perris Valley MDP E-3
Tributary Area=134 acres

Perris Valley MDP E-11
Tributary Area=108.3 acres

LEGEND

- HYD BOUNDARY
- HYD SUB-AREA
- STORMDRAIN
- NODE
- ELEVATION
- AREA
- LENGTH



LINE D HYDROLOGY	
PERRIS VALLEY COMMERCE CENTER	
SPECIFIC PLAN	
LINE D	
HYDROLOGY MAP	
DATE: 08/20/2013	CIVIL ENGINEERS
SCALE: AS SHOWN	PROJECT NO: 2009
DESIGNED: J. J. WEBB	REVISION NO: 0006
CHECKED: J. J. WEBB	DATE: 08/20/2013
APPROVED: J. J. WEBB	BY: J. J. WEBB
PROJECT: PERRIS VALLEY COMMERCE CENTER	SHEET NO: 1
SHEET 1 OF 1	

SECTION 3

Ultimate Developed Condition

100-Year Rational Method Hydrology Analysis

Areas Tributary to Storm Drain Lateral D, Lateral D-2,

& Lateral D-3

Runoff from this stream = 38.230(CFS)
Time of concentration = 33.98 min.
Rainfall intensity = 1.585(In/Hr)

++++
Process from Point/Station 136.800 to Point/Station 136.900
**** INITIAL AREA EVALUATION ****

Initial area flow distance = 893.000(Ft.)
Top (of initial area) elevation = 1457.500(Ft.)
Bottom (of initial area) elevation = 1455.500(Ft.)
Difference in elevation = 2.000(Ft.)
Slope = 0.00224 s(percent) = 0.22
TC = $k(0.300)*[(\text{length}^3)/(\text{elevation change})]^{0.2}$
Initial area time of concentration = 15.397 min.
Rainfall intensity = 2.337(In/Hr) for a 100.0 year storm
COMMERCIAL subarea type
Runoff Coefficient = 0.882
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
RI index for soil(AMC 2) = 69.00
Pervious area fraction = 0.100; Impervious fraction = 0.900
Initial subarea runoff = 20.603(CFS)
Total initial stream area = 10.000(Ac.)
Pervious area fraction = 0.100

++++
Process from Point/Station 136.900 to Point/Station 136.700
**** NATURAL CHANNEL TIME + SUBAREA FLOW ADDITION ****

Top of natural channel elevation = 1455.500(Ft.)
End of natural channel elevation = 1454.500(Ft.)
Length of natural channel = 786.000(Ft.)
Estimated mean flow rate at midpoint of channel = 33.067(CFS)

Natural valley channel type used
L.A. County flood control district formula for channel velocity:
Velocity(ft/s) = $(7 + 8(q(\text{English Units})^{0.352})(\text{slope}^{0.5}))$
Velocity using mean channel flow = 1.23(Ft/s)

Correction to map slope used on extremely rugged channels with
drops and waterfalls (Plate D-6.2)
Normal channel slope = 0.0013
Corrected/adjusted channel slope = 0.0013
Travel time = 10.67 min. TC = 26.07 min.

Adding area flow to channel
COMMERCIAL subarea type
Runoff Coefficient = 0.878
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
RI index for soil(AMC 2) = 69.00
Pervious area fraction = 0.100; Impervious fraction = 0.900
Rainfall intensity = 1.805(In/Hr) for a 100.0 year storm
Subarea runoff = 19.171(CFS) for 12.100(Ac.)
Total runoff = 39.774(CFS) Total area = 22.100(Ac.)

++++
Process from Point/Station 136.900 to Point/Station 136.700
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 2 in normal stream number 2
Stream flow area = 22.100(Ac.)

SECTION 3

Ultimate Developed Condition

10-Year Rational Method Hydrology Analysis

Areas Tributary to Storm Drain Lateral D, Lateral D-2

& Lateral D-3

Time of concentration = 35.04 min.
Rainfall intensity = 1.271(In/Hr)

++++
Process from Point/Station 136.800 to Point/Station 136.900
**** INITIAL AREA EVALUATION ****

Initial area flow distance = 893.000(Ft.)
Top (of initial area) elevation = 1457.500(Ft.)
Bottom (of initial area) elevation = 1455.500(Ft.)
Difference in elevation = 2.000(Ft.)
Slope = 0.00224 s(percent)= 0.22
TC = $k(0.300)*[(length^3)/(elevation\ change)]^{0.2}$
Initial area time of concentration = 15.397 min.
Rainfall intensity = 1.901(In/Hr) for a 10.0 year storm
COMMERCIAL subarea type
Runoff Coefficient = 0.878
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
RI index for soil(AMC 2) = 69.00
Pervious area fraction = 0.100; Impervious fraction = 0.900
Initial subarea runoff = 16.702(CFS)
Total initial stream area = 10.000(Ac.)
Pervious area fraction = 0.100

++++
Process from Point/Station 136.900 to Point/Station 136.700
**** NATURAL CHANNEL TIME + SUBAREA FLOW ADDITION ****

Top of natural channel elevation = 1455.500(Ft.)
End of natural channel elevation = 1454.500(Ft.)
Length of natural channel = 786.000(Ft.)
Estimated mean flow rate at midpoint of channel = 26.807(CFS)

Natural valley channel type used
L.A. County flood control district formula for channel velocity:
Velocity(ft/s) = $(7 + 8(q(\text{English Units})^{.352})(\text{slope}^{.5}))$
Velocity using mean channel flow = 1.16(Ft/s)

Correction to map slope used on extremely rugged channels with
drops and waterfalls (Plate D-6.2)
Normal channel slope = 0.0013
Corrected/adjusted channel slope = 0.0013
Travel time = 11.32 min. TC = 26.71 min.

Adding area flow to channel
COMMERCIAL subarea type
Runoff Coefficient = 0.874
Decimal fraction soil group A = 0.000
Decimal fraction soil group B = 0.000
Decimal fraction soil group C = 1.000
Decimal fraction soil group D = 0.000
RI index for soil(AMC 2) = 69.00
Pervious area fraction = 0.100; Impervious fraction = 0.900
Rainfall intensity = 1.451(In/Hr) for a 10.0 year storm
Subarea runoff = 15.345(CFS) for 12.100(Ac.)
Total runoff = 32.047(CFS) Total area = 22.100(Ac.)

++++
Process from Point/Station 136.900 to Point/Station 136.700
**** CONFLUENCE OF MINOR STREAMS ****

Along Main Stream number: 2 in normal stream number 2
Stream flow area = 22.100(Ac.)
Runoff from this stream = 32.047(CFS)

SECTION 3

**Revised Ultimate Developed Condition
100-Year Rational Method Hydrology Analysis
Street Flow tributary to Redlands Avenue
Areas A, B, C & D**

APPENDIX B

HYDROLOGY CALCULATIONS

EXISTING CONDITION

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON
RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT
(RCFC&WCD) 1978 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
(Rational Tabling Version 23.0)
Release Date: 07/01/2016 License ID 1435

Analysis prepared by:

***** DESCRIPTION OF STUDY *****
* NANCE STREET INDUSTRIAL DEVELOPMENT *
* EXISTING CONDITION 100-YEAR *
* NODES 100-101 *

FILE NAME: W:\3951\E100.DAT
TIME/DATE OF STUDY: 18:15 03/12/2021

USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:

USER SPECIFIED STORM EVENT (YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE (INCH) = 12.00
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.95
2-YEAR, 1-HOUR PRECIPITATION (INCH) = 0.450
100-YEAR, 1-HOUR PRECIPITATION (INCH) = 1.200
COMPUTED RAINFALL INTENSITY DATA:
STORM EVENT = 100.00 1-HOUR INTENSITY (INCH/HOUR) = 1.200
SLOPE OF INTENSITY DURATION CURVE = 0.5000
RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
NOTE: CONSIDER ALL CONFLUENCE STREAM COMBINATIONS
FOR ALL DOWNSTREAM ANALYSES

USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL

NO.	HALF- WIDTH (FT)	CROWN TO CROSSFALL (FT)	STREET-CROSSFALL: IN- / OUT-/PARK- SIDE / SIDE/ WAY	CURB HEIGHT (FT)	GUTTER-GEOMETRIES: WIDTH LIP HIKE (FT) (FT) (FT)	MANNING FACTOR (n)
1	30.0	20.0	0.018/0.018/0.020	0.67	2.00 0.0313 0.167	0.0150

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:

- Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
 - (Depth)*(Velocity) Constraint = 6.0 (FT*FT/S)
- *SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*

FLOW PROCESS FROM NODE 100.00 TO NODE 101.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====

ASSUMED INITIAL SUBAREA UNIFORM
DEVELOPMENT IS: UNDEVELOPED WITH POOR COVER
TC = K * [(LENGTH**3)/(ELEVATION CHANGE)]**.2
INITIAL SUBAREA FLOW-LENGTH (FEET) = 611.00
UPSTREAM ELEVATION (FEET) = 1456.95
DOWNSTREAM ELEVATION (FEET) = 1456.02
ELEVATION DIFFERENCE (FEET) = 0.93
TC = 0.533 * [(611.00**3)/(0.93)]**.2 = 25.371
100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 1.845
UNDEVELOPED WATERSHED RUNOFF COEFFICIENT = .6794
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF (CFS) = 2.70
TOTAL AREA (ACRES) = 2.15 TOTAL RUNOFF (CFS) = 2.70

END OF STUDY SUMMARY:
TOTAL AREA (ACRES) = 2.2 TC (MIN.) = 25.37
PEAK FLOW RATE (CFS) = 2.70
=====

END OF RATIONAL METHOD ANALYSIS



RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON
RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT
(RCFC&WCD) 1978 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
(Rational Tabling Version 23.0)
Release Date: 07/01/2016 License ID 1435

Analysis prepared by:

***** DESCRIPTION OF STUDY *****
* NANCE STREET INDUSTRIAL DEVELOPMENT *
* EXISTING CONDITION 100-YEAR *
* NODES 110-111 *

FILE NAME: W:\3951\E110.DAT
TIME/DATE OF STUDY: 18:25 03/12/2021

USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:

USER SPECIFIED STORM EVENT (YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE (INCH) = 12.00
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.95
2-YEAR, 1-HOUR PRECIPITATION (INCH) = 0.450
100-YEAR, 1-HOUR PRECIPITATION (INCH) = 1.200
COMPUTED RAINFALL INTENSITY DATA:
STORM EVENT = 100.00 1-HOUR INTENSITY (INCH/HOUR) = 1.200
SLOPE OF INTENSITY DURATION CURVE = 0.5000
RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
NOTE: CONSIDER ALL CONFLUENCE STREAM COMBINATIONS
FOR ALL DOWNSTREAM ANALYSES

USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL

NO.	HALF- WIDTH (FT)	CROWN TO CROSSFALL (FT)	STREET-CROSSFALL IN- / OUT- / PARK- SIDE / SIDE / WAY	CURB HEIGHT (FT)	GUTTER-GEOMETRIES WIDTH LIP HIKE (FT) (FT) (FT)	MANNING FACTOR (n)
1	30.0	20.0	0.018/0.018/0.020	0.67	2.00 0.0313 0.167	0.0150

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:

- Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
 - (Depth)*(Velocity) Constraint = 6.0 (FT*FT/S)
- *SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*

FLOW PROCESS FROM NODE 110.00 TO NODE 111.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====

ASSUMED INITIAL SUBAREA UNIFORM
DEVELOPMENT IS: UNDEVELOPED WITH POOR COVER
TC = K * [(LENGTH**3) / (ELEVATION CHANGE)]**0.2
INITIAL SUBAREA FLOW-LENGTH (FEET) = 593.00
UPSTREAM ELEVATION (FEET) = 1456.80
DOWNSTREAM ELEVATION (FEET) = 1455.57
ELEVATION DIFFERENCE (FEET) = 1.23
TC = 0.533 * [(593.00**3) / (1.23)]**0.2 = 23.564
100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 1.915
UNDEVELOPED WATERSHED RUNOFF COEFFICIENT = .6855
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF (CFS) = 5.64
TOTAL AREA (ACRES) = 4.30 TOTAL RUNOFF (CFS) = 5.64

END OF STUDY SUMMARY:
TOTAL AREA (ACRES) = 4.3 TC (MIN.) = 23.56
PEAK FLOW RATE (CFS) = 5.64
=====

END OF RATIONAL METHOD ANALYSIS

PROPOSED CONDITION

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON
RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT
(RCFC&WCD) 1978 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
(Rational Tabling Version 23.0)
Release Date: 07/01/2016 License ID 1435

Analysis prepared by:

***** DESCRIPTION OF STUDY *****
* NANCE STREET INDUSTRIAL DEVELOPMENT *
* PROPOSED CONDITION 100-YEAR *
* NODES 100-132 *

FILE NAME: W:\3951\P100.DAT
TIME/DATE OF STUDY: 16:34 04/27/2021

USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:

USER SPECIFIED STORM EVENT (YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE (INCH) = 12.00
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.95
2-YEAR, 1-HOUR PRECIPITATION (INCH) = 0.450
100-YEAR, 1-HOUR PRECIPITATION (INCH) = 1.200
COMPUTED RAINFALL INTENSITY DATA:
STORM EVENT = 100.00 1-HOUR INTENSITY (INCH/HOUR) = 1.200
SLOPE OF INTENSITY DURATION CURVE = 0.5000
RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
NOTE: CONSIDER ALL CONFLUENCE STREAM COMBINATIONS
FOR ALL DOWNSTREAM ANALYSES

USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL
HALF- CROWN TO STREET-CROSSFALL: CURB GUTTER-GEOMETRIES: MANNING
WIDTH CROSSFALL IN- / OUT-/PARK- HEIGHT WIDTH LIP HIKE FACTOR
NO. (FT) (FT) SIDE / SIDE/ WAY (FT) (FT) (FT) (FT) (n)
=====
1 30.0 20.0 0.018/0.018/0.020 0.67 2.00 0.0313 0.167 0.0150

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:

1. Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
 2. (Depth)*(Velocity) Constraint = 6.0 (FT*FT/S)
- *SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*

FLOW PROCESS FROM NODE 100.00 TO NODE 101.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<

ASSUMED INITIAL SUBAREA UNIFORM
DEVELOPMENT IS COMMERCIAL
TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
INITIAL SUBAREA FLOW-LENGTH (FEET) = 139.00
UPSTREAM ELEVATION (FEET) = 1456.22
DOWNSTREAM ELEVATION (FEET) = 1453.17
ELEVATION DIFFERENCE (FEET) = 3.05
TC = 0.303*[(139.00**3)/(3.05)]**.2 = 4.683
COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.157
COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8887
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF (CFS) = 4.99
TOTAL AREA (ACRES) = 1.35 TOTAL RUNOFF (CFS) = 4.99

FLOW PROCESS FROM NODE 101.00 TO NODE 112.00 IS CODE = 31

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<

ELEVATION DATA: UPSTREAM (FEET) = 1450.58 DOWNSTREAM (FEET) = 1450.34
FLOW LENGTH (FEET) = 121.00 MANNING'S N = 0.012
DEPTH OF FLOW IN 21.0 INCH PIPE IS 12.6 INCHES
PIPE-FLOW VELOCITY (FEET/SEC.) = 3.32
ESTIMATED PIPE DIAMETER (INCH) = 21.00 NUMBER OF PIPES = 1
PIPE-FLOW (CFS) = 4.99
PIPE TRAVEL TIME (MIN.) = 0.61 Tc (MIN.) = 5.61
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 112.00 = 260.00 FEET.

FLOW PROCESS FROM NODE 112.00 TO NODE 122.00 IS CODE = 1

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<

TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION (MIN.) = 5.61
RAINFALL INTENSITY (INCH/HR) = 3.93
TOTAL STREAM AREA (ACRES) = 1.35
PEAK FLOW RATE (CFS) AT CONFLUENCE = 4.99

FLOW PROCESS FROM NODE 110.00 TO NODE 111.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<

ASSUMED INITIAL SUBAREA UNIFORM DEVELOPMENT IS COMMERCIAL
TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
INITIAL SUBAREA FLOW-LENGTH(FEET) = 116.00
UPSTREAM ELEVATION(FEET) = 1455.01
DOWNSTREAM ELEVATION(FEET) = 1453.17
ELEVATION DIFFERENCE(FEET) = 1.84
TC = 0.303*[(116.00**3)/(1.84)]**.2 = 4.648
COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.157
COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8887
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF(CFS) = 3.32
TOTAL AREA(ACRES) = 0.90 TOTAL RUNOFF(CFS) = 3.32

FLOW PROCESS FROM NODE 111.00 TO NODE 112.00 IS CODE = 31

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<

ELEVATION DATA: UPSTREAM(FEET) = 1450.67 DOWNSTREAM(FEET) = 1450.59
FLOW LENGTH(FEET) = 23.00 MANNING'S N = 0.012
DEPTH OF FLOW IN 15.0 INCH PIPE IS 10.4 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 3.66
ESTIMATED PIPE DIAMETER(INCH) = 15.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 3.32
PIPE TRAVEL TIME(MIN.) = 0.10 Tc(MIN.) = 5.10
LONGEST FLOWPATH FROM NODE 110.00 TO NODE 112.00 = 139.00 FEET.

FLOW PROCESS FROM NODE 112.00 TO NODE 112.00 IS CODE = 1

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<

TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION(MIN.) = 5.10
RAINFALL INTENSITY(INCH/HR) = 4.11
TOTAL STREAM AREA(ACRES) = 0.90
PEAK FLOW RATE(CFS) AT CONFLUENCE = 3.32

** CONFLUENCE DATA **
Table with 5 columns: STREAM NUMBER, RUNOFF (CFS), Tc (MIN.), INTENSITY (INCH/HOUR), AREA (ACRE). Rows 1 and 2.

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **
Table with 4 columns: STREAM NUMBER, RUNOFF (CFS), Tc (MIN.), INTENSITY (INCH/HOUR). Rows 1 and 2.

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
PEAK FLOW RATE(CFS) = 8.16 Tc(MIN.) = 5.61
TOTAL AREA(ACRES) = 2.2
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 112.00 = 260.00 FEET.

FLOW PROCESS FROM NODE 112.00 TO NODE 122.00 IS CODE = 31

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<

ELEVATION DATA: UPSTREAM(FEET) = 1450.33 DOWNSTREAM(FEET) = 1450.13
FLOW LENGTH(FEET) = 100.00 MANNING'S N = 0.012
DEPTH OF FLOW IN 24.0 INCH PIPE IS 15.7 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 3.74
ESTIMATED PIPE DIAMETER(INCH) = 24.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 8.16
PIPE TRAVEL TIME(MIN.) = 0.45 Tc(MIN.) = 6.05
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 122.00 = 360.00 FEET.

FLOW PROCESS FROM NODE 122.00 TO NODE 122.00 IS CODE = 1

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<

TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION(MIN.) = 6.05
RAINFALL INTENSITY(INCH/HR) = 3.78
TOTAL STREAM AREA(ACRES) = 2.25
PEAK FLOW RATE(CFS) AT CONFLUENCE = 8.16

FLOW PROCESS FROM NODE 120.00 TO NODE 121.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<

ASSUMED INITIAL SUBAREA UNIFORM

DEVELOPMENT IS COMMERCIAL
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH(FEET) = 116.00
 UPSTREAM ELEVATION(FEET) = 1455.01
 DOWNSTREAM ELEVATION(FEET) = 1453.17
 ELEVATION DIFFERENCE(FEET) = 1.84
 TC = 0.303*[(116.00**3)/(1.84)]**.2 = 4.648
 COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
 100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.157
 COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8887
 SOIL CLASSIFICATION IS "C"
 SUBAREA RUNOFF(CFS) = 3.32
 TOTAL AREA(ACRES) = 0.90 TOTAL RUNOFF(CFS) = 3.32

 FLOW PROCESS FROM NODE 121.00 TO NODE 122.00 IS CODE = 31

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
 >>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
 =====
 ELEVATION DATA: UPSTREAM(FEET) = 1450.67 DOWNSTREAM(FEET) = 1450.39
 FLOW LENGTH(FEET) = 24.00 MANNING'S N = 0.012
 DEPTH OF FLOW IN 12.0 INCH PIPE IS 8.2 INCHES
 PIPE-FLOW VELOCITY(FEET/SEC.) = 5.78
 ESTIMATED PIPE DIAMETER(INCH) = 12.00 NUMBER OF PIPES = 1
 PIPE-FLOW(CFS) = 3.32
 PIPE TRAVEL TIME(MIN.) = 0.07 Tc(MIN.) = 5.07
 LONGEST FLOWPATH FROM NODE 120.00 TO NODE 122.00 = 140.00 FEET.

 FLOW PROCESS FROM NODE 122.00 TO NODE 122.00 IS CODE = 1

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
 >>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<
 =====
 TOTAL NUMBER OF STREAMS = 2
 CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
 TIME OF CONCENTRATION(MIN.) = 5.07
 RAINFALL INTENSITY(INCH/HR) = 4.13
 TOTAL STREAM AREA(ACRES) = 0.90
 PEAK FLOW RATE(CFS) AT CONFLUENCE = 3.32

** CONFLUENCE DATA **

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)	AREA (ACRE)
1	7.86	5.55	3.944	2.25
1	8.16	6.05	3.778	2.25
2	3.32	5.07	4.128	0.90

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
 CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)
1	10.50	5.07	4.128
2	11.04	5.55	3.944
3	11.20	6.05	3.778

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
 PEAK FLOW RATE(CFS) = 11.20 Tc(MIN.) = 6.05
 TOTAL AREA(ACRES) = 3.2
 LONGEST FLOWPATH FROM NODE 100.00 TO NODE 122.00 = 360.00 FEET.

 FLOW PROCESS FROM NODE 122.00 TO NODE 132.00 IS CODE = 31

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
 >>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
 =====
 ELEVATION DATA: UPSTREAM(FEET) = 1450.13 DOWNSTREAM(FEET) = 1449.94
 FLOW LENGTH(FEET) = 96.00 MANNING'S N = 0.012
 DEPTH OF FLOW IN 27.0 INCH PIPE IS 17.8 INCHES
 PIPE-FLOW VELOCITY(FEET/SEC.) = 4.04
 ESTIMATED PIPE DIAMETER(INCH) = 27.00 NUMBER OF PIPES = 1
 PIPE-FLOW(CFS) = 11.20
 PIPE TRAVEL TIME(MIN.) = 0.40 Tc(MIN.) = 6.45
 LONGEST FLOWPATH FROM NODE 100.00 TO NODE 132.00 = 456.00 FEET.

 FLOW PROCESS FROM NODE 132.00 TO NODE 132.00 IS CODE = 1

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
 =====
 TOTAL NUMBER OF STREAMS = 2
 CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
 TIME OF CONCENTRATION(MIN.) = 6.45
 RAINFALL INTENSITY(INCH/HR) = 3.66
 TOTAL STREAM AREA(ACRES) = 3.15
 PEAK FLOW RATE(CFS) AT CONFLUENCE = 11.20

 FLOW PROCESS FROM NODE 130.00 TO NODE 131.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
 =====
 ASSUMED INITIAL SUBAREA UNIFORM
 DEVELOPMENT IS COMMERCIAL
 TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
 INITIAL SUBAREA FLOW-LENGTH(FEET) = 152.00

UPSTREAM ELEVATION(FEET) = 1456.11
 DOWNSTREAM ELEVATION(FEET) = 1453.17
 ELEVATION DIFFERENCE(FEET) = 2.94
 $TC = 0.303 * [(152.00 ** 3) / (2.94)] ** .2 = 4.978$
 COMPUTED TIME OF CONCENTRATION INCREASED TO 5 MIN.
 100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.157
 COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8887
 SOIL CLASSIFICATION IS "C"
 SUBAREA RUNOFF(CFS) = 4.99
 TOTAL AREA(ACRES) = 1.35 TOTAL RUNOFF(CFS) = 4.99

 FLOW PROCESS FROM NODE 131.00 TO NODE 132.00 IS CODE = 31

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
 >>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
 =====
 ELEVATION DATA: UPSTREAM(FEET) = 1450.67 DOWNSTREAM(FEET) = 1450.45
 FLOW LENGTH(FEET) = 23.00 MANNING'S N = 0.012
 DEPTH OF FLOW IN 15.0 INCH PIPE IS 9.7 INCHES
 PIPE-FLOW VELOCITY(FEET/SEC.) = 5.96
 ESTIMATED PIPE DIAMETER(INCH) = 15.00 NUMBER OF PIPES = 1
 PIPE-FLOW(CFS) = 4.99
 PIPE TRAVEL TIME(MIN.) = 0.06 Tc(MIN.) = 5.06
 LONGEST FLOWPATH FROM NODE 130.00 TO NODE 132.00 = 175.00 FEET.

 FLOW PROCESS FROM NODE 132.00 TO NODE 132.00 IS CODE = 1

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
 >>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<
 =====

TOTAL NUMBER OF STREAMS = 2
 CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
 TIME OF CONCENTRATION(MIN.) = 5.06
 RAINFALL INTENSITY(INCH/HR) = 4.13
 TOTAL STREAM AREA(ACRES) = 1.35
 PEAK FLOW RATE(CFS) AT CONFLUENCE = 4.99

** CONFLUENCE DATA **

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)	AREA (ACRE)
1	10.50	5.48	3.969	3.15
1	11.04	5.95	3.810	3.15
1	11.20	6.45	3.660	3.15
2	4.99	5.06	4.130	1.35

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
 CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)
1	14.69	5.06	4.130
2	15.30	5.48	3.969
3	15.64	5.95	3.810
4	15.62	6.45	3.660

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
 PEAK FLOW RATE(CFS) = 15.64 Tc(MIN.) = 5.95
 TOTAL AREA(ACRES) = 4.5
 LONGEST FLOWPATH FROM NODE 100.00 TO NODE 132.00 = 456.00 FEET.

END OF STUDY SUMMARY:
 TOTAL AREA(ACRES) = 4.5 TC(MIN.) = 5.95
 PEAK FLOW RATE(CFS) = 15.64

*** PEAK FLOW RATE TABLE ***

Q (CFS)	Tc (MIN.)
1 14.69	5.06
2 15.30	5.48
3 15.64	5.95
4 15.62	6.45

=====

END OF RATIONAL METHOD ANALYSIS

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON
RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT
(RCFC&WCD) 1978 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
(Rational Tabling Version 23.0)
Release Date: 07/01/2016 License ID 1435

Analysis prepared by:

***** DESCRIPTION OF STUDY *****
* NANCE STREET INDUSTRIAL DEVELOPMENT *
* PROPOSED CONDITION 100-YEAR *
* NODES 140-152 *

FILE NAME: W:\3951\p140.DAT
TIME/DATE OF STUDY: 16:42 04/27/2021

USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:

USER SPECIFIED STORM EVENT (YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE (INCH) = 12.00
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.95
2-YEAR, 1-HOUR PRECIPITATION (INCH) = 0.450
100-YEAR, 1-HOUR PRECIPITATION (INCH) = 1.200
COMPUTED RAINFALL INTENSITY DATA:
STORM EVENT = 100.00 1-HOUR INTENSITY (INCH/HOUR) = 1.200
SLOPE OF INTENSITY DURATION CURVE = 0.5000
RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
NOTE: CONSIDER ALL CONFLUENCE STREAM COMBINATIONS
FOR ALL DOWNSTREAM ANALYSES

USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL

NO.	HALF- WIDTH (FT)	CROWN TO CROSSFALL (FT)	STREET-CROSSFALL: IN- / OUT-/PARK- SIDE / SIDE/ WAY	CURB HEIGHT (FT)	GUTTER-GEOMETRIES: WIDTH LIP HIKE (FT) (FT) (FT)	MANNING FACTOR (n)
1	30.0	20.0	0.018/0.018/0.020	0.67	2.00 0.0313 0.167	0.0150

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
1. Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
2. (Depth)*(Velocity) Constraint = 6.0 (FT*FT/S)
*SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*

FLOW PROCESS FROM NODE 140.00 TO NODE 141.00 IS CODE = 21

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<

ASSUMED INITIAL SUBAREA UNIFORM
DEVELOPMENT IS COMMERCIAL
TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
INITIAL SUBAREA FLOW-LENGTH (FEET) = 169.00
UPSTREAM ELEVATION (FEET) = 1456.42
DOWNSTREAM ELEVATION (FEET) = 1454.50
ELEVATION DIFFERENCE (FEET) = 1.92
TC = 0.303*[(169.00**3)/(1.92)]**.2 = 5.776
100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.867
COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8879
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF (CFS) = 2.23
TOTAL AREA (ACRES) = 0.65 TOTAL RUNOFF (CFS) = 2.23

FLOW PROCESS FROM NODE 141.00 TO NODE 152.00 IS CODE = 31

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<

ELEVATION DATA: UPSTREAM (FEET) = 1451.16 DOWNSTREAM (FEET) = 1450.16
FLOW LENGTH (FEET) = 334.00 MANNING'S N = 0.012
DEPTH OF FLOW IN 15.0 INCH PIPE IS 8.4 INCHES
PIPE-FLOW VELOCITY (FEET/SEC.) = 3.18
ESTIMATED PIPE DIAMETER (INCH) = 15.00 NUMBER OF PIPES = 1
PIPE-FLOW (CFS) = 2.23
PIPE TRAVEL TIME (MIN.) = 1.75 Tc (MIN.) = 7.53
LONGEST FLOWPATH FROM NODE 140.00 TO NODE 152.00 = 503.00 FEET.

FLOW PROCESS FROM NODE 152.00 TO NODE 152.00 IS CODE = 1

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<

TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION (MIN.) = 7.53
RAINFALL INTENSITY (INCH/HR) = 3.39
TOTAL STREAM AREA (ACRES) = 0.65
PEAK FLOW RATE (CFS) AT CONFLUENCE = 2.23

FLOW PROCESS FROM NODE 150.00 TO NODE 151.00 IS CODE = 21

=====
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====

ASSUMED INITIAL SUBAREA UNIFORM
DEVELOPMENT IS COMMERCIAL

TC = K*[(LENGTH**3)/(ELEVATION CHANGE)]**.2
INITIAL SUBAREA FLOW-LENGTH(FEET) = 286.00
UPSTREAM ELEVATION(FEET) = 1456.04
DOWNSTREAM ELEVATION(FEET) = 1453.67
ELEVATION DIFFERENCE(FEET) = 2.37
TC = 0.303*[(286.00**3)/(2.37)]**.2 = 7.594
.100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 3.373
COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8864
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF(CFS) = 2.39
TOTAL AREA(ACRES) = 0.80 TOTAL RUNOFF(CFS) = 2.39

FLOW PROCESS FROM NODE 151.00 TO NODE 152.00 IS CODE = 31
=====

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
=====

ELEVATION DATA: UPSTREAM(FEET) = 1450.59 DOWNSTREAM(FEET) = 1450.38
FLOW LENGTH(FEET) = 5.00 MANNING'S N = 0.012
ESTIMATED PIPE DIAMETER(INCH) INCREASED TO 12.000
DEPTH OF FLOW IN 12.0 INCH PIPE IS 4.6 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 8.66
ESTIMATED PIPE DIAMETER(INCH) = 12.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 2.39
PIPE TRAVEL TIME(MIN.) = 0.01 Tc(MIN.) = 7.60
LONGEST FLOWPATH FROM NODE 150.00 TO NODE 152.00 = 291.00 FEET.

FLOW PROCESS FROM NODE 152.00 TO NODE 152.00 IS CODE = 1
=====

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<
=====

TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION(MIN.) = 7.60
RAINFALL INTENSITY(INCH/HR) = 3.37
TOTAL STREAM AREA(ACRES) = 0.80
PEAK FLOW RATE(CFS) AT CONFLUENCE = 2.39

** CONFLUENCE DATA **

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)	AREA (ACRE)
1	2.23	7.53	3.388	0.65
2	2.39	7.60	3.371	0.80

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)
1	4.60	7.53	3.388
2	4.61	7.60	3.371

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
PEAK FLOW RATE(CFS) = 4.61 Tc(MIN.) = 7.60
TOTAL AREA(ACRES) = 1.5
LONGEST FLOWPATH FROM NODE 140.00 TO NODE 152.00 = 503.00 FEET.
=====

END OF STUDY SUMMARY:

TOTAL AREA(ACRES) = 1.5 TC(MIN.) = 7.60
PEAK FLOW RATE(CFS) = 4.61

*** PEAK FLOW RATE TABLE ***

	Q(CFS)	Tc(MIN.)
1	4.60	7.53
2	4.61	7.60

=====
END OF RATIONAL METHOD ANALYSIS
=====

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON
RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT
(RCFC&WCD) 1978 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
(Rational Tabling Version 23.0)
Release Date: 07/01/2016 License ID 1435

Analysis prepared by:

***** DESCRIPTION OF STUDY *****
* NANCE STREET INDUSTRIAL DEVELOPMENT *
* PROPOSED CONDITION 100-YEAR *
* NODE 160 *

FILE NAME: W:\3951\P160.DAT
TIME/DATE OF STUDY: 16:47 04/27/2021

USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:

USER SPECIFIED STORM EVENT (YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE (INCH) = 12.00
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.95
2-YEAR, 1-HOUR PRECIPITATION (INCH) = 0.450
100-YEAR, 1-HOUR PRECIPITATION (INCH) = 1.200
COMPUTED RAINFALL INTENSITY DATA:
STORM EVENT = 100.00 1-HOUR INTENSITY (INCH/HOUR) = 1.200
SLOPE OF INTENSITY DURATION CURVE = 0.5000
RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
NOTE: CONSIDER ALL CONFLUENCE STREAM COMBINATIONS
FOR ALL DOWNSTREAM ANALYSES

USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL

NO.	HALF- WIDTH (FT)	CROWN TO CROSSFALL (FT)	STREET-CROSSFALL: IN- / OUT-/PARK- SIDE / SIDE/ WAY	CURB HEIGHT (FT)	GUTTER-GEOMETRIES: WIDTH LIP HIKE (FT) (FT) (FT)	MANNING FACTOR (n)
1	30.0	20.0	0.018/0.018/0.020	0.67	2.00 0.0313 0.167	0.0150

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
1. Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
2. (Depth)*(Velocity) Constraint = 6.0 (FT*FT/S)
*SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*

FLOW PROCESS FROM NODE 160.00 TO NODE 160.00 IS CODE = 22

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====

ASSUMED INITIAL SUBAREA UNIFORM
DEVELOPMENT IS COMMERCIAL
USER SPECIFIED Tc (MIN.) = 5.000
100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.157
COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8887
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF (CFS) = 0.92
TOTAL AREA (ACRES) = 0.25 TOTAL RUNOFF (CFS) = 0.92
=====

END OF STUDY SUMMARY:
TOTAL AREA (ACRES) = 0.2 TC (MIN.) = 5.00
PEAK FLOW RATE (CFS) = 0.92
=====

END OF RATIONAL METHOD ANALYSIS

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM BASED ON
RIVERSIDE COUNTY FLOOD CONTROL & WATER CONSERVATION DISTRICT
(RCFC&WCD) 1978 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
(Rational Tabling Version 23.0)
Release Date: 07/01/2016 License ID 1435

Analysis prepared by:

***** DESCRIPTION OF STUDY *****
* NANCE STREET INDUSTRIAL DEVELOPMENT *
* PROPOSED CONDITION 100-YEAR *
* NODE 170 *

FILE NAME: W:\3951\P170.DAT
TIME/DATE OF STUDY: 10:20 04/28/2021

USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:

USER SPECIFIED STORM EVENT (YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE (INCH) = 12.00
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.95
2-YEAR, 1-HOUR PRECIPITATION (INCH) = 0.450
100-YEAR, 1-HOUR PRECIPITATION (INCH) = 1.200
COMPUTED RAINFALL INTENSITY DATA:
STORM EVENT = 100.00 1-HOUR INTENSITY (INCH/HOUR) = 1.200
SLOPE OF INTENSITY DURATION CURVE = 0.5000
RCFC&WCD HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
NOTE: CONSIDER ALL CONFLUENCE STREAM COMBINATIONS
FOR ALL DOWNSTREAM ANALYSES

USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL

NO.	HALF- WIDTH (FT)	CROWN TO CROSSFALL (FT)	STREET-CROSSFALL: IN- / OUT-/PARK- SIDE / SIDE/ WAY	CURB HEIGHT (FT)	GUTTER-GEOMETRIES: WIDTH LIP HIKE (FT) (FT) (FT)	MANNING FACTOR (n)
1	30.0	20.0	0.018/0.018/0.020	0.67	2.00 0.0313 0.167	0.0150

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
1. Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
2. (Depth)*(Velocity) Constraint = 6.0 (FT*FT/S)
*SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.*

FLOW PROCESS FROM NODE 170.00 TO NODE 170.00 IS CODE = 22

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====

ASSUMED INITIAL SUBAREA UNIFORM
DEVELOPMENT IS COMMERCIAL
USER SPECIFIED Tc (MIN.) = 5.000
100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 4.157
COMMERCIAL DEVELOPMENT RUNOFF COEFFICIENT = .8887
SOIL CLASSIFICATION IS "C"
SUBAREA RUNOFF (CFS) = 0.92
TOTAL AREA (ACRES) = 0.25 TOTAL RUNOFF (CFS) = 0.92
=====


END OF STUDY SUMMARY:
TOTAL AREA (ACRES) = 0.2 TC (MIN.) = 5.00
PEAK FLOW RATE (CFS) = 0.92
=====

END OF RATIONAL METHOD ANALYSIS


APPENDIX C

HYDROLOGY MAPS


HARVEY KNOX BLVD.



VICINITY MAP
N.T.S.



LEGEND	
	PROJECT BOUNDARY
	SUBAREA BOUNDARY
	FLOW PATH
	SUBAREA AREA
	NODE NUMBER




Last Update: 5/17/21
0_3900-3999_3951_3951HYD-EX.dwg

CITY OF PERRIS
PUBLIC WORKS DEPARTMENT
EXISTING CONDITION
HYDROLOGY MAP
HARLEY KNOX
COMMERCE CENTER

PREPARED FOR:
HARLEY KNOX 2021, LLC
11777 SAN VICENTE BLVD., STE. 780
LOS ANGELES, CA 90049
PHONE: (949) 296-7006




Designed by _____	Approved by _____	Date _____
Checked by _____	Public Works Director _____	R.C.E. XXXXX
Designed by _____		
Date _____		
Sheet 1 of 1		Sheets



VICINITY MAP
N.T.S.

LEGEND	
	PROJECT BOUNDARY
	SUBAREA BOUNDARY
	FLOW PATH
	SUBAREA AREA
	NODE NUMBER



Last Update: 12/1/21
0:13900-3999:3999:139991110.DWG

CITY OF PERRIS PUBLIC WORKS DEPARTMENT	
PROPOSED CONDITION HYDROLOGY MAP	
HARLEY KNOX COMMERCE CENTER	
Designed by _____	Approved by _____ Date _____
Checked by _____	Public Works Director _____ R.C.E. XXXXX
Designed by _____	
Checked by _____	
Date _____	Sheet 1 of 1 Sheets

PREPARED FOR:
HARLEY KNOX 2021, LLC
11777 SAN VICENTE BLVD., STE. 780
LOS ANGELES, CA 90049
PHONE: (949) 296-7006



3951/1 OF 1 SHEET

