



**Thienes Engineering, Inc.**  
CIVIL ENGINEERING • LAND SURVEYING

**PROJECT SPECIFIC PRELIMINARY  
WATER QUALITY MANAGEMENT PLAN  
(P-WQMP)**

FOR:

**P20-00004-BLDG1**

**FIRST MARCH LOGISTICS – BUILDING 1**

NATWAR LANE

PERRIS, CALIFORNIA 92571

APNs: 294-180-28, -29, -30 AND PORTION OF -32

PREPARED FOR:

**FIRST INDUSTRIAL REALTY TRUST, INC.**

898 N. PACIFIC COAST HIGHWAY, SUITE 175

EL SEGUNDO, CA 90245

PHONE: (310) 321-3813

CONTACT: MICHAEL GOODWIN

MARCH 11, 2020

JUNE 22, 2020

MARCH 22, 2021

NOVEMBER 16, 2021

JOB NO. 3788

PREPARED BY:

THIENES ENGINEERING, INC.

14349 FIRESTONE BLVD.

LA MIRADA, CALIFORNIA 90638

PHONE: (714) 521-4811

FAX: (714) 521-4173

CONTACT: LUIS PRADO (luisp@thieneseng.com)

**PROJECT SPECIFIC PRELIMINARY  
WATER QUALITY MANAGEMENT PLAN  
(P-WQMP)**

**FOR**

**“FIRST MARCH LOGISTICS – BUILDING 1”**



PREPARED BY LUIS PRADO  
UNDER THE SUPERVISION OF:

---

REINHARD STENZEL  
R.C.E. 56155  
EXP. 12/31/2022

11/16/21  
DATE

# Project Specific Water Quality Management Plan


A Template for Projects located within the **Santa Ana Watershed** Region of Riverside County

**Project Title:** First March Logistics – Building 1

**Development No:** P20-00004

**Design Review/Case No:** P20-00004-Bldg1

APN Numbers: 294-180-028, -029, -030 and 295-300-005, -007



- Preliminary
- Final

**Original Date Prepared:** March 11, 2020

**Revision Date(s):** June 22, 2020  
March 22, 2021  
November 16, 2021

*Prepared for Compliance with  
Regional Board Order No. **R8-2010-0033***

## Contact Information:

### Prepared for:


First Industrial Realty Trust, Inc.  
898 N. Pacific Coast Highway, Suite 175  
El Segundo, CA 90245  
Phone: (310) 321-3813  
Contact: Michael Goodwin

### Prepared by:

Thienes Engineering, Inc.  
14349 Firestone Boulevard  
La Mirada, CA 90638  
(714) 521-4811  
Contact: Luis Prado (luisp@thieneseng.com)  
Job No. 3788

## A Brief Introduction

This Project-Specific WQMP Template for the **Santa Ana Region** has been prepared to help guide you in documenting compliance for your project. Because this document has been designed to specifically document compliance, you will need to utilize the WQMP Guidance Document as your “how-to” manual to help guide you through this process. Both the Template and Guidance Document go hand-in-hand, and will help facilitate a well prepared Project-Specific WQMP. Below is a flowchart for the layout of this Template that will provide the steps required to document compliance.



## OWNER'S CERTIFICATION

This Project-Specific Water Quality Management Plan (WQMP) has been prepared for **First Industrial Realty Trust, Inc.** by **Thienes Engineering, Inc.** for the **First March Logistics – Building 1** project (P20-00004).

This WQMP is intended to comply with the requirements of **City of Perris** for **Ordinance No. 1194** which includes the requirement for the preparation and implementation of a Project-Specific WQMP.

The undersigned, while owning the property/project described in the preceding paragraph, shall be responsible for the implementation and funding of this WQMP and will ensure that this WQMP is amended as appropriate to reflect up-to-date conditions on the site. In addition, the property owner accepts responsibility for interim operation and maintenance of Stormwater BMPs until such time as this responsibility is formally transferred to a subsequent owner. This WQMP will be reviewed with the facility operator, facility supervisors, employees, tenants, maintenance and service contractors, or any other party (or parties) having responsibility for implementing portions of this WQMP. At least one copy of this WQMP will be maintained at the project site or project office in perpetuity. The undersigned is authorized to certify and to approve implementation of this WQMP. The undersigned is aware that implementation of this WQMP is enforceable under **City of Perris Ordinance No. 1194**.

"I, the undersigned, certify under penalty of law that the provisions of this WQMP have been reviewed and accepted and that the WQMP will be transferred to future successors in interest."

\_\_\_\_\_  
Owner's Signature

\_\_\_\_\_  
Date

Michael Goodwin  
Owner's Printed Name

\_\_\_\_\_  
Owner's Title/Position

## PREPARER'S CERTIFICATION

"The selection, sizing and design of stormwater treatment and other stormwater quality and quantity control measures in this plan meet the requirements of Regional Water Quality Control Board Order No. **R8-2010-0033** and any subsequent amendments thereto."

\_\_\_\_\_  
Preparer's Signature

\_\_\_\_\_  
Date

Reinhard Stenzel  
Preparer's Printed Name

Director of Engineering  
Preparer's Title/Position

Preparer's Licensure:

## Table of Contents

Section A: Project and Site Information.....	6
A.1 Maps and Site Plans .....	7
A.2 Identify Receiving Waters .....	8
A.3 Additional Permits/Approvals required for the Project: .....	8
Section B: Optimize Site Utilization (LID Principles) .....	9
Section C: Delineate Drainage Management Areas (DMAs).....	11
Section D: Implement LID BMPs .....	13
D.1 Infiltration Applicability .....	13
D.2 Harvest and Use Assessment.....	14
D.3 Bioretention and Biotreatment Assessment .....	17
D.4 Feasibility Assessment Summaries .....	17
D.5 LID BMP Sizing .....	18
Section E: Alternative Compliance (LID Waiver Program) .....	19
E.1 Identify Pollutants of Concern .....	19
E.2 Stormwater Credits .....	20
E.3 Sizing Criteria.....	21
E.4 Treatment Control BMP Selection .....	21
Section F: Hydromodification .....	22
F.1 Hydrologic Conditions of Concern (HCOC) Analysis.....	22
F.2 HCOC Mitigation.....	23
Section G: Source Control BMPs.....	24
Section H: Construction Plan Checklist .....	26
Section I: Operation, Maintenance and Funding.....	27

## List of Tables

Table A.1 Identification of Receiving Waters.....	8
Table A.2 Other Applicable Permits.....	8
Table C.1 DMA Classifications.....	11
Table C.2 Type 'A', Self-Treating Areas.....	11
Table C.3 Type 'B', Self-Retaining Areas.....	11
Table C.4 Type 'C', Areas that Drain to Self-Retaining Areas.....	12
Table C.5 Type 'D', Areas Draining to BMPs.....	12
Table D.1 Infiltration Feasibility.....	13
Table D.2 LID Prioritization Summary Matrix.....	17
Table D.3 DCV Calculations for LID BMPs.....	18
Table E.1 Potential Pollutants by Land Use Type.....	20
Table E.2 Water Quality Credits.....	20
Table E.3 Treatment Control BMP Sizing.....	21
Table E.4 Treatment Control BMP Selection.....	21
Table F.1 Hydrologic Conditions of Concern Summary.....	22
Table G.1 Permanent and Operational Source Control Measures.....	24
Table H.1 Construction Plan Cross-reference.....	26

## List of Appendices

Appendix 1: Maps and Site Plans.....	28
Appendix 2: Construction Plans.....	29
Appendix 3: Soils Information.....	30
Appendix 4: Historical Site Conditions.....	31
Appendix 5: LID Infeasibility.....	32
Appendix 6: BMP Design Details.....	33
Appendix 7: Hydromodification.....	34
Appendix 8: Source Control.....	35
Appendix 9: O&M.....	36
Appendix 10: Educational Materials.....	37

## Section A: Project and Site Information

PROJECT INFORMATION	
Type of Project:	Light Industrial Warehouse
Planning Area:	Industrial/Business Park
Community Name:	N/A
Development Name:	First March Logistics – Building 1
PROJECT LOCATION	
Latitude & Longitude (GIS): 33.868953, -117.260566	
Project Watershed and Sub-Watershed: Santa Ana River & San Jacinto	
APN(s): 294-180-028, -029, -030 and 295-300-005, -007	
Total Project Area: 19.95 acres	
Map Book and Page No.: Assessor's Map BK294 PG. 18 and BK295 PG. 30	
PROJECT CHARACTERISTICS	
Proposed or Potential Land Use(s)	Light Industrial
Proposed or Potential SIC Code(s)	4225
Area of Existing Impervious Project Footprint (SF)	0
Total Area of <u>proposed</u> Impervious Surfaces within the Project Limits (SF)/or Replacement	797,148 (18.30 acres)
Does the project consist of offsite road improvements?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N
Does the project propose to construct unpaved roads?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
Is the project part of a larger common plan of development (phased project)?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
EXISTING SITE CHARACTERISTICS	
Total area of <u>existing</u> Impervious Surfaces within the project limits (SF)	0
Is the project located within any MSHCP Criteria Cell?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
If so, identify the Cell number:	N/A
Are there any natural hydrologic features on the project site?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
Is a Geotechnical Report attached?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N
If no Geotech. Report, list the NRCS soils type(s) present on the site (A, B, C and/or D)	Infiltration Report Available
What is the Water Quality Design Storm Depth for the project?	0.61

### Project Description:

The project site encompasses approximately 19.95 acres. Proposed improvements to the site include a light industrial warehouse (Building 1) of approximately 419,034 square feet utilized for the transfer and storage of finished goods. There will be truck yards on the east and west sides of the building. Vehicle parking lots will be on the north and south sides of the project. Landscaping will be adjacent to the street and scattered throughout the site. Per the infiltration report, infiltration rates resulted in less than 0.3 inches per hour; therefore, the project proposes to use underground detention systems (StormTech MC-4500 Chambers) and proprietary biotreatment units (Bio Clean Modular Wetlands Systems) to treat runoff produced by the 85<sup>th</sup> percentile storm rainfall depth. In addition, catch basin filters will be provided in order to pre-treat runoff prior to entering the water quality features.

### Existing Site:

Under existing conditions, the site is a vacant lot covered in natural grasses and sparse vegetation. Runoff from the site generally drains from west to east towards Natwar Lane.

### Hydrology:

Flow from the easterly half of the building, the easterly truck yard and the northeasterly parking lot and drive aisle will drain to catch basins located in the easterly truck yard area. Runoff from the southerly parking lot and drive aisle will drain to a catch basin at the southeasterly portion of the parking lot. A proposed storm drain will convey flows from the southerly parking to the north and confluence with runoff from the easterly truck yard. The easterly

storm drain system continues northerly and connects to the proposed 84" public storm drain that wraps around this project/site.

Runoff from the westerly half of the building, the westerly truck yard, the northwesterly parking lot, and the southwesterly drive aisle will drain to catch basins located in the westerly truck yard. A storm drain will convey runoff northerly to the same proposed 84" public storm drain that wraps around this project/site.

This proposed 84" storm drain routes existing offsite run-on, from west of this project and west of the I-215, northerly around the building, and continues easterly towards an interim detention basin. The interim detention basin is used to detain the Q100 from the project site and all offsite flows. An 84" CMP riser/inlet is proposed to route/bubble up stormwater into the northeasterly corner of the interim detention basin. An interim pump is used to discharge residual stormwater, within the 84" pipe, via a parkway drain onto Western Way. A 24" CMP riser/outlet is proposed at the southeasterly corner to slowly discharge stormwater from the interim detention basin. At a specific water surface elevation, see separate "Interim Detention Basin Calculations" report prepared by Thienes Engineering, detained stormwater will outlet via the large/parallel parkway culverts onto Western Way.

In the ultimate condition, the interim detention basin and all interim storm drain apparatuses will be capped/abandoned and/or demolished for the construction of future Building 2. The proposed 84" public storm drain associated with this project will be extended easterly through future Building 2 and connect to the upstream portion of the proposed Perris Valley Channel Lateral "B". This lateral and all tributary areas to it are exempt from HCOCs.

The area fronting Natwar Lane (DMA C, 0.40 acres) comprised mostly of landscaping (and some driveway) will sheet flow offsite. These landscaped areas are considered self-treating areas. Similarly, the pervious area located adjacent to the Freeway (DMA D, 0.60 acres) will be conveyed to the south via a proposed gutter. A portion of the freeway drains toward the site and runoff will also be collected by the proposed gutter. A wall along the southerly neighbor's westerly property line will block offsite run-on and flows will continue southerly, discharging onto Nandina Drive.

## A.1 Maps and Site Plans

When completing your Project-Specific WQMP, include a map of the local vicinity and existing site. In addition, include all grading, drainage, landscape/plant palette and other pertinent construction plans in Appendix 2. At a **minimum**, your WQMP Site Plan should include the following:

- Drainage Management Areas
- Proposed Structural BMPs
- Drainage Path
- Drainage Infrastructure, Inlets, Overflows
- Source Control BMPs
- Buildings, Roof Lines, Downspouts
- Impervious Surfaces
- Standard Labeling

Use your discretion on whether or not you may need to create multiple sheets or can appropriately accommodate these features on one or two sheets. Keep in mind that the Co-Permittee plan reviewer must be able to easily analyze your project utilizing this template and its associated site plans and maps.

## A.2 Identify Receiving Waters

Using Table A.1 below, list in order of upstream to downstream, and the receiving waters that the project site is tributary to. Continue to fill each row with the Receiving Water's 303(d) listed impairments (if any), designated beneficial uses, and proximity, if any, to a RARE beneficial use. Include a map of the receiving waters in Appendix 1.

**Table A.1** Identification of Receiving Waters

Receiving Waters	EPA Approved 303(d) List Impairments	Designated Beneficial Uses	Proximity to RARE Beneficial Use
Perris Valley Storm Drain	None	None	Not classified as a RARE waterbody.
San Jacinto River, Reach 3	None	AGR, GWR, REC1, REC2, WARM, WILD	Not classified as a RARE waterbody.
Canyon Lake (aka San Jacinto River, Reach 2)	Nutrients, Pathogens	MUN, AGR, GWR, REC1, REC2, WARM, WILD	Not classified as a RARE waterbody.
San Jacinto River, Reach 1	None	MUN, AGR, GWR, REC1, REC2, WARM, WILD	Not classified as a RARE waterbody.
Lake Elsinore	Nutrients, Organic Enrichment/Low Dissolved Oxygen, Indicator Bacteria	REC1, REC2, WARM, WILD	Not classified as a RARE waterbody.

## A.3 Additional Permits/Approvals required for the Project:

**Table A.2** Other Applicable Permits

Agency	Permit Required	
State Department of Fish and Game, 1602 Streambed Alteration Agreement	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
State Water Resources Control Board, Clean Water Act (CWA) Section 401 Water Quality Cert.	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
US Army Corps of Engineers, CWA Section 404 Permit	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
US Fish and Wildlife, Endangered Species Act Section 7 Biological Opinion	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
Statewide Construction General Permit Coverage	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N
Statewide Industrial General Permit Coverage (dependent on tenant)	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N
Western Riverside MSHCP Consistency Approval (e.g., JPR, DBESP)	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
Other (please list in the space below as required) City of Perris Grading Permit	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N
Other (please list in the space below as required) City of Perris Building Permit	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N

If yes is answered to any of the questions above, the Co-Permittee may require proof of approval/coverage from those agencies as applicable including documentation of any associated requirements that may affect this Project-Specific WQMP.

## Section B: Optimize Site Utilization (LID Principles)

Review of the information collected in Section 'A' will aid in identifying the principal constraints on site design and selection of LID BMPs as well as opportunities to reduce imperviousness and incorporate LID Principles into the site and landscape design. For example, **constraints** might include impermeable soils, high groundwater, groundwater pollution or contaminated soils, steep slopes, geotechnical instability, high-intensity land use, heavy pedestrian or vehicular traffic, utility locations or safety concerns. **Opportunities** might include existing natural areas, low areas, oddly configured or otherwise unbuildable parcels, easements and landscape amenities including open space and buffers (which can double as locations for bioretention BMPs), and differences in elevation (which can provide hydraulic head). Prepare a brief narrative for each of the site optimization strategies described below. This narrative will help you as you proceed with your LID design and explain your design decisions to others.

The 2010 Santa Ana MS4 Permit further requires that LID Retention BMPs (Infiltration Only or Harvest and Use) be used unless it can be shown that those BMPs are infeasible. Therefore, it is important that your narrative identify and justify if there are any constraints that would prevent the use of those categories of LID BMPs. Similarly, you should also note opportunities that exist which will be utilized during project design. Upon completion of identifying Constraints and Opportunities, include these on your WQMP Site plan in Appendix 1.

### Site Optimization

The following questions are based upon Section 3.2 of the WQMP Guidance Document. Review of the WQMP Guidance Document will help you determine how best to optimize your site and subsequently identify opportunities and/or constraints, and document compliance.

Did you identify and preserve existing drainage patterns? If so, how? If not, why?

- *There are no creeks, wetlands, or riparian habitats nearby.*
- *Existing drainage patterns flow from west to east to an existing 24" storm drain in Natwar Lane that conveys stormwater further east and ultimately into the Perris Valley Storm Drain. Proposed condition drainage patterns mimic pre-development conditions.*

Did you identify and protect existing vegetation? If so, how? If not, why?

- *Not applicable, the entire site was previously disturbed (mass-graded).*
- *Not applicable, there are no sensitive areas.*
- *No applicable, there are no existing trees or vegetation to preserve.*

Did you identify and preserve natural infiltration capacity? If so, how? If not, why?

- *Per the infiltration report, infiltration rates resulted in less than 0.3 inches per hour; therefore, the project proposes to use underground detention systems and proprietary biotreatment units to treat runoff produced by the 85th percentile storm rainfall depth.*

Did you identify and minimize impervious area? If so, how? If not, why?

- *Impervious area on the site has been minimized to City standards.*
- *Due to the nature of the project site (large trucks), substitution of pavement for landscaping is not feasible. The project does not propose overflow parking where substitution of pavement for*

*landscaping would be optimal. Landscaping has been provided wherever applicable and to the maximum extent practicable.*

- *The entire Design Capture Volume (DCV) is handled by the proposed underground detention systems and proprietary biotreatment units. Permeable pavement is not needed to meet the DCV.*

Did you identify and disperse runoff to adjacent pervious areas? If so, how? If not, why?

- *Roof runoff is directed to the underground detention systems and proprietary biotreatment units for treatment.*
- *The site is not on a hillside.*
- *All stormwater runoff will be piped or sheet flow into the underground detention systems and proprietary biotreatment units; therefore, curb-cuts into landscaped areas are not utilized.*

# Section C: Delineate Drainage Management Areas (DMAs)

Utilizing the procedure in Section 3.3 of the WQMP Guidance Document which discusses the methods of delineating and mapping your project site into individual DMAs, complete Table C.1 below to appropriately categorize the types of classification (e.g., Type A, Type B, etc.) per DMA for your project site. Upon completion of this table, this information will then be used to populate and tabulate the corresponding tables for their respective DMA classifications.

**Table C.1 DMA Classifications**

DMA Name or ID	Surface Type(s) <sup>1</sup>	Area (Sq. Ft.)	Area (Acres)	DMA Type
A-1	Roofs/Conc/Asphalt	357,192	8.20	Type D
A-2	Ornamental Landscaping	13,068	0.30	Type D
B-1	Roofs/Conc/Asphalt	439,956	10.10	Type D
B-2	Ornamental Landscaping	15,246	0.35	Type D
C	Ornamental Landscaping	17,424	0.40	Type A
D	Ornamental Landscaping	26,136	0.60	Type A

<sup>1</sup>Reference Table 2-1 in the WQMP Guidance Document to populate this column.

DMA B-1 consists of landscape areas that drain offsite.

**Table C.2 Type 'A', Self-Treating Areas**

DMA Name or ID	Area (Sq. Ft.)	Stabilization Type	Irrigation Type (if any)
C	17,424	California Native Vegetation	Timed Sprinklers
D	26,136	California Native Vegetation	Timed Sprinklers

**Table C.3 Type 'B', Self-Retaining Areas**

Self-Retaining Area				Type 'C' DMAs that are draining to the Self-Retaining Area		
DMA Name/ ID	Post-project surface type	Area (square feet)	Storm Depth (inches)	DMA Name / ID	[C] from Table C.4	Required Retention Depth (inches)
		[A]	[B]		[C]	
n/a	n/a	n/a	n/a	n/a	n/a	n/a

$$[D] = [B] + \frac{[B] \cdot [C]}{[A]}$$

**Table C.4 Type 'C', Areas that Drain to Self-Retaining Areas**

DMA					Receiving Self-Retaining DMA		
DMA Name/ ID	Area (square feet)	Post-project surface type	Runoff factor	Product	DMA name /ID	Area (square feet)	Ratio
	[A]		[B]	[C] = [A] x [B]		[D]	[C]/[D]
n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a

**Table C.5 Type 'D', Areas Draining to BMPs**

DMA Name or ID	BMP Name or ID
A-1	StormTech MC-4500 Chambers & Modular Wetlands System (STC-A & MWS-A )
A-2	StormTech MC-4500 Chambers & Modular Wetlands System (STC-A & MWS-A )
B-1	StormTech MC-4500 Chambers & Modular Wetlands System (STC-B & MWS-B)
B-2	StormTech MC-4500 Chambers & Modular Wetlands System (STC-B & MWS-B )

*Note: More than one drainage management area can drain to a single LID BMP, however, one drainage management area may not drain to more than one BMP.*

## Section D: Implement LID BMPs

### D.1 Infiltration Applicability

Is there an approved downstream ‘Highest and Best Use’ for stormwater runoff (see discussion in Chapter 2.4.4 of the WQMP Guidance Document for further details)?  Y  N

If yes has been checked, Infiltration BMPs shall not be used for the site. If no, continue working through this section to implement your LID BMPs. It is recommended that you contact your Co-Permittee to verify whether or not your project discharges to an approved downstream ‘Highest and Best Use’ feature.

#### Geotechnical Report

A Geotechnical Report or Phase I Environmental Site Assessment may be required by the Copermitttee to confirm present and past site characteristics that may affect the use of Infiltration BMPs. In addition, the Co-Permittee, at their discretion, may not require a geotechnical report for small projects as described in Chapter 2 of the WQMP Guidance Document. If a geotechnical report has been prepared, include it in Appendix 3. In addition, if a Phase I Environmental Site Assessment has been prepared, include it in Appendix 4.

Is this project classified as a small project consistent with the requirements of Chapter 2 of the WQMP Guidance Document?  Y  N

#### Infiltration Feasibility

Table D.1 below is meant to provide a simple means of assessing which DMAs on your site support Infiltration BMPs and is discussed in the WQMP Guidance Document in Chapter 2.4.5. Check the appropriate box for each question and then list affected DMAs as applicable. If additional space is needed, add a row below the corresponding answer.

Table D.1 Infiltration Feasibility

Does the project site...	YES	NO
...have any DMAs with a seasonal high groundwater mark shallower than 10 feet? If Yes, list affected DMAs:		X
...have any DMAs located within 100 feet of a water supply well? If Yes, list affected DMAs:		X
...have any areas identified by the geotechnical report as posing a public safety risk where infiltration of stormwater could have a negative impact? If Yes, list affected DMAs:		X
...have measured in-situ infiltration rates of less than 1.6 inches / hour? If Yes, list affected DMAs: Per the infiltration report, infiltration rates resulted in less than 0.3 inches per hour; therefore, the project proposes to use underground detention systems and proprietary biotreatment units to treat runoff produced by the 85th percentile storm rainfall depth for the entire site.	X	
...have significant cut and/or fill conditions that would preclude in-situ testing of infiltration rates at the final infiltration surface? If Yes, list affected DMAs:		X
...geotechnical report identify other site-specific factors that would preclude effective and safe infiltration? Describe here:		X

If you answered “Yes” to any of the questions above for any DMA, Infiltration BMPs should not be used for those DMAs and you should proceed to the assessment for Harvest and Use below.

## D.2 Harvest and Use Assessment

Please check what applies:

- Reclaimed water will be used for the non-potable water demands for the project.
- Downstream water rights may be impacted by Harvest and Use as approved by the Regional Board (verify with the Copermittee).
- The Design Capture Volume will be addressed using Infiltration Only BMPs. In such a case, Harvest and Use BMPs are still encouraged, but it would not be required if the Design Capture Volume will be infiltrated or evapotranspired.
- None of the above

If any of the above boxes have been checked, Harvest and Use BMPs need not be assessed for the site. If neither of the above criteria applies, follow the steps below to assess the feasibility of irrigation use, toilet use and other non-potable uses (e.g., industrial use).

### Irrigation Use Feasibility

Complete the following steps to determine the feasibility of harvesting stormwater runoff for Irrigation Use BMPs on your site:

Step 1: Identify the total area of irrigated landscape on the site, and the type of landscaping used.

*Total Area of Irrigated Landscape: 1.65 acres*

*Type of Landscaping (Conservation Design or Active Turf): Conservative Design*

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for irrigation use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

*Total Area of Impervious Surfaces: 18.30 acres*

Step 3: Cross reference the Design Storm depth for the project site (see Exhibit A of the WQMP Guidance Document) with the left column of Table 2-3 in Chapter 2 to determine the minimum area of Effective Irrigated Area per Tributary Impervious Area (EIATIA).

*Enter your EIATIA factor: 0.79*

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum irrigated area that would be required.

*Minimum required irrigated area: 14.46 acres*

Step 5: Determine if harvesting stormwater runoff for irrigation use is feasible for the project by comparing the total area of irrigated landscape (Step 1) to the minimum required irrigated area (Step 4).

Minimum required irrigated area (Step 4)	Available Irrigated Landscape (Step 1)
14.46 acres	1.65 acres

## Toilet Use Feasibility

Complete the following steps to determine the feasibility of harvesting stormwater runoff for toilet flushing uses on your site:

Step 1: Identify the projected total number of daily toilet users during the wet season, and account for any periodic shut downs or other lapses in occupancy:

*Projected Number of Daily Toilet Users: 119 (approximate # of parking stalls)*

*Project Type: Light Industrial*

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for toilet use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

*Total Area of Impervious Surfaces: 18.30*

Step 3: Enter the Design Storm depth for the project site (see Exhibit A) into the left column of Table 2-2 in Chapter 2 to determine the minimum number of toilet users per tributary impervious acre (TUTIA).

*Enter your TUTIA factor: 172*

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum number of toilet users that would be required.

*Minimum number of toilet users: 3,148*

Step 5: Determine if harvesting stormwater runoff for toilet flushing use is feasible for the project by comparing the Number of Daily Toilet Users (Step 1) to the minimum required number of toilet users (Step 4).

<b>Minimum required Toilet Users (Step 4)</b>	<b>Projected number of toilet users (Step 1)</b>
3,148	119

### Other Non-Potable Use Feasibility

Are there other non-potable uses for stormwater runoff on the site (e.g. industrial use)? See Chapter 2 of the Guidance for further information. If yes, describe below. If no, write N/A.

N/A

Step 1: Identify the projected average daily non-potable demand, in gallons per day, during the wet season and accounting for any periodic shut downs or other lapses in occupancy or operation.

*Average Daily Demand: N/A*

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for the identified non-potable use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

*Total Area of Impervious Surfaces: N/A*

Step 3: Enter the Design Storm depth for the project site (see Exhibit A) into the left column of Table 2-3 in Chapter 2 to determine the minimum demand for non-potable uses per tributary impervious acre.

*Enter the factor from Table 2-3: N/A*

Step 4: Multiply the unit value obtained from Step 4 by the total of impervious areas from Step 3 to develop the minimum number of gallons per day of non-potable use that would be required.

*Minimum required use: N/A*

Step 5: Determine if harvesting stormwater runoff for other non-potable use is feasible for the project by comparing the Number of Daily Toilet Users (Step 1) to the minimum required number of toilet users (Step 4).

<b>Minimum required non-potable use (Step 4)</b>	<b>Projected average daily use (Step 1)</b>
N/A	N/A

If Irrigation, Toilet and Other Use feasibility anticipated demands are less than the applicable minimum values, Harvest and Use BMPs are not required and you should proceed to utilize LID Bioretention and Biotreatment, unless a site-specific analysis has been completed that demonstrates technical infeasibility as noted in D.3 below.

### D.3 Bioretention and Biotreatment Assessment

Other LID Bioretention and Biotreatment BMPs as described in Chapter 2.4.7 of the WQMP Guidance Document are feasible on nearly all development sites with sufficient advance planning.

Select one of the following:

- LID Bioretention/Biotreatment BMPs will be used for some or all DMAs of the project as noted below in Section D.4 (note the requirements of Section 3.4.2 in the WQMP Guidance Document).
- A site-specific analysis demonstrating the technical infeasibility of all LID BMPs has been performed and is included in Appendix 5. If you plan to submit an analysis demonstrating the technical infeasibility of LID BMPs, request a pre-submittal meeting with the Copermittee to discuss this option. Proceed to Section E to document your alternative compliance measures.

### D.4 Feasibility Assessment Summaries

From the Infiltration, Harvest and Use, Bioretention and Biotreatment Sections above, complete Table D.2 below to summarize which LID BMPs are technically feasible, and which are not, based upon the established hierarchy.

Table D.2 LID Prioritization Summary Matrix

DMA Name/ID	LID BMP Hierarchy				Alternative Compliance (Modular Wetlands Systems)
	1. Infiltration	2. Harvest and use	3. Bioretention	4. Biotreatment	
A-1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
A-2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
B-1	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
B-2	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

For those DMAs where LID BMPs are not feasible, provide a brief narrative below summarizing why they are not feasible, include your technical infeasibility criteria in Appendix 5, and proceed to Section E below to document Alternative Compliance measures for those DMAs. Recall that each proposed DMA must pass through the LID BMP hierarchy before alternative compliance measures may be considered.

## D.5 LID BMP Sizing

Each LID BMP must be designed to ensure that the Design Capture Volume will be addressed by the selected BMPs. First, calculate the Design Capture Volume for each LID BMP using the  $V_{BMP}$  worksheet in Appendix F of the LID BMP Design Handbook. Second, design the LID BMP to meet the required  $V_{BMP}$  using a method approved by the Copermittee. Utilize the worksheets found in the LID BMP Design Handbook or consult with your Copermittee to assist you in correctly sizing your LID BMPs. Complete Table D.3 below to document the Design Capture Volume and the Proposed Volume for each LID BMP. Provide the completed design procedure sheets for each LID BMP in Appendix 6. You may add additional rows to the table below as needed.

**Table D.3** DCV Calculations for LID BMPs

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Impervious Fraction, $I_f$	DMA Runoff Factor	DMA Areas x Runoff Factor	Design Storm Depth (in)	Design Capture Volume, $V_{BMP}$ (cubic feet)	Proposed Volume on Plans (cubic feet)
	[A]		[B]	[C]	[A] x [C]			
A-1	357,192	Roofs/Conc/Asphalt	1.00	0.89	318,615.3	0.61	16196.3	16,415
A-2	13,068	Ornamental Landscaping	0.10	0.11	1,443.5	0.61	73.4	
B-1	439,956	Roofs/Conc/Asphalt	1.00	0.89	392,440.8	0.61	19949.1	20,172
B-2	15,246	Ornamental Landscaping	0.10	0.11	1,684.0	0.61	85.6	
	370,260				714,184	0.61	36,304	36,587

[B], [C] is obtained as described in Section 2.3.1 of the WQMP Guidance Document

[E] is obtained from Exhibit A in the WQMP Guidance Document

[G] is obtained from a design procedure sheet, such as in LID BMP Design Handbook and placed in Appendix 6

## Section E: Alternative Compliance (LID Waiver Program)

LID BMPs are expected to be feasible on virtually all projects. Where LID BMPs have been demonstrated to be infeasible as documented in Section D, other Treatment Control BMPs must be used (subject to LID waiver approval by the Copermittee). Check one of the following Boxes:

LID Principles and LID BMPs have been incorporated into the site design to fully address all Drainage Management Areas. No alternative compliance measures are required for this project and thus this Section is not required to be completed.

- Or -

The following Drainage Management Areas are unable to be addressed using LID BMPs. A site-specific analysis demonstrating technical infeasibility of LID BMPs has been approved by the Co-Permittee and included in Appendix 5. Additionally, no downstream regional and/or sub-regional LID BMPs exist or are available for use by the project. The following alternative compliance measures on the following pages are being implemented to ensure that any pollutant loads expected to be discharged by not incorporating LID BMPs, are fully mitigated.

### E.1 Identify Pollutants of Concern

Utilizing Table A.1 from Section A above which noted your project's receiving waters and their associated EPA approved 303(d) listed impairments, cross reference this information with that of your selected Priority Development Project Category in Table E.1 below. If the identified General Pollutant Categories are the same as those listed for your receiving waters, then these will be your Pollutants of Concern and the appropriate box or boxes will be checked on the last row. The purpose of this is to document compliance and to help you appropriately plan for mitigating your Pollutants of Concern in lieu of implementing LID BMPs.

**Table E.1 Potential Pollutants by Land Use Type**

Priority Project Categories and/or Project Features (check those that apply)	General Pollutant Categories							
	Bacterial Indicators	Metals	Nutrients	Pesticides	Toxic Organic Compounds	Sediments	Trash & Debris	Oil & Grease
<input type="checkbox"/> Detached Residential Development	P	N	P	P	N	P	P	P
<input type="checkbox"/> Attached Residential Development	P	N	P	P	N	P	P	P <sup>(2)</sup>
<input checked="" type="checkbox"/> Commercial/Industrial Development	P <sup>(3)</sup>	P	P <sup>(1)</sup>	P <sup>(1)</sup>	P <sup>(5)</sup>	P <sup>(1)</sup>	P	P
<input type="checkbox"/> Automotive Repair Shops	N	P	N	N	P <sup>(4, 5)</sup>	N	P	P
<input type="checkbox"/> Restaurants (>5,000 ft <sup>2</sup> )	P	N	N	N	N	N	P	P
<input type="checkbox"/> Hillside Development (>5,000 ft <sup>2</sup> )	P	N	P	P	N	P	P	P
<input checked="" type="checkbox"/> Parking Lots (>5,000 ft <sup>2</sup> )	P <sup>(6)</sup>	P	P <sup>(1)</sup>	P <sup>(1)</sup>	P <sup>(4)</sup>	P <sup>(1)</sup>	P	P
<input type="checkbox"/> Retail Gasoline Outlets	N	P	N	N	P	N	P	P
<b>Project Priority Pollutant(s) of Concern</b>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

P = Potential

N = Not Potential

<sup>(1)</sup> A potential Pollutant if non-native landscaping exists or is proposed onsite; otherwise not expected

<sup>(2)</sup> A potential Pollutant if the project includes uncovered parking areas; otherwise not expected

<sup>(3)</sup> A potential Pollutant is land use involving animal waste

<sup>(4)</sup> Specifically petroleum hydrocarbons

<sup>(5)</sup> Specifically solvents

<sup>(6)</sup> Bacterial indicators are routinely detected in pavement runoff

## E.2 Stormwater Credits

Projects that cannot implement LID BMPs but nevertheless implement smart growth principles are potentially eligible for Stormwater Credits. Utilize Table 3-8 within the WQMP Guidance Document to identify your Project Category and its associated Water Quality Credit. If not applicable, write N/A.

**Table E.2 Water Quality Credits**

Qualifying Project Categories	Credit Percentage <sup>2</sup>
N/A	
<b>Total Credit Percentage<sup>1</sup></b>	

<sup>1</sup>Cannot Exceed 50%

<sup>2</sup>Obtain corresponding data from Table 3-8 in the WQMP Guidance Document

## E.3 Sizing Criteria

After you appropriately considered Stormwater Credits for your project, utilize Table E.3 below to appropriately size them to the DCV, or Design Flow Rate, as applicable. Please reference Chapter 3.5.2 of the WQMP Guidance Document for further information.

Table E.3 Treatment Control BMP Sizing

DMA Type/ ID	DMA Area (square feet)	Post- Project Surface Type	Effective Imp Fraction, $I_f$	DMA Runoff Factor	DMA Area x Runoff Factor				
	[A]		[B]	[C]	[A] x [C]				
N/A	N/A	N/A	N/A	N/A	N/A	Design Storm Depth (in)	Minimum Design Capture Volume (cubic feet)	Total Storm Water Credit % Reduction	Proposed Volume or Flow on Plans (cubic feet or cfs)

[B], [C] is obtained as described in Section 2.3.1 from the WQMP Guidance Document

[E] is obtained from Exhibit A in the WQMP Guidance Document

[G] is for Flow-Based Treatment Control BMPs [G] = 43,560, for Volume-Based Control Treatment BMPs, [G] = 12

[H] is from the Total Credit Percentage as Calculated from Table E.2 above

[I] as obtained from a design procedure sheet from the BMP manufacturer and should be included in Appendix 6

## E.4 Treatment Control BMP Selection

Treatment Control BMPs typically provide proprietary treatment mechanisms to treat potential pollutants in runoff, but do not sustain significant biological processes. Treatment Control BMPs must have a removal efficiency of a medium or high effectiveness as quantified below:

- **High:** equal to or greater than 80% removal efficiency
- **Medium:** between 40% and 80% removal efficiency

Such removal efficiency documentation (e.g., studies, reports, etc.) as further discussed in Chapter 3.5.2 of the WQMP Guidance Document, must be included in Appendix 6. In addition, ensure that proposed Treatment Control BMPs are properly identified on the WQMP Site Plan in Appendix 1.

Table E.4 Treatment Control BMP Selection

Selected Treatment Control BMP Name or ID <sup>1</sup>	Priority Pollutant(s) of Concern to Mitigate <sup>2</sup>	Removal Efficiency Percentage <sup>3</sup>
Modular Wetlands System	Metals	38%-69%
Modular Wetlands System	Trash & Debris/TSS	85%
Modular Wetlands System	Oil & Grease	95%

<sup>1</sup> Treatment Control BMPs must not be constructed within Receiving Waters. In addition, a proposed Treatment Control BMP may be listed more than once if they possess more than one qualifying pollutant removal efficiency.

<sup>2</sup> Cross Reference Table E.1 above to populate this column.

<sup>3</sup> As documented in a Co-Permittee Approved Study and provided in Appendix 6.

## Section F: Hydromodification

### F.1 Hydrologic Conditions of Concern (HCOC) Analysis

Once you have determined that the LID design is adequate to address water quality requirements, you will need to assess if the proposed LID Design may still create a HCOC. Review Chapters 2 and 3 (including Figure 3-7) of the WQMP Guidance Document to determine if your project must mitigate for Hydromodification impacts. If your project meets one of the following criteria which will be indicated by the check boxes below, you do not need to address Hydromodification at this time. However, if the project does not qualify for Exemptions 1, 2 or 3, then additional measures must be added to the design to comply with HCOC criteria. This is discussed in further detail below in Section F.2.

**HCOC EXEMPTION 1:** The Priority Development Project disturbs less than one acre. The Copermitttee has the discretion to require a Project-Specific WQMP to address HCOCs on projects less than one acre on a case by case basis. The disturbed area calculation should include all disturbances associated with larger common plans of development.

Does the project qualify for this HCOC Exemption?  Y  N

If Yes, HCOC criteria do not apply.

**HCOC EXEMPTION 2:** The volume and time of concentration<sup>1</sup> of storm water runoff for the post-development condition is not significantly different from the pre-development condition for a 2-year return frequency storm (a difference of 5% or less is considered insignificant) using one of the following methods to calculate:

- Riverside County Hydrology Manual
- Technical Release 55 (TR-55): Urban Hydrology for Small Watersheds (NRCS 1986), or derivatives thereof, such as the Santa Barbara Urban Hydrograph Method
- Other methods acceptable to the Co-Permittee

Does the project qualify for this HCOC Exemption?  Y  N

If yes, report results in Table F.1 below and provide your substantiated hydrologic analysis in Appendix 7.

**Table F.1** Hydrologic Conditions of Concern Summary

	2 year – 24 hour		
	Pre-condition	Post-condition	% Difference
<b>Time of Concentration (min)</b>	N/A	N/A	N/A
<b>Volume (Cubic Feet)</b>	N/A	N/A	N/A

<sup>1</sup> Time of concentration is defined as the time after the beginning of the rainfall when all portions of the drainage basin are contributing to flow at the outlet.

**HCOC EXEMPTION 3:** All downstream conveyance channels to an adequate sump (for example, Prado Dam, Lake Elsinore, Canyon Lake, Santa Ana River, or other lake, reservoir or naturally erosion resistant feature) that will receive runoff from the project are engineered and regularly maintained to ensure design flow capacity; no sensitive stream habitat areas will be adversely affected; or are not identified on the Co-Permittees Hydromodification Sensitivity Maps.

Does the project qualify for this HCOC Exemption?       Y     N

If Yes, HCOC criteria do not apply and note below which adequate sump applies to this HCOC qualifier:

## F.2 HCOC Mitigation

If none of the above HCOC Exemption Criteria are applicable, HCOC criteria is considered mitigated if they meet one of the following conditions:

- a. Additional LID BMPS are implemented onsite or offsite to mitigate potential erosion or habitat impacts as a result of HCOCs. This can be conducted by an evaluation of site-specific conditions utilizing accepted professional methodologies published by entities such as the California Stormwater Quality Association (CASQA), the Southern California Coastal Water Research Project (SCCRWP), or other Co-Permittee approved methodologies for site-specific HCOC analysis.
- b. The project is developed consistent with an approved Watershed Action Plan that addresses HCOC in Receiving Waters.
- c. Mimicking the pre-development hydrograph with the post-development hydrograph, for a 2-year return frequency storm. Generally, the hydrologic conditions of concern are not significant, if the post-development hydrograph is no more than 10% greater than pre-development hydrograph. In cases where excess volume cannot be infiltrated or captured and reused, discharge from the site must be limited to a flow rate no greater than 110% of the pre-development 2-year peak flow.
- d. None of the above.

**All pertinent documentation used in analysis of the items a, b or c can be found in Appendix 7.**

**The project site is located within the exempted HCOC area, as presented in the April 20, 2017 approved WAP/HCOC document. Refer to HCOC map provided in Appendix 7. This project will route stormwater runoff easterly into an interim detention basin that will outlet into an interim proposed public storm drain that traverse southerly through Western Way and makes its way towards the Perris Valley Storm Drain. In the ultimate condition, the northerly 84" public storm drain will have been extended easterly and the project's stormwater will tie directly into the future Perris Valley Channel Lateral "B".**

## Section G: Source Control BMPs

Source control BMPs include permanent, structural features that may be required in your project plans — such as roofs over and berms around trash and recycling areas — and Operational BMPs, such as regular sweeping and “housekeeping”, that must be implemented by the site’s occupant or user. The MEP standard typically requires both types of BMPs. In general, Operational BMPs cannot be substituted for a feasible and effective permanent BMP. Using the Pollutant Sources/Source Control Checklist in Appendix 8, review the following procedure to specify Source Control BMPs for your site:

1. **Identify Pollutant Sources:** Review Column 1 in the Pollutant Sources/Source Control Checklist. Check off the potential sources of Pollutants that apply to your site.
2. **Note Locations on Project-Specific WQMP Exhibit:** Note the corresponding requirements listed in Column 2 of the Pollutant Sources/Source Control Checklist. Show the location of each Pollutant source and each permanent Source Control BMP in your Project-Specific WQMP Exhibit located in Appendix 1.
3. **Prepare a Table and Narrative:** Check off the corresponding requirements listed in Column 3 in the Pollutant Sources/Source Control Checklist. In the left column of Table G.1 below, list each potential source of runoff Pollutants on your site (from those that you checked in the Pollutant Sources/Source Control Checklist). In the middle column, list the corresponding permanent, Structural Source Control BMPs (from Columns 2 and 3 of the Pollutant Sources/Source Control Checklist) used to prevent Pollutants from entering runoff. **Add additional narrative** in this column that explains any special features, materials or methods of construction that will be used to implement these permanent, Structural Source Control BMPs.
4. **Identify Operational Source Control BMPs:** To complete your table, refer once again to the Pollutant Sources/Source Control Checklist. List in the right column of your table the Operational BMPs that should be implemented as long as the anticipated activities continue at the site. Copermittee stormwater ordinances require that applicable Source Control BMPs be implemented; the same BMPs may also be required as a condition of a use permit or other revocable Discretionary Approval for use of the site.

**Table G.1** Permanent and Operational Source Control Measures

Potential Sources of Runoff pollutants	Permanent Structural Source Control BMPs	Operational Source Control BMPs
A. On-site storm drain inlets	<ul style="list-style-type: none"> <li>• Mark all inlets with the words “Only Rain Down the Storm Drain” or similar.</li> </ul>	<ul style="list-style-type: none"> <li>• Maintain and periodically repaint or replace inlet markings annually.</li> <li>• Provide stormwater pollution prevention information to new site owners, lessees, or operators upon occupancy and annually thereafter.</li> <li>• See CASQA fact sheet SC-44 for “Drainage System Maintenance,” included in Appendix of this document.</li> <li>• Include the following lease agreements: “Tenant shall not allow anyone to discharge anything to storm drain or to store or deposit materials so as to create a potential discharge to storm drains.”</li> </ul>

Potential Sources of Runoff pollutants	Permanent Structural Source Control BMPs	Operational Source Control BMPs
<b>B.</b> Interior floor drains and elevator shaft sump pumps	<ul style="list-style-type: none"> <li>Interior floor drains and elevator shaft sump pumps will be plumbed to sanitary sewer.</li> </ul>	<ul style="list-style-type: none"> <li>Inspect and maintain drains semi-annually to prevent blockages and overflow.</li> </ul>
<b>D2.</b> Landscape / Outdoor Pesticide Use	<ul style="list-style-type: none"> <li>Landscape plans will minimize irrigation and runoff, to promote surface infiltration where appropriate, and to minimize the use of fertilizers and pesticides that can contribute to stormwater pollution.</li> <li>Pest-resistant plans will be used adjacent to hardscape.</li> <li>The landscape plans will consider plants appropriate to the site soils, slopes, climate, sun, wind, rain, land use, air movement, ecological consistency, and plant interactions.</li> </ul>	<ul style="list-style-type: none"> <li>Maintain landscaping only using minimum pesticides, when needed.</li> <li>See Appendix 10 for "Landscape and Gardening" brochure by RCFlood.</li> <li>Provide Integrated Pest Management (IPM) information to new owners, lessees and operators upon occupancy and annually thereafter. IPM is an effective and environmentally sensitive approach to pest management.</li> </ul>
<b>G.</b> Refuse Areas	<ul style="list-style-type: none"> <li>Site refuse will be handled by contractor on a weekly basis.</li> <li>Signs will be posted on or near dumpsters with the words "Do not dump hazardous materials here" or similar.</li> </ul>	<ul style="list-style-type: none"> <li>A minimum of two receptacles will be provided and located indoors. Receptacles are to be inspected daily and repairs or replacements to leaky receptacles will be completed immediately. Receptacles are to remain covered when not in use. Dumping of liquid or hazardous wastes is prohibited. A "no hazardous materials" sign will be posted. Spills will be cleaned immediately upon discovery. Spill control materials will be available onsite. See Appendix 10 for CASQA fact sheet SC-34 for "Waste Handling and Disposal."</li> </ul>
<b>H.</b> Industrial processes	<ul style="list-style-type: none"> <li>All process activities to be performed indoors. No processes to drain to exterior or to storm drain system.</li> </ul>	<ul style="list-style-type: none"> <li>See Appendix 10 for CASQA fact sheet SC-10 for "Non-Stormwater Discharges"</li> </ul>
<b>M.</b> Loading Docks	<ul style="list-style-type: none"> <li>Spills will be cleaned up immediately and disposed of properly.</li> </ul>	<ul style="list-style-type: none"> <li>Move loaded and unloaded items indoors as soon as possible.</li> <li>See Appendix 10 for CASQA fact sheet SC-30 for "Outdoor Loading and Unloading"</li> </ul>
<b>O.</b> Miscellaneous Drain or Wash Water or Other Sources	<ul style="list-style-type: none"> <li>A drainage sumps on-site shall feature a sediment sump to reduce the quantity of sediment in pumped water.</li> </ul>	
<b>P.</b> Plazas, sidewalks, and parking lots		<ul style="list-style-type: none"> <li>Sweep plazas, sidewalks, and parking lots monthly to prevent accumulation of litter and debris. Collect debris from pressure washing to prevent entry into the storm drain system. Collect washwater containing any cleaning agent or degreaser and discharge to the sanitary sewer not to a storm drain.</li> </ul>

## Section H: Construction Plan Checklist

Populate Table H.1 below to assist the plan checker in an expeditious review of your project. The first two columns will contain information that was prepared in previous steps, while the last column will be populated with the corresponding plan sheets. This table is to be completed with the submittal of your final Project-Specific WQMP.

**Table H.1 Construction Plan Cross-reference**

BMP No. or ID	BMP Identifier and Description	Corresponding Plan Sheet(s)	Latitude	Longitude
A	On-site storm drain inlets	TBD	---	---
B	Interior floor drains and elevator shaft sump pumps	TBD	---	---
D2	Landscape / Outdoor Pesticide Use	TBD	---	---
G	Refuse Areas	TBD	---	---
H	Industrial processes	TBD	---	---
M	Loading Docks	TBD	---	---
P	Plazas, sidewalks, and parking lots	TBD	---	---
MWS-A	Modular Wetlands System	TBD	---	---
STC-A	Underground Detention	TBD	---	---
MWS-B	Modular Wetlands System	TBD	---	---
STC-B	Underground Detention	TBD	---	---

Note that the updated table — or Construction Plan WQMP Checklist — is **only a reference tool** to facilitate an easy comparison of the construction plans to your Project-Specific WQMP. Co-Permittee staff can advise you regarding the process required to propose changes to the approved Project-Specific WQMP.

**This section will be completed and addressed at the time of the final WQMP Submittal.**

## Section I: Operation, Maintenance and Funding

The Copermittee will periodically verify that Stormwater BMPs on your site are maintained and continue to operate as designed. To make this possible, your Copermittee will require that you include in Appendix 9 of this Project-Specific WQMP:

1. A means to finance and implement facility maintenance in perpetuity, including replacement cost.
2. Acceptance of responsibility for maintenance from the time the BMPs are constructed until responsibility for operation and maintenance is legally transferred. A warranty covering a period following construction may also be required.
3. An outline of general maintenance requirements for the Stormwater BMPs you have selected.
4. Figures delineating and designating pervious and impervious areas, location, and type of Stormwater BMP, and tables of pervious and impervious areas served by each facility. Geo-locating the BMPs using a coordinate system of latitude and longitude is recommended to help facilitate a future statewide database system.
5. A separate list and location of self-retaining areas or areas addressed by LID Principles that do not require specialized O&M or inspections but will require typical landscape maintenance as noted in Chapter 5, pages 85-86, in the WQMP Guidance. Include a brief description of typical landscape maintenance for these areas.

Your local Co-Permittee will also require that you prepare and submit a detailed Stormwater BMP Operation and Maintenance Plan that sets forth a maintenance schedule for each of the Stormwater BMPs built on your site. An agreement assigning responsibility for maintenance and providing for inspections and certification may also be required.

Details of these requirements and instructions for preparing a Stormwater BMP Operation and Maintenance Plan are in Chapter 5 of the WQMP Guidance Document.

**Maintenance Mechanism:** City of Perris:  
Covenant and Agreement  
Water Quality Management Plan and Urban Runoff BMP Transfer, Access and Maintenance Agreement

Will the proposed BMPs be maintained by a Home Owners' Association (HOA) or Property Owners Association (POA)?

Y       N

Include your Operation and Maintenance Plan and Maintenance Mechanism in Appendix 9. Additionally, include all pertinent forms of educational materials for those personnel that will be maintaining the proposed BMPs within this Project-Specific WQMP in Appendix 10.

This section will be completed and addressed at the time of the final WQMP Submittal.

# Appendix 1: Maps and Site Plans

*Location Map, WQMP Site Plan and Receiving Waters Map*


**Legend**  
↓ PROJECT SITE




LAKE PERRIS




**VICINITY MAP**  
FIRST MARCH LOGISTICS - BUILDING 1





VICINITY MAP  
N.T.S.



**LEGEND**

- 1 LOADING/UNLOADING TRUCK DOCKS
- 2 EDUCATIONAL MATERIAL
- 3 STORM DRAIN STENCIL
- 4 MC-4500 STORMTECH CHAMBERS W/ IMPERMEABLE LINER
- 5 TRASH ENCLOSURE
- 6 PARKING LOT MAINTENANCE (SWEEPING)
- 7 PROPRIETARY BIOTREATMENT UNIT
- 8 DRAIN INSERT(S)
- 9 SUMP PUMP
- 10 SELF-TREATING LANDSCAPE
- 11 DIVERSION STRUCTURES

**NOTE:**

- RD ROOF DRAIN
- BOUNDARY
- SUBAREAS
- SURFACE FLOW LINE
- SD FLOW LINE

**DMA A** (Yellow)

**DMA B** (Orange)

**DMA C** (Green)

**DMA D** (Blue)


**LANDSCAPE AREA** (Dotted pattern)

**STORM DRAIN NOTES:**


- MAIN STORM DRAIN
- INBOUND TO CHAMBERS
- OUTBOUND FROM CHAMBERS



SAMPLE STORM DRAIN STENCIL



TRASH ENCLOSURE DETAIL




ROOF DRAIN/DOWNSPOUT DETAIL (TYP.)


DMA Name or ID	Surface Type(s)	Area (Sq. Ft.)	Area (Acres)	DMA Type
A-1	Roofs/Conc/Asphalt	357,192	8.20	Type D
A-2	Ornamental Landscaping	13,068	0.30	Type D
B-1	Roofs/Conc/Asphalt	439,956	10.10	Type D
B-2	Ornamental Landscaping	15,246	0.35	Type D
C	Ornamental Landscaping	17,424	0.40	Type A
D	Ornamental Landscaping	26,136	0.60	Type A

**SUMMARY TABLE**


DMA	AREA (ACRES)	DCV (CF)	MODULAR WETLANDS SYSTEM (MWS)		MC-4500 STORMTECH CHAMBERS		TOTAL VOLUME PROVIDED (CF)	CHECK	
			MWS MODEL	LINEAR STATIC CAPACITY (CF)	DETENTION REQUIRED (CF)	DETENTION PROVIDED (CF)			# OF CHAMBERS
A	8.50	16,270	MWS-L-4-21	144	16,126	16,271	79	16,415	OK
B	10.45	20,035	MWS-L-8-12	187	19,848	19,985	98	20,172	OK
<b>TOTAL</b>	<b>18.95</b>	<b>36,305</b>		<b>331</b>	<b>35,974</b>	<b>36,256</b>	<b>177</b>	<b>36,587</b>	




DIVERSION MANHOLE 'A'  
N.T.S.



DIVERSION MANHOLE 'B'  
N.T.S.



SELF-TREATING DETAIL (TYP.)  
GRASS AREAS SHEET FLOWING OFFSITE



SCALE: 1"=60'

**PREPARED FOR:**  
FIRST INDUSTRIAL REALTY TRUST, INC.  
898 N. PACIFIC COAST HIGHWAY STE. 175  
EL SEGUNDO, CA 90245  
PHONE: (310) 321-3813

**PREPARED BY:**  
**Tai** Thienes Engineering, Inc.  
CIVIL ENGINEERING - LAND SURVEYING  
14340 FIRESTONE BOULEVARD  
LA BREA, CALIFORNIA 90639  
PH: (714) 521-4811 FAX: (714) 521-4753

**CITY OF PERRIS**  
PUBLIC WORKS DEPARTMENT

**POST-CONSTRUCTION BMP SITE PLAN**  
**FIRST MARCH LOGISTICS BUILDING 1**  
**FIR FREEWAY 215 AND NATWAR LANE, P20-00004-BLDG1**

Designed by: \_\_\_\_\_ Date: \_\_\_\_\_  
Checked by: \_\_\_\_\_ Date: \_\_\_\_\_  
Designed by: \_\_\_\_\_ Date: \_\_\_\_\_  
Checked by: \_\_\_\_\_ Date: \_\_\_\_\_


Approved by: \_\_\_\_\_ Date: \_\_\_\_\_  
Public Works Director: R.C.E.

Sheet **1** of **2** Sheets

3788/1 OF 2 SHEET

Last Update: 11/16/21  
Q:\3700-3790\3788\3788BMPSTEMAP.dwg





**EARTHWORK BALANCE CALCULATIONS**

PROJECT:	CONCEPTUAL GP (LEVEL FLOOR)	QUANTITY
JOB#	215 FWY & NATWAR LANE	JN 3788
	BLDG AREA	415,470
K.	SITE AREA	945,396
L.	SUBSIDENCE FACTOR:	0.163
M.	SHRINKAGE FACTOR:	13.0
N.	SITE STRIPPING FACTOR:	0.10
O.	OVEREXCAVATION:	46,163.33
A.	CALCULATED CUT:	37,045
B.	TOTAL SPOILS	12,730
	SPOILS FROM BASIN	17,996
	ADDITIONAL CUT (FLOOR SLAB)	1,282
C.	TOTAL CUT: (A+B)	69,053
D.	CALCULATED FILL:	44,884
E.	LIGHT PAVING FILL:	
F.	SUBSIDENCE: (LxK)/27=	5,690
G.	SHRINKAGE: (M/100)C=	8,977
H.	SITE STRIPPING	3,501
I.	OVEREXCAVATION SHRINKAGE	6,001
J.	TOTAL FILL: (D+E+F+G+H)=	69,054
K.	TOTAL (IMPORT) OR EXPORT:	(0)
	SITE ADJUSTMENT	(0.00)

**BUILDING 1**  
419,034 SF

1514.44 FF  
1513.86 PAD

**I-215 FREEWAY**

**NATWAR LANE**

**36 DOCK DOORS**

**7 DOCK DOORS**


**CITY OF PERRIS**  
PUBLIC WORKS DEPARTMENT

**CONCEPTUAL GRADING PLAN**

**FIRST MARCH LOGISTICS**  
**NATWAR LANE**



Designed by _____	Approved by _____	Date _____
Checked by _____	Public Works Director	R.C.E. XXXXX
Designed by _____		
Checked by _____		

Sheet **1** of **8** Sheets




**PREPARED FOR**

FIRST INDUSTRY REALTY TRUST, INC.  
898 N. PACIFIC COAST HIGHWAY STE. 175  
EL SEGUNDO, CA 90245  
PHONE: (310) 321-3813  
EMAIL: MPLO@FIRSTINDUSTRIAL.COM



# Appendix 2: Construction Plans

*Grading and Drainage Plans*



**EARTHWORK BALANCE CALCULATIONS**

PROJECT:	CONCEPTUAL GP (LEVEL FLOOR)	QUANTITY
JOB#	215 FWY & NATWAR LANE	JN 3788
	BLDG AREA	415,470
	K. SITE AREA	945,396
	L. SUBSIDIANCE FACTOR:	0.163
	M. SHRINKAGE FACTOR:	13.0
	N. SITE STRIPPING FACTOR:	0.10
	O. OVEREXCAVATION:	46,163.33
	A. CALCULATED CUT:	37,045
	B. TOTAL SPOILS	12,730
	SPOILS FROM BASIN	17,996
	ADDITIONAL CUT (FLOOR SLAB)	1,282
	C. TOTAL CUT: (A+B)	69,053
	D. CALCULATED FILL:	44,884
	E. LIGHT PAVING FILL:	
	F. SUBSIDIANCE: (LxK)/27=	5,690
	G. SHRINKAGE: (M/100)C=	8,977
	H. SITE STRIPPING	3,501
	I. OVEREXCAVATION SHRINKAGE	6,001
	J. TOTAL FILL: (D+E+F+G+H)=	69,054
	K. TOTAL (IMPORT) OR EXPORT:	(0)
	SITE ADJUSTMENT	(0.00)

**BUILDING 1**  
419,034 SF

1514.44 FF  
1513.86 PAD

**I-215 FREEWAY**

**NATWAR LANE**

**36 DOCK DOORS**

**7 DOCK DOORS**

**CITY OF PERRIS**  
PUBLIC WORKS DEPARTMENT


**CONCEPTUAL GRADING PLAN**

**FIRST MARCH LOGISTICS**  
NATWAR LANE



Designed by \_\_\_\_\_ Date \_\_\_\_\_  
Checked by \_\_\_\_\_ Date \_\_\_\_\_  
Designed by \_\_\_\_\_ Date \_\_\_\_\_  
Checked by \_\_\_\_\_ Date \_\_\_\_\_


Approved by \_\_\_\_\_ Date \_\_\_\_\_  
Public Works Director R.C.E. XXXXX

Sheet **1** of **8** Sheets



PREPARED FOR  
**FIRST INDUSTRY REALTY TRUST, INC.**  
898 N. PACIFIC COAST HIGHWAY STE. 175  
EL SEGUNDO, CA 90245  
PHONE: (310) 321-3813  
EMAIL: MPLO@FIRSTINDUSTRIAL.COM





PROPOSED WATER SURFACE ELEVATION = 1509.40  
 MAXIMUM PONDING DEPTH = 7.50'  
 TOTAL PONDING VOLUME = 1339696 CF. / 30.755 AC. FT.




POUNDING DEPTH (FT.)	LEGEND
7.40	[Blue Box]
5.61	[Light Blue Box]
3.74	[Lightest Blue Box]
1.87	[White Box]

WATER SURFACE ELEVATION (WSE) (FT.)	MAXIMUM PONDING DEPTH AT WSE (FT.)	LEGEND
1503.87	1.87	[White Box]
1505.74	3.74	[Lightest Blue Box]
1507.61	5.61	[Light Blue Box]
1509.40	7.40	[Blue Box]

**EARTHWORK ANALYSIS:**

MATERIAL AVAILABLE:	MATERIAL REQUIRED:
TOTAL EXCAVATION 24,978 C.Y.	FILL 6,981 C.Y.
APPROXIMATE EXPORT 17,996 C.Y.	

NOTE: EARTHWORK FIGURES SHOWN ARE APPROXIMATE FIGURES AND ARE TO BE USED BY BUILDING DEPARTMENT ONLY. CONTRACTOR SHALL CALCULATE HIS OWN EARTHWORK QUANTITIES AND BID A COMPLETE JOB.



**CITY OF PERRIS**  
PUBLIC WORKS DEPARTMENT

**DETENTION BASIN PLAN**  
**FIRST MARCH**  
**NATWAR LANE**

Designed by _____	Approved by _____	Date _____
Checked by _____	Public Works Director _____	R.C.E. XXXXX
Designed by _____		
Date _____		
Checked by _____		
Date _____		

Sheet **2** of **8** Sheets

**PREPARED FOR:**  
 FIRST INDUSTRY REALTY TRUST, INC.  
 888 N. PACIFIC COAST HIGHWAY STE. 175  
 EL SEGUNDO, CA 90245  
 PHONE: (310) 321-3813  
 EMAIL: MPIC@FIRSTINDUSTRIAL.COM

**Tai** Thienes Engineering, Inc.  
 CIVIL ENGINEERING - LAND SURVEYING  
 14340 FIRESTONE BOULEVARD  
 LA BARRA, CALIFORNIA 90639  
 PH: (714) 321-4811 FAX: (714) 321-4753

SEE CONTINUATION BELOW

SEE CONTINUATION ABOVE

# BUILDING 1 419,034 SF

1514.44 FF  
1513.86 PAD

36 DOCK DOORS


41 DOCK DOORS

FREEMWAY

B.N.S.F.

215

215



**CITY OF PERRIS**  
PUBLIC WORKS DEPARTMENT  
**CONCEPTUAL UTILITY PLAN**  
FREEMWAY 215 AND NATWAR LANE  
NATWAR LANE










PREPARED FOR:  
**FIRST INDUSTRY REALTY TRUST, INC.**  
898 N. PACIFIC COAST HIGHWAY STE. 175  
EL SEGUNDO, CA 90245  
PHONE: (310) 321-3813  
EMAIL: MPLO@FIRSTINDUSTRIAL.COM

**Tai** *Thienes Engineering, Inc.*  
CIVIL ENGINEERING - LAND SURVEYING  
14140 FIRESTONE BOULEVARD  
LA MIRADA, CALIFORNIA 90638  
PH: (714) 321-4811 FAX: (714) 321-4733

Designed by	Approved by	Date
Checked by	Public Works Director	R.C.E. XXXXX
Designed by		
Checked by		
Sheet <b>3</b> of <b>8</b>		Sheets

3788/3 OF 8 SHEET

SEE SHEET 2



**CITY OF PERRIS**  
PUBLIC WORKS DEPARTMENT  
**CONCEPTUAL UTILITY PLAN**  
**FREWAY 215 AND NATWAR LANE**  
**NATWAR LANE**

**PREPARED FOR:**  
FIRST INDUSTRY REALTY TRUST, INC.  
898 N. PACIFIC COAST HIGHWAY STE. 175  
EL SEGUNDO, CA 90245  
PHONE: (310) 321-3813  
EMAIL: MPOL@FIRSTINDUSTRIAL.COM

**Tai** Thienes Engineering, Inc.  
CIVIL ENGINEERING • LAND SURVEYING  
14340 FIRESTONE BOULEVARD  
LA BREA, CALIFORNIA 90639  
PH: (714) 521-4811 FAX: (714) 521-4753

Designed by _____	Approved by _____	Date _____
Checked by _____	Public Works Director _____	R.C.E. XXXXX
Designed by _____		
Date _____		
Checked by _____		
Date _____		

Sheet **4** of **8** Sheets

3788/4 OF 8 SHEET

Last Update: 11/10/21  
G:\3788-3789\3788\3788CDP-04CUP.dwg

MARCH AIR RESERVE BASE

BUILDING 1  
419,034 SF

PHASE ONE  
INTERIM DETENTION BASIN

INTERSTATE 215


B.N.S.F.

RAILROAD

NATWAR LANE

36 DOCK DOORS

41 DOCK DOORS



City of Perris Public Works Department  
**CONCEPTUAL STORM DRAIN PLAN**  
**FIRST MARCH LOGISTICS**  
**NATWAR LANE**

Designed by	Approved by	Date
Checked by		
Date		
Designed by	Public Works Director	R.C.E. XXXXX
Date		
Checked by		
Date		



Sheet **5** of **8** Sheets

PREPARED FOR:  
**FIRST INDUSTRY REALTY TRUST, INC.**  
 888 N. PACIFIC COAST HIGHWAY STE. 175  
 EL SEGUNDO, CA 90245  
 PHONE: (310) 321-3813  
 EMAIL: MPLO@FIRSTINDUSTRIAL.COM



3788.5 OF 8 SHEET

Last Update: 11/10/21  
G:\3780-3789\3788\3788COP-05-SD PLAN.dwg



Last Update: 11/10/21  
 G:\3780-3789\3788\3788COP-06-SD-PROF.dwg

**CITY OF PERRIS**  
 PUBLIC WORKS DEPARTMENT

**CONCEPTUAL STORM DRAIN PROFILES**

**FIRST MARCH LOGISTICS**  
**NATWAR LANE**

3788.6 OF 8 SHEET

Designed by _____	Approved by _____	Date _____
Checked by _____		
Designed by _____	Public Works Director _____	R.C.E. XXXXX
Checked by _____		
Date _____	Sheet <b>6</b> of <b>8</b>	Sheets

PREPARED FOR:  
 FIRST INDUSTRY REALTY TRUST, INC.  
 898 N. PACIFIC COAST HIGHWAY STE. 175  
 EL SEGUNDO, CA 90245  
 PHONE: (310) 321-3813  
 EMAIL: MPICOL@FIRSTINDUSTRIAL.COM



MARCH AIR RESERVE BASE

FUTURE 10'x10' RCB  
PER WEBB PLAN DATED 2/18/20

FUTURE 10'x10' RCB  
PER WEBB PLAN DATED 2/18/20

FUTURE HEADWALL  
PER WEBB PLAN DATED 2/18/20  
FUTURE OUTLET AT HEADWALL  
PER WEBB PLAN DATED 2/18/20  
1486.23 INV.

FUTURE 1 TON HALF DEPTH  
GROUTED RIP RAP  
PER WEBB PLAN DATED 2/18/20

FUTURE 12'x10' RCB  
PER PRELIMINARY  
PERRIS VALLEY CHANNEL  
LATERAL "B" STAGE 4

PHASE ONE  
INTERIM DETENTION BASIN

BUILDING 1  
419,034 SF

36 DOCK DOORS

4 DOCK DOORS

NATWAR LANE

WESTERN WAY

INTERSTATE 215  
RAILROAD

B.N.S.F.

NANDINA DRIVE



Last Update: 11/10/21  
G:\3788-3789\3788\3788COP-07-SD\_PUB.dwg

**CITY OF PERRIS**  
PUBLIC WORKS DEPARTMENT

**CONCEPTUAL PUBLIC STORM  
DRAIN PLAN**

**FIRST MARCH LOGISTICS  
NATWAR LANE**


PREPARED FOR:  
FIRST INDUSTRY REALTY TRUST, INC.  
898 N. PACIFIC COAST HIGHWAY STE. 175  
EL SEGUNDO, CA 90245  
PHONE: (310) 321-3813  
EMAIL: MPLO@FIRSTINDUSTRIAL.COM

**Tai** Thienes Engineering, Inc.  
CIVIL ENGINEERING - LAND SURVEYING  
14140 FIRESTONE BOULEVARD  
LA MIRADA, CALIFORNIA 90638  
PHONE: (714) 521-4811 FAX: (714) 521-4773

Designed by	Approved by	Date
Checked by	Public Works Director	R.C.E. XXXXX
Designed by		
Date		
Checked by		
Date		

Sheet **7** of **8** Sheets

3788.7 OF 8 SHEET




**SD LINE A**

PROFILE SCALE:  
 HORIZ. - 1" = 40'  
 VERT. - 1" = 4'

\*CONTRACTOR TO VERIFY LOCATION AND INVERT ELEVATIONS OF EXISTING UTILITIES AND DRAINAGE SYSTEMS AND NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO ANY CONSTRUCTION.

12+00 13+00 14+00 15+00 16+00 17+00 18+00 19+00 20+00 21+00 22+00 23+00 24+00




**SD LINE A**

PROFILE SCALE:  
 HORIZ. - 1" = 40'  
 VERT. - 1" = 4'

\*CONTRACTOR TO VERIFY LOCATION AND INVERT ELEVATIONS OF EXISTING UTILITIES AND DRAINAGE SYSTEMS AND NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO ANY CONSTRUCTION.

24+00 25+00 26+00 27+00 28+00 29+00 30+00 31+00 32+00 33+00 34+00 35+00 36+00 37+00



**SD LINE B**

PROFILE SCALE:  
 HORIZ. - 1" = 40'  
 VERT. - 1" = 4'

\*CONTRACTOR TO VERIFY LOCATION AND INVERT ELEVATIONS OF EXISTING UTILITIES AND DRAINAGE SYSTEMS AND NOTIFY ENGINEER OF ANY DISCREPANCIES PRIOR TO ANY CONSTRUCTION.

24+00 25+00 26+00 27+00 28+00 29+00 30+00 31+00 32+00

Last Update: 11/10/21  
 G:\3788-3789\3788\3788COP-08-SD PUB PROF.dwg

**CITY OF PERRIS**  
 PUBLIC WORKS DEPARTMENT

**CONCEPTUAL PUBLIC STORM DRAIN PROFILES**


**FIRST MARCH LOGISTICS**  
**NATWAR LANE**

Designed by _____	Approved by _____
Checked by _____	Date _____
Designed by _____	Public Works Director _____ R.C.E. XXXXX
Date _____	
Checked by _____	
Date _____	

Sheet **8** of **8** Sheets

3788 8 OF 8 SHEET

PREPARED FOR:  
**FIRST INDUSTRY REALTY TRUST, INC.**  
 898 N. PACIFIC COAST HIGHWAY STE. 175  
 EL SEGUNDO, CA 90245  
 PHONE: (310) 321-3813  
 EMAIL: MPICOL@FIRSTINDUSTRIAL.COM



# Appendix 3: Soils Information

*Geotechnical Study and Other Infiltration Testing Data*



**ARAGÓN GEOTECHNICAL, INC.**  
Consultants in the Earth & Material Sciences

July 19, 2019  
Project No. 4528-I

**First Industrial Realty Trust, Inc.**  
898 N. Pacific Coast Highway, Suite 175  
El Segundo, California 90245

Attention: Mr. Matt Pioli

Subject: WQMP Site Assessment & Infiltration Test Results  
"Freeway 215 & Natwar Lane" Light Industrial Project  
City of Perris, Riverside County, California.

Dear Mr. Pioli:

In accordance with our proposal dated February 8, 2019, Aragón Geotechnical Inc. (AGI) has completed site testing and analyses of soil infiltration potential. Our conclusions are intended to support the creation of a site-specific water quality management plan (WQMP) and final selection of stormwater best management practices (BMPs) at the listed project. Data and recommendations for BMP engineering design and construction of low impact development (LID), hydromodification, and pollution prevention features are required by the Santa Ana Region (SAR) *Water Quality Management Plan* effective January 1, 2013. AGI services were performed concurrently with a preliminary geotechnical design investigation for the proposed industrial development. Subsurface explorations, geological reconnaissance and research, and characterization of the local groundwater regime were requirements for both of AGI's current studies. Our primary tasks for the infiltration feasibility assessment consisted of (1) Review of local and regional geologic, soil, and groundwater elevation maps plus proprietary data from other nearby AGI investigations; (2) Machine drilling of percolation test borings to estimated elevations of a proposed infiltration system, using a hollow-stem auger drilling rig; (3) Field tests of water absorption rates; and (4) Preparation of this results report. Calculations or recommendations for the design precipitation event intensity or duration, climate coefficients, storm water retention or treatment flow rates, or treatment volumes were outside of AGI's scope.

### **Proposed Construction**

AGI was furnished with a conceptual development plan dated February 26, 2019, prepared by the Irvine firm of HPA Architecture. The site plan included a proposed structure outline, but lacked topographic contours or preliminary finish surface elevations. The primary new features in the approximately 23.2-acre project site would be a 453,760-square-foot warehouse surrounded by access driveways and parking stalls for automobiles and heavy trucks. Concrete pavements are expected with limited possible exceptions for automobile parking lots. The logistics or light industrial building would reasonably comprise concrete tilt-up walls resting on shallow strip footings, with a concrete slab-on-grade industrial floor.

One BMP for stormwater management has been assessed by this study: A simple excavated water quality basin located in a narrow property “tail” that extends almost 1,000 feet east of the end of Natwar Lane. The basin would be situated just east of a proposed extension of Western Way, and an already-built Metropolitan Water District buried water transmission pipeline (the 96-inch-diameter welded-steel Perris Valley Pipeline). Estimated infiltration surface elevations were established by AGI at 10 feet below current grade. This deeper-than-average prospective basin floor was selected to maximize possible capture volume, while also assessing potentially more-favorable soils below cemented horizons detected during exploration drilling. Overflows or controlled discharges would presumably be directed east, toward an unlined surface swale within March Air Reserve Base property. Based on City-minimum landscape area guidelines, we would predict up to 88 percent of the site’s incident precipitation will intercept impermeable surfaces composed of the building and surrounding pavements.

### **Subsurface Investigation and Permeability Testing**

At the time of AGI’s investigations, the project site consisted of a very flat, vacant, and formerly agricultural open field. Field work encountered ground surfaces that were soft and furrowed from weed abatement plowing.

Site-wide, 14 deep exploratory soil borings were drilled on June 18 and June 25, 2019 with a truck-mounted hollow-stem auger rig for the project geotechnical investigation. One boring was located east of the Perris Valley Pipeline where a basin could be accommodated. Most other geotechnical borings were situated within the building envelope. These borings, and some anecdotal information from other crews performing direct-push testing for environmental screening studies, were nonetheless useful for assessing feasibility for

shallow basins or bioswales closer to Natwar Lane. All exploratory borings were continuously observed by AGI's engineering geologist and logged for materials classifications, interpreted materials origins, relative density as determined from *in situ* penetration tests, presence of groundwater, and other characteristics that can influence water uptake rates. The exploration borings were backfilled with tamped auger cuttings. No permanent wells were created. The Field Boring Log for the basin exploration hole B-10 is included in the accompanying Appendix. A modified version of the conceptual plan depicting a speculative BMP site, geotechnical and infiltration-related soil borings, and locations of tests done for this study is presented on Plate No. 1 at the back of this report.

AGI's infiltration determinations were based on technical guidelines for percolation testing in small-diameter boreholes. Most California jurisdictions including co-permittees of the Riverside County master discharge permit accept percolation test results for stormwater BMP design, with the proviso that percolation test data be adjusted to an equivalent one-dimensional (1-D) infiltration velocity. Boreholes of course infiltrate water both vertically and laterally. Considering potential available head in a narrow but fairly deep basin, AGI elected to use the constant-head U.S. Bureau of Reclamation Well Permeameter Method (USBR Procedure 7300-89). Measured water takes in units of vol/time are converted by formula into an equivalent infiltration test velocity in units of length/time. All field exploration, percolation testing, and derivations of equivalent infiltration rates were performed by or under direct supervision of the following qualified professionals:

- Fernando Aragón, P.E.: California Registered Civil Engineer and Geotechnical Engineer, with over 15 years of professional experience.
- Mark G. Doerschlag: California Professional Geologist and Certified Engineering Geologist, with over 35 years of professional experience.

The as-built test hole depths were established at 10.1 feet below ground surfaces (bgs). Approximately 2 to 3 inches of 3/4" gravel was placed in the bottom of each test hole, followed by insertion of a 3¼-inch O.D. PVC perforated pipe encased in filter fabric material. Well bore gravel filter packs were omitted from the annular space between the plastic pipe and hole sidewalls given stable and cohesive soils in the test intervals. Pre-saturation of the test bores was omitted for a constant-head test.

Heads of 5.0 feet were assigned for all 4 tested locations. AGI's intent was to test the roughly 5 feet of materials composing possible bottom and sidewall surfaces. The

intended 5.0-foot interval also exceeded the minimum-desired test interval of at least 10 times the 4-inch borehole radius. Regular garden hoses provided pressurized municipal water to each test site. Feed water was introduced at the bottom of infiltration test holes. Maximum-available delivery rates of about 8 gallons per minute were much higher than water-take rates. The soils proved to be relatively impermeable. Water volumes delivered per time-trial increment were directly measured to the nearest 0.1 gallon using a Sensus SR-II magnetic-drive positive displacement water meter. A gate valve downstream of the meter was adjusted as needed to maintain the specified 5.0-foot test head. Absolute water level was monitored with an electric meter probe inserted into the primary perforated pipe. Total input durations of about 2½ hours were sufficient to arrive at near-steady-state water takes. A typical permeameter test would show incremental (constant-head) rates asymptotically approaching a minimum rate. Record sheets with the field measurement data are included in the Appendix.

## **FINDINGS**

### **Local Soil Conditions**

Surficial soils east of the Western Way projection consist of brown-colored and medium dense silty sand (Unified Soil Classification System symbol SM). The BMP-area shallow soils are notably “brownier” and less cohesive than most near-surface horizons in the future building area. Slightly clayey and lightly cemented conditions occur near 5 feet deep. The base of the surficial subunit is marked by an erosional contact at a depth of 10 feet. A few very thin layers of cleaner sand may occur near the basal contact.

Materials at the tested basin-bottom elevation constitute dense to very dense, massive silty sand with some clay (symbol SM). Fines proportions of around 35% and distinctively weathered coarse sand grains are characteristic. Clayey sand (symbol SC) composes possibly half or more of the total interval between 15 and 26½ feet below grade. Vertical variability is gradational in nature, and not marked by sharp stratigraphic boundaries.

From a soil science viewpoint, the National Resources Conservation Service classifies basin-site surficial materials as Hanford fine sandy loam HgA. Hanford soils characteristically do not have indurated duripans, although as noted above there is some cemented soil below 5 feet based on our exploration. Sandy loam HgA is assigned to hydrologic soil group A. Soil classifications and hydrologic soil groups are usually limited to materials shallower than 60 inches or so; thus, we would expect that a basin-type BMP improvement

will completely bypass NRCS soil series and cannot be qualified solely on the basis of a NRCS hydrologic soil group.

AGI's geotechnical studies identified the site materials as early to middle Pleistocene alluvium (unit Qvof<sub>a</sub> of Morton & Miller, 2006). Regional maps generally omit shallow veneers of younger sediments that are frequently found near the edges of the Perris Plain. We interpret materials shallower than 10 feet at the basin site as not technically part of the Qvof<sub>a</sub> unit. Weaker soil development would be consistent with a late Pleistocene age assignment. Most of the Perris Plain where the Wilson Avenue project is sited is considered part of the "Paloma" depositional surface of Woodford et al. (1971), typified by fairly strongly developed illuvial clay and calcic horizons atop the older parent materials. Detrital sediments have originated from granitic bedrock terrains located west and north of the project. The alluvium buries and conceals several deep erosional channels carved into granitic basement bedrock that can be considered tributaries to an ancestral San Jacinto River. The maximum depth of the Qvof<sub>a</sub> unit at the project site is not known with certainty, but may be approximately 550 feet based on geophysical survey data (AECOM, 2013). Basement rock rises rapidly toward the Interstate 215 freeway, where it is possibly only 50 to 70 feet deep.

### **Groundwater**

AGI's BMP exploration boring did not encounter groundwater within the 26½-foot total exploration depth. At geotechnical boring B-1 to the west, slow groundwater inflows were observed. A stable water level 24.0 feet below grade was measured after several hours. Boring B-3 also exhibited a stable water level at around 28 feet. All other soil borings remained dry.

The project site is within the West San Jacinto groundwater subbasin. According to many years of monitoring well records reviewed through the State GeoTracker website, groundwater within a radius of about a half-mile from the property becomes shallower to the west and north, with minimum measured depths occasionally under 20 feet. Groundwater gradients steepen near the site. The hydrogeologic regime is complex due to the heterogeneity of the alluvial basin fill, substantial erosional relief of the buried bedrock surfaces under the northern Perris Valley, and municipal groundwater pumping. There is a well-documented record for rising groundwater levels inside the adjacent March Air Reserve Base. Rising water levels are attributed to changing land uses in the Perris

Plain vicinity, such as the cessation of formerly widespread agricultural pumping and introduction of irrigated suburban tracts, golf courses, and the Riverside National Cemetery near the project. Nonetheless, AGI concludes that minimum depths to permanent groundwater in the BMP basin area have always been in excess of 30 feet.

Jurisdictional requirements usually mandate a minimum separation between stormwater BMPs and groundwater of at least 10 feet and up to 40 feet (for very permeable soils). Data thus indicate there should be zero limitations on BMP design or construction due to groundwater at the project.

**Permeameter Test Results**

The table below summarizes the obtained field test results. Based on the drilling log, the test results are interpreted as representative of longer-duration uptake capacity in denser materials at the bottom of injection holes. Lateral absorption into thin cleaner-sand lenses was short-lived and limited in volume.

Test Location	Tested Interval (depth below existing ground surface, feet)	Constant-Head Percolation Rate (gal/hr)	Field Test Infiltration Velocity $I_f$ (in/hr)
IN-1	6.1 - 10.1	8.4	0.17
IN-2	6.1 - 10.1	11.6	0.23
IN-3	6.1 - 10.1	20.8	0.41
IN-4	6.1 - 10.1	3.6	0.07

Measured percolation rates were converted to 1-D infiltration velocities by the USBR 7300-89 formula:

$$K_s = \frac{Q[\ln(H/r + (H/r + 1)^{0.5}) - 1](\mu_T/\mu_{20})}{2\pi H^2}$$

Where:

- $K_s$  = saturated hydraulic conductivity (infiltration rate, inches/hour)
- H = height of water in well (inches)
- Q = percolation flow rate from selected time interval (cubic inches/hour)
- r = effective radius of well (inches)
- $\mu_T$  = viscosity of water at water temperature, t
- $\mu_{20}$  = viscosity of water at 20°C

The calculated result  $K_s$  is close to but not exactly the same as an infiltration test velocity  $I_t$  calculated from a ring infiltrometer test. The minor difference is ignored for stormwater BMP design.

The calculated velocities would be judged very poor for infiltration BMPs. We think the results correctly characterize the dense and somewhat clayey nature of test-area sediments deeper than 10 feet. We do not think there are better soil conditions above or below the tested intervals.

### **Conclusions, Recommendations, and Advice**

The SAR *Water Quality Management Plan* explicitly requires any infiltration-based BMP to be clear of water in 72 hours or less after the design storm event. Mathematically, for typical volume-based BMP improvements, this requires field infiltration velocities  $I_t$  of roughly 1.6 inches per hour or faster. Achieved Natwar Lane project test results are far lower. AGI recommends a mean field-test infiltration test velocity of 0.22 inches per hour for the prospective basin near Western Way.

We think actual performance may be reduced further once available vadose-zone storage is filled during first-of-the-season storm events and the wetting front encounters deeper clayey strata. Riverside County guidelines for storm water best management practices specify a factor of safety of 3.0 when calculating the design infiltration velocity  $I_d$  for an infiltration-type BMP, based on the methods and results of this investigation (Appendix A, Table 1, *Design Handbook for Low Impact Development Best Management Practices*). The AGI-recommended average  $I_t$  should be reduced by a factor of 3 to derive final  $I_d$ . Unless the design capture volume is unexpectedly small, it appears that the designated WQMP BMP site cannot rely on surface infiltration. Hydromodification to reduce peak flows will likely require extended detention, treatment, and thence controlled release to the MS4 system [open ditch in MARB property].

Our reviews of geotechnical boring data did not identify any other site areas that could be considered favorable for either shallow open-basin BMPs or subterranean installations. Soils beneath and beside the proposed warehouse were logged as cemented and would be judged impermeable starting just 2 to 3 feet below grade and extending to depths exceeding 10 feet. Limited areas had possibly permeable sandy horizons near 20 feet

deep, but problems with inadequate separation to groundwater appear to rule out certain engineered options such as drywells. At this time, hydromodification with biofiltration “treat and release” appear to be the only viable options for peak-discharge and water quality management.

It is important to note the test velocities were obtained in carefully prepared test holes as free as practicable of surface sealing and boundary-zone compaction. Field performance of any designed LID improvement could be markedly lower than AGI’s achieved results if precautions are not maintained during construction. It will be imperative to *specify* construction practices for minimizing excavation bottom compaction. Excavations should be made with backhoes, grade-alls, or excavators working from beside the basin bottom. An overall goal of preventing heavy equipment from rolling or tracking any infiltration system excavation bottom should be understood.

Lastly, AGI concludes from test and exploration findings that the selected BMP location should neither cause structural concerns, nor result in significantly increased risks to the proposed building or neighboring properties from slope instability, liquefaction, or settlement. Future grading plan reviews are recommended, however, to analyze bottom elevations and lateral setbacks to nearby proposed street improvements. We add that MWD may have additional setback requirements for treatment control BMPs near their Perris Valley Pipeline.


### **Investigation Limitations**


The findings in this report may require modification as a result of later field observations. Our opinions have been based on the results of limited testing within the planned water-quality BMP site combined with extrapolations of soil conditions away from the test bores. The nature and extent of variations within or beyond the proposed BMP may not become evident until construction. If conditions encountered during construction vary significantly from those indicated by this report, or BMP type or location changes are proposed, then additional site testing, preparation recommendations, or as-built tests may be needed to achieve correct designs for the treatment control BMP system(s).

**Closure**

This report was prepared for the use of First Industrial Realty Trust, Inc., their civil engineers, and authorized designates in cooperation with this office. Our findings and recommendations were prepared in accordance with generally accepted professional principles and local practice in the fields of engineering geology and geotechnical engineering. We make no other warranties either expressed or implied. Questions concerning the test results or design advice are invited, and may be directed to the undersigned at our Riverside office at (951) 776-0345.

Respectfully submitted,  
**Aragón Geotechnical, Inc.**

  
7/19/19



Mark G. Doerschlag, CEG 1752  
Engineering Geologist

  
7/19/19



C. Fernando Aragón, P.E., M.S.  
Geotechnical Engineer, G.E. 2994

MGD/CFA:mma

Attachments: Exploratory Boring Log, Boring B-10  
Percolation Field Test Data, Sites IN-1 through IN-4  
Plate No. 1, Exploration & Infiltration Test Location Map (fold-out)

Distribution: (4) Addressee

## REFERENCES

- AECOM Technical Services, Inc., 2013, *Final 2011-2012 Annual Monitoring Report, Long-Term Groundwater Monitoring Program, March Air Reserve Base, Former March Air Force Base, California*: contractor's report dated December 9, 2013 (Contract No. FA8903-09-D-8547-0007, Project No. 60271680-0009AG), digital download from State of California GeoTracker website, <https://geotracker.waterboards.ca.gov/>
- Morton, D.M., and Miller, F.K., 2006, Geologic map of the San Bernardino and Santa Ana 30' x 60' quadrangles, California [ver. 1.0], U.S. Geological Survey Open File Report 2006-1217, scale 1:100,000.
- Natural Resources Conservation Service, 2019, Web Soil Survey utility, accessed 7/18/19 from Internet URL <http://websoilsurvey.nrcs.usda.gov/app/HomePage.htm>
- Riverside County Flood Control and Water Conservation District, 2011, *Design Handbook for Low Impact Development Best Management Practices*, Riverside, California, download file at Internet URL [http://rcflood.org/downloads/NPDES/Documents/LIDManual/LID\\_BMP\\_Design\\_Handbook.pdf](http://rcflood.org/downloads/NPDES/Documents/LIDManual/LID_BMP_Design_Handbook.pdf)
- Woodford, A.O., Shelton, J.S., Doehring, D.O., and Morton, R.K., 1971, Pliocene-Pleistocene history of the Perris Block, southern California: Geological Society of America Bulletin, v. 82, p. 3421-3448.



# FIELD LOG OF BORING B - 10

Sheet 1 of 2

Project: **FREEWAY 215 & NATWAR LANE INDUSTRIAL PROJECT**

Location: **CITY OF PERRIS, RIVERSIDE COUNTY, CALIF.**

Date(s) Drilled: <b>6/25/19</b>	Logged By: <b>M. Doerschlag</b>	
Drilled By: <b>GP Drilling</b>	Total Depth: <b>26.5 Ft.</b>	
Rig Make/Model: <b>Mobile B-61</b>	Hammer Type: <b>Automatic trip</b>	
Drilling Method: <b>Hollow-Stem Auger</b>	Hammer Weight/Drop: <b>140 Lb./30 In.</b>	
Hole Diameter: <b>8 In.</b>	Surface Elevation: <b>± 1505.0 Ft. AMSL per Earth DEM</b>	

Comments: Located near center of proposed BMP basin.

DEPTH (ft.)	ELEVATION (MSL DATUM)	SAMPLE INTERVALS		GRAPHIC LOG	USCS	GEOTECHNICAL DESCRIPTION	DRY DENSITY (pcf)	WATER CONTENT (%)	WELL COMPLETION	OTHER TESTS
		BULK DRIVE	TYPE, "N" or (Blows/ft.)							
0	1505				SM	Silty Sand: Brown; medium dense; slightly moist; fine to coarse-grained sand. Massive and probably bioturbated in upper 4-5 feet. Does not have particularly strong pedogenic soil development -- interpreted slightly younger fan sediments over Paloma-age alluvium. [Very old alluvium]				
5	1500		SPT 11 9 11 N=20		SM	← Silty sand, trace to some clay and slightly cemented, with diffuse carbonate. Not visibly porous.				
			SPT 8 13 13 N=26		SM	← Silty sand, trace of clay, weakly cemented, few coarse weathered granules, not visibly porous.				
10	1495		SPT 9 14 20 N=34		SM	Sharp erosional contact.				
15	1490				SM	Silty Sand: Yellowish brown; dense; slightly moist; fine to coarse immature sand in silty matrix with variable clay content (unit alternately grades from silty sand to clayey sand). Grains highly weathered. Sample at 10' is massive and not visibly porous. [Very old alluvium]				

Continued on next sheet.



# FIELD LOG OF BORING B - 10

Sheet 1 of 2

Project: **FREEWAY 215 & NATWAR LANE INDUSTRIAL PROJECT**

Location: **CITY OF PERRIS, RIVERSIDE COUNTY, CALIF.**

Date(s) Drilled: <b>6/25/19</b>	Logged By: <b>M. Doerschlag</b>	
Drilled By: <b>GP Drilling</b>	Total Depth: <b>26.5 Ft.</b>	
Rig Make/Model: <b>Mobile B-61</b>	Hammer Type: <b>Automatic trip</b>	
Drilling Method: <b>Hollow-Stem Auger</b>	Hammer Weight/Drop: <b>140 Lb./30 In.</b>	
Hole Diameter: <b>8 In.</b>	Surface Elevation: <b>± 1505.0 Ft. AMSL per Earth DEM</b>	

Comments: Located near center of proposed BMP basin.

DEPTH (ft.)	ELEVATION (MSL DATUM)	SAMPLE INTERVALS		GRAPHIC LOG	USCS	GEOTECHNICAL DESCRIPTION	DRY DENSITY (pcf)	WATER CONTENT (%)	WELL COMPLETION	OTHER TESTS
		BULK DRIVE	TYPE, "N" or (Blows/ft.)							
0	1505				SM	Silty Sand: Brown; medium dense; slightly moist; fine to coarse-grained sand. Massive and probably bioturbated in upper 4-5 feet. Does not have particularly strong pedogenic soil development -- interpreted slightly younger fan sediments over Paloma-age alluvium. [Very old alluvium]				
5	1500		SPT 11 9 11 N=20		SM	← Silty sand, trace to some clay and slightly cemented, with diffuse carbonate. Not visibly porous.				
			SPT 8 13 13 N=26		SM	← Silty sand, trace of clay, weakly cemented, few coarse weathered granules, not visibly porous.				
10	1495		SPT 9 14 20 N=34		SM	Sharp erosional contact.				
					SM	Silty Sand: Yellowish brown; dense; slightly moist; fine to coarse immature sand in silty matrix with variable clay content (unit alternately grades from silty sand to clayey sand). Grains highly weathered. Sample at 10' is massive and not visibly porous. [Very old alluvium]				
15	1490									

Continued on next sheet.

**Percolation Data Sheet (Constant Head Method, Metered Input)**

Project: <i>FIRST LND. NATWAR</i>	Project No. <i>4528-SF1</i>	
Test Hole No. <i>1N-1</i>	Date Drilled: <i>6/25/19</i>	
Depth of Test Hole: <i>10.1</i>	Soil Classification: <i>SM</i>	
Check for Sandy Soil Criteria Tested By: <i>—</i>	Date: <i>—</i>	Presoak: <i>—</i>
Field Percolation Test By: <i>ALD</i>	Date: <i>7/1/19</i>	

Sandy Soil Criteria Test

Trial No.	Time	Time Interval (Min.)	Initial Water Level (In.)	Final Water Level (In.)	Δ in Water Level (In.)
1					
2					

- Use:  Normal Soil Criteria  
 Sandy Soil Criteria (>50% of wetted interval drop in <25 min. both trials)

Time	Time Interval (min.)	Total Elapsed Time (min.)	Initial Meter Reading	Final Meter Reading	Total Discharge Volume (gal)	Wetted Length (ft.)	Q F.S. = 3 (gal/ft. <sup>2</sup> /day)
<i>11:18</i>	<i>15.0</i>	<i>15:00</i>	<i>7030.7</i>	<i>7034.5</i>	<i>3.8</i>	<i>5.0</i> <i>4.0</i>	
<i>11:33</i>	<i>15.0</i>	<i>30:00</i>	<i>7034.5</i>	<i>7037.0</i>	<i>3.5</i>		
<i>11:48</i>	<i>15.0</i>	<i>45:00</i>	<i>7037.0</i>	<i>7040.4</i>	<i>3.4</i>		
<i>12:03</i>	<i>15.0</i>	<i>60:00</i>	<i>7040.4</i>	<i>7043.4</i>	<i>3.0</i>		
<i>12:18</i>	<i>15.0</i>	<i>75:00</i>	<i>7043.4</i>	<i>7046.0</i>	<i>2.6</i>		
<i>12:33</i>	<i>15.0</i>	<i>90:00</i>	<i>7046.0</i>	<i>7048.1</i>	<i>2.1</i>		
<i>12:48</i>	<i>15.0</i>	<i>105:00</i>	<i>7048.1</i>	<i>7050.0</i>	<i>1.9</i>		
<i>1:03</i>	<i>15.0</i>	<i>120:00</i>	<i>7050.0</i>	<i>7053.2</i>	<i>3.2</i>		
<i>1:18</i>	<i>15.0</i>	<i>135:00</i>	<i>7053.2</i>	<i>7056.3</i>	<i>3.1</i>		
<i>1:33</i> <i>1:48</i>	<i>15.0</i>	<i>150:00</i>	<i>7056.3</i>	<i>7058.4</i>	<i>2.1</i>		

*END*

**Percolation Data Sheet (Constant Head Method, Metered Input)**

Project: <i>FIRST IND. NATWAR</i>		Project No. <i>4528-SF1</i>	
Test Hole No. <i>IN-2</i>		Date Drilled: - <i>4/25/19</i>	
Depth of Test Hole: <i>10.1' bgs</i>		Soil Classification: <i>SM</i>	
Check for Sandy Soil Criteria Tested By: <i>—</i>		Date: <i>—</i>	Presoak: <i>—</i>
Field Percolation Test By: <i>KGL</i>		Date: <i>7/1/19</i>	

Sandy Soil Criteria Test

Trial No.	Time	Time Interval (Min.)	Initial Water Level (In.)	Final Water Level (In.)	Δ in Water Level (In.)
1					
2					

- Use:  Normal Soil Criteria  
 Sandy Soil Criteria (>50% of wetted interval drop in <25 min. both trials)

START  
11:18

Time	Time Interval (min.)	Total Elapsed Time (min.)	Initial Meter Reading	Final Meter Reading	Total Discharge Volume (gal)	Wetted Length (ft.)	Q F.S. = 3 (gal/ft. <sup>2</sup> /day)
	15.0	15 min.	616.4	620.5	4.1	5.0' 	
11:33	15.0	30:00	620.5	623.2	2.7		
11:48	15.0	45:00	623.2	626.1	2.9		
12:03	15.0	60:00	626.1	628.6	2.5		
12:18	15.0	75:00	628.6	631.4	2.8		
12:33	15.0	90:00	631.4	634.1	2.7		
12:48	15.0	105:00	634.1	637.0	2.9		
1:03	15.0	120:00	637.0	639.7	2.7		
1:18	15.0	135:00	639.7	642.2	2.5		
1:33	15.0	150:00	642.2	645.1	2.9		
1:48							

END

**Percolation Data Sheet (Constant Head Method, Metered Input)**

Project: <i>FIRST ADD. NATWAR</i>	Project No. <i>4528-0F1</i>	
Test Hole No. <i>14-3</i>	Date Drilled: <i>6/25/19</i>	
Depth of Test Hole: <i>10.1'</i>	Soil Classification: <i>SM</i>	
Check for Sandy Soil Criteria Tested By: <i>→</i>	Date: <i>—</i>	Presoak: <i>—</i>
Field Percolation Test By: <i>MCD/KL</i>	Date: <i>7/1/19</i>	

Sandy Soil Criteria Test

Trial No.	Time	Time Interval (Min.)	Initial Water Level (In.)	Final Water Level (In.)	Δ in Water Level (In.)
1					
2					

- Use:  Normal Soil Criteria  
 Sandy Soil Criteria (>50% of wetted interval drop in <25 min. both trials)

Time	Time Interval (min.)	Total Elapsed Time (min.)	Initial Meter Reading	Final Meter Reading	Total Discharge Volume (gal)	Wetted Length (ft.)	Q F.S. = 3 (gal/ft. <sup>2</sup> /day)
<i>1400</i>	<i>15.0</i>	<i>15:00</i>	<i>7073.5</i>	<i>7081.7</i>	<i>8.2</i>	<i>60" / 50'</i>	
<i>1415</i>	<i>15.0</i>	<i>30:00</i>	<i>7081.7</i>	<i>7088.2</i>	<i>6.5</i>		
<i>1430</i>	<i>15.0</i>	<i>45:00</i>	<i>7088.2</i>	<i>7092.6</i>	<i>4.4</i>		
<i>1445</i>	<i>15.0</i>	<i>60:00</i>	<i>7092.6</i>	<i>7098.2</i>	<i>5.6</i>		
<i>1500</i>	<i>23.0</i>	<i>83:00</i>	<i>7098.2</i>	<i>7108.8</i>	<i>10.6</i>		
<i>1523</i>	<i>7.0</i>	<i>90:00</i>	<i>7108.8</i>	<i>7111.3</i>	<i>2.5</i>		
<i>1530</i>	<i>15.0</i>	<i>105:00</i>	<i>7111.3</i>	<i>7116.8</i>	<i>5.5</i>		
<i>1545</i>	<i>15.0</i>	<i>120:00</i>	<i>7116.8</i>	<i>7120.4</i>	<i>3.6</i>		
<i>1600</i>	<i>15.0</i>	<i>135:00</i>	<i>7120.4</i>	<i>7125.6</i>	<i>5.2</i>		
<i>1615</i>							
<i>END</i>							

**Percolation Data Sheet (Constant Head Method, Metered Input)**

Project: <u>FIRST IND. NATWAR</u>	Project No. <u>4528-SF1</u>	
Test Hole No. <u>IN-4</u>	Date Drilled: <u>6/25/19</u>	
Depth of Test Hole: <u>10'-1"</u>	Soil Classification: <u>SM</u>	
Check for Sandy Soil Criteria Tested By: <u>—</u>	Date: <u>—</u>	Presoak: <u>—</u>
Field Percolation Test By: <u>KGL</u>	Date: <u>7/1/19</u>	

Sandy Soil Criteria Test

Trial No.	Time	Time Interval (Min.)	Initial Water Level (In.)	Final Water Level (In.)	Δ in Water Level (In.)
1					
2					

- Use:  Normal Soil Criteria  
 Sandy Soil Criteria (>50% of wetted interval drop in <25 min. both trials)

START  
1:57 PM

Time	Time Interval (min.)	Total Elapsed Time (min.)	Initial Meter Reading	Final Meter Reading	Total Discharge Volume (gal)	Wetted Length (ft.)	Q F.S. = 3 (gal/ft. <sup>2</sup> /day)
	15.0	15 MIN	659.2	662.5	3.2	5.0'	
1412	15.0	30:00	662.5	664.6	2.1	↓	
1427	15.0	45:00	664.6	666.6	2.0		
1442	15.0	60:00	666.6	667.9	1.3		
1457	15.0	75:00	667.9	669.9	2.0		
1512	15.0	90:00	669.9	671.3	2.3		
1527	15.0	105:00	671.3	672.4	1.1		
1542	15.0	120:00	672.4	673.6	1.2		
1557	15.0	135:00	673.6	674.5	0.9		
1612	15.0						
	END						

### Aerial Map




### Tabulation

<b>SITE AREA</b>	
in sq. ft.	1,012,436 s.f.
in acres	23.2 ac
<b>BUILDING AREA</b>	
office 1st floor	5,000 s.f.
office 1st floor	5,000 s.f.
warehouse	443,760 s.f.
<b>TOTAL</b>	<b>453,760 s.f.</b>
<b>COVERAGE</b>	
	44.8%
<b>AUTO PARKING REQUIRED</b>	
1st 20K @ 1/1,000 sf	20 stalls
2nd 20K @ 1/2,000 sf	10 stalls
Over 40K @ 1/5,000 sf	83 stalls
<b>TOTAL</b>	<b>113 stalls</b>
<b>AUTO PARKING PROVIDED</b>	
standard (9'x19')	174 stalls
<b>TRAILER PARKING PROVIDED</b>	
trailer (12' x 55')	144 stalls
<b>Zoning Ordinance for City</b>	
Zoning Designation - Perris Valley Commercial Center SP (PVCC-SP) - Light Industrial	
<b>MAXIMUM FLOOR AREA RATIO</b>	
F.A.R. -	.75
<b>MAXIMUM LOT COVERAGE</b>	
Coverage -	50%
<b>SETBACKS</b>	
<b>Front Yard / Street side</b>	<b>Side Yard</b>
Local / Collector St. - 10'	Adjoining non-residential - 0'
Arterials - 15'	Adjoining residential - 20'
Expressway/Freeway - 20'	
<b>Rear Yard</b>	
Adjoining non-residential - 0'	
Adjoining residential - 20'	
<b>LANDSCAPE REQUIRED</b>	
Percentage	12%
<b>LANDSCAPE REQUIRED</b>	
Percentage (base on net)	12.3%
in sq. ft.	124,669 s.f.

### Legend


- POTENTIAL OFFICE WITH 2ND FLOOR
- WAREHOUSE
- DRIVE THRU DOOR



**GEOTECHNICAL LEGEND**

- + **B-14** Approximate location of exploratory boring
- **4** Approximate location of infiltration test
- Qvof Very old fan alluvium

**Note:** This is a conceptual plan. It is based on preliminary information which is not fully verified and may be incomplete. It is meant as a comparative aid in examining alternate development strategies and any quantities indicated are subject to revision as more reliable information becomes available.



**EXPLORATION & TEST LOCATION MAP**

FREEWAY 215 & NATWAR LANE, PERRIS, CA

PROJECT NO. 4528-SFI    DATE: 7/19/19    PLATE NO. 1

# Conceptual Site Plan

## Freeway 215 & Natwar Lane

## Appendix 4: Historical Site Conditions

*Phase I Environmental Site Assessment or Other Information on Past Site Use (NOT APPLICABLE)*

# Appendix 5: LID Infeasibility

*LID Technical Infeasibility Analysis (NOT APPLICABLE)*

# Appendix 6: BMP Design Details

*BMP Sizing, Design Details and other Supporting Documentation*

Riverside County SWCT<sup>2</sup> Stormwater & Water Conservation Tracking Tool

TOC Choose search item from list Enter Value Locate Clear

Clear All Metadata

- Base Maps
- Base Data
- Stormwater Data
  - Hydromodification Susceptibility Mapping
  - 2010 - 303d/TMDL
  - Hydromodification Exemption Areas
  - District Facilities
    - District Facilities
    - Proposed District Facilities
    - Basin
    - Detention Basin
    - Retention Basin
    - Debris Basin
    - Dam
    - Levee
    - Spreading Grounds
    - Other
  - Permit Areas
  - Hydrologic Unit Codes (HUC)
  - Topographic Drainage Boundary
  - Drainage Area Boundaries
  - City Storm Drains
  - WQMP 85% Design Isohyetal Map
    - Rain Gauges
    - Isohyetal Minor Contours
    - Isohyetal Major Contours
  - CRP (Control Release Point)
  - FEMA Flood Plain
  - Flood Plain - Other Special Studies
  - As-Built Plans
- Groundwater Data
- U.S. Fish and Wildlife Critical Habitat

PROJECT SITE @ 0.61 INCH

Identify Features  
Click on map to view data.

06065C\_654974 (Fema Flood Zones)

OBJECTID_1	1106
OBJECTID	1318
DFIRM_ID	06065C
VERSION_ID	1.1.1.0
FLD_AR_ID	06065C_654974
STUDY_TYP	NP
ZONE_SUBTY	AREA OF MINIMAL
SFHA_TF	F
STATIC_BFE	-9999
V_DATUM	
DEPTH	0
LEN_UNIT	
VELOCITY	0

**Santa Ana Watershed - BMP Design Volume,  $V_{BMP}$**

(Rev. 10-2011)

Legend:

Required Entries

Calculated Cells

*(Note this worksheet shall **only** be used in conjunction with BMP designs from the **LID BMP Design Handbook**)*

Company Name **Thienes Engineering, Inc.**

Date **11/16/2021**

Designed by **Vicky Li**

Case No

Company Project Number/Name

**First March Logistics - Building 1 (3788)**

**BMP Identification**

BMP NAME / ID **MWS-A / DMA A**

*Must match Name/ID used on BMP Design Calculation Sheet*

**Design Rainfall Depth**

85th Percentile, 24-hour Rainfall Depth,  
from the Isohyetal Map in Handbook Appendix E

$D_{85}$  = **0.61** inches

**Drainage Management Area Tabulation**

*Insert additional rows if needed to accommodate all DMAs draining to the BMP*

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Imperivous Fraction, $I_f$	DMA Runoff Factor	DMA Areas x Runoff Factor	Design Storm Depth (in)	Design Capture Volume, $V_{BMP}$ (cubic feet)	Proposed Volume on Plans (cubic feet)
A-1	357192	Roofs	1	0.89	318615.3			
A-2	13068	Ornamental Landscaping	0.1	0.11	1443.5			
	<b>370260</b>		<b>Total</b>		<b>320058.8</b>	<b>0.61</b>	<b>16269.7</b>	<b>16415</b>

Notes:

# WetlandMOD VOLUME BASED SIZING SHEET

## Project Location

Project Name	First March Logistics - Building 1 (DMA A)
City/Town	Perris
State	California
Zip Code	92571



**Horizontal Flow Biofiltration System**

## SIZING CALCULATIONS

### Impervious Area



	Inputs	Units	Notes/References
<b>BMP Drainage Area</b> <small>(not required - manual entry - not part of formula)</small>	8.5	Acres	This includes all areas that will contribute runoff to the proposed BMP, including pervious areas, impervious areas, and off-site areas, whether or not they are directly or indirectly connected to the BMP.
<b>Watershed Impervious Ratio</b> <small>(not required - manual entry - not part of formula)</small>			Watershed Imperviousness Ratio", is equal to the percent of total impervious area in the "BMP Drainage Area" divided by 100
<b>Runoff Coefficient "C"</b> <small>(not required - manual entry - not part of formula)</small>			

<b>Water Quality Volume (required)</b>	16270	cubic feet	Use sizing procedures provided by state or local agencies to determine the appropriate Water Quality Volume. Intensities and design storms vary widely by region and method.
<b>Design Storm Duration</b>	0	hours	Varies depending on geographical region. Set at 0 for pump system set up. LA County 3 hours. Call for details.

### MWS - Linear Sizing

<b>MWS - Linear Model Number (from matrix)</b>	MWS-L-4-21	quantity	Please choose size from "Model Size Matrix" Tab
<b># Of Units</b>	1	quantity	Select the number of systems required to treat the water quality volume. Will vary depending on drain down time regulations.
<b>Discharge Rate (from matrix)</b>	30.41	gallons/minute	Rate of 0.26 gpm/sq ft or 25 in/hr. Field Verified.

### Volume Treated During Event

Processed through MWS - Linear	0.0	cubic feet	30.41 gals/minute
--------------------------------	-----	------------	-------------------

### Volume Treated Following Event

<b>MWS - Linear Static Capacity (from matrix)</b>	144	cubic feet	
<b>Volume Needed in Pre-Storage</b>	16126	cubic feet	Set at zero to start. Size pre-storage system to hold this volume

Sizing complete when equal to value of zero.

<b>TOTAL STORMWATER TREATED</b>	16270	cubic feet	Note: This amount should be equal to the "Water Quality Volume"
<b>Drain Down Time</b>	66.88	hours	Drain down time must be equal to or less than requirement of local jurisdiction. Default 48 hours.

Feel free to fax or email proposed sizing calculations to Modular Wetlands Systems, Inc. for assistance with sizing, compliance, and design.

Phone: 760.433.7640

Fax: 760.433.3176

Email: [Info@modularwetlands.com](mailto:Info@modularwetlands.com)

**Project Information:**

Project Name: First March Logistics - Building 1 (DMA A)  
 Location: Perris, CA  
 Date: 11/16/2021  
 Engineer: Thienes Engineering, Inc.  
 StormTech RPM:

**MC-4500 Site Calculator**

**System Requirements**


Units	Imperial	
Required Storage Volume	16126	CF
Stone Porosity (Industry Standard = 40%)	40	%
Stone Above Chambers (12 inch min.)	12	inches
Stone Foundation Depth (9 inch min.)	36	inches
Average Cover over Chambers (24 inch min.)	24	inches
Bed size controlled by WIDTH or LENGTH?	WIDTH	
Limiting WIDTH or LENGTH dimension	35	feet
Storage Volume per Chamber	195.5	CF
Storage Volume per End Cap	137.7	CF

**System Sizing**

Number of Chambers Required	79	each
Number of End Caps Required	6	each
Bed Size (including perimeter stone)	3,190	square feet
Stone Required (including perimeter stone)	1055	tons
Volume of Excavation	1182	cubic yards
Non-woven Filter Fabric Required (20% Safety Factor)	1197	square yards
Length of Isolator Row	115.8	feet
Woven Isolator Row Fabric (20% Safety Factor)	318	square yards
Installed Storage Volume	16,271	cubic feet

**Controlled by Width (Rows)**

Maximum Width =	35	feet
1 row of	27	chambers
2 row of	26	chambers
Maximum Length =	115.8	feet
Maximum Width =	28.5	feet



**Santa Ana Watershed - BMP Design Volume,  $V_{BMP}$**

(Rev. 10-2011)

Legend:

Required Entries

Calculated Cells

*(Note this worksheet shall **only** be used in conjunction with BMP designs from the **LID BMP Design Handbook**)*

Company Name **Thienes Engineering, Inc.**

Date **11/16/2021**

Designed by **Vicky Li**

Case No

Company Project Number/Name

**First March Logistics - Building 1 (3788)**

**BMP Identification**

BMP NAME / ID **MWS-B / DMA B**

*Must match Name/ID used on BMP Design Calculation Sheet*

**Design Rainfall Depth**

85th Percentile, 24-hour Rainfall Depth,  
from the Isohyetal Map in Handbook Appendix E

$D_{85}$  = **0.61** inches

**Drainage Management Area Tabulation**

*Insert additional rows if needed to accommodate all DMAs draining to the BMP*

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Imperivous Fraction, $I_f$	DMA Runoff Factor	DMA Areas x Runoff Factor	Design Storm Depth (in)	Design Capture Volume, $V_{BMP}$ (cubic feet)	Proposed Volume on Plans (cubic feet)
B-1	439956	Roofs	1	0.89	392440.8			
B-2	15246	Ornamental Landscaping	0.1	0.11	1684			
	<b>455202</b>		<b>Total</b>		<b>394124.8</b>	<b>0.61</b>	<b>20034.7</b>	<b>20172</b>

Notes:

# WetlandMOD VOLUME BASED SIZING SHEET

## Project Location

Project Name	First March Logistics - Building 1 (DMA B)
City/Town	Perris
State	California
Zip Code	92571



**Horizontal Flow Biofiltration System**

## SIZING CALCULATIONS

### Impervious Area



	Inputs	Units	Notes/References
<b>BMP Drainage Area</b> <small>(not required - manual entry - not part of formula)</small>	10.45	Acres	This includes all areas that will contribute runoff to the proposed BMP, including pervious areas, impervious areas, and off-site areas, whether or not they are directly or indirectly connected to the BMP.
<b>Watershed Impervious Ratio</b> <small>(not required - manual entry - not part of formula)</small>			Watershed Imperviousness Ratio", is equal to the percent of total impervious area in the "BMP Drainage Area" divided by 100
<b>Runoff Coefficient "C"</b> <small>(not required - manual entry - not part of formula)</small>			

<b>Water Quality Volume</b> (required)	20035	cubic feet	Use sizing procedures provided by state or local agencies to determine the appropriate Water Quality Volume. Intensities and design storms vary widely by region and method.
<b>Design Storm Duration</b>	0	hours	Varies depending on geographical region. Set at 0 for pump system set up. LA County 3 hours. Call for details.

### MWS - Linear Sizing

<b>MWS - Linear Model Number</b> (from matrix)	MWS-L-8-12	quantity	Please choose size from "Model Size Matrix" Tab
<b># Of Units</b>	1	quantity	Select the number of systems required to treat the water quality volume. Will vary depending on drain down time regulations.
<b>Discharge Rate</b> (from matrix)	39.25	gallons/minute	Rate of 0.26 gpm/sq ft or 25 in/hr. Field Verified.

### Volume Treated During Event

Processed through MWS - Linear	0.0	cubic feet	<b>39.25 gals/minute</b>
--------------------------------	-----	------------	--------------------------

### Volume Treated Following Event

<b>MWS - Linear Static Capacity</b> (from matrix)	187	cubic feet	Set at zero to start. Size pre-storage system to hold this volume
<b>Volume Needed in Pre-Storage</b>	19848	cubic feet	

Sizing complete when equal to value of zero.

<b>TOTAL STORMWATER TREATED</b>	<b>20035</b>	<b>cubic feet</b>	Note: This amount should be equal to the "Water Quality Volume"
<b>Drain Down Time</b>	<b>63.81</b>	<b>hours</b>	Drain down time must be equal to or less than requirement of local jurisdiction. Default 48 hours.

Feel free to fax or email proposed sizing calculations to Modular Wetlands Systems, Inc. for assistance with sizing, compliance, and design.

Phone: 760.433.7640

Fax: 760.433.3176

Email: [Info@modularwetlands.com](mailto:Info@modularwetlands.com)

**Project Information:**

Project Name: First March Logistics - Building 1 (DMA B)  
 Location: Perris, CA  
 Date: 11/16/2021  
 Engineer: Thienes Engineering, Inc.  
 StormTech RPM:

**MC-4500 Site Calculator**

**System Requirements**


Units	Imperial	
Required Storage Volume	19848	CF
Stone Porosity (Industry Standard = 40%)	40	%
Stone Above Chambers (12 inch min.)	12	inches
Stone Foundation Depth (9 inch min.)	36	inches
Average Cover over Chambers (24 inch min.)	24	inches
Bed size controlled by WIDTH or LENGTH?	WIDTH	
Limiting WIDTH or LENGTH dimension	35	feet
Storage Volume per Chamber	195.5	CF
Storage Volume per End Cap	137.7	CF

**System Sizing**

Number of Chambers Required	98	each
Number of End Caps Required	6	each
Bed Size (including perimeter stone)	3,933	square feet
Stone Required (including perimeter stone)	1299	tons
Volume of Excavation	1457	cubic yards
Non-woven Filter Fabric Required (20% Safety Factor)	1453	square yards
Length of Isolator Row	139.9	feet
Woven Isolator Row Fabric (20% Safety Factor)	384	square yards
Installed Storage Volume	19,985	cubic feet

**Controlled by Width (Rows)**

Maximum Width =	35	feet
2 rows of	33	chambers
1 row of	32	chambers
Maximum Length =	139.9	feet
Maximum Width =	28.5	feet





# Appendix 7: Hydromodification

*Supporting Detail Relating to Hydrologic Conditions of Concern*

# HCOC MAP

**Legend**


-  HCOC EXEMPT
-  NOT HCOC EXEMPT

BUILDING 1  
STORMWATER  
RUNOFF  
ROUTED TO  
HCOC  
EXEMPTION  
AREA IN  
PROPOSED  
CONDITIONS

PROPOSED  
84" PUBLIC  
STORM  
DRAIN

INTERIM  
DETENTION BASIN  
OUTLET TO  
WESTERN WAY

Phase I - Interim  
Detention Basin



# Appendix 8: Source Control

*Pollutant Sources/Source Control Checklist*

## Appendix 9: O&M

*Operation and Maintenance Plan and Documentation of Finance, Maintenance and Recording Mechanisms*

# Appendix 10: Educational Materials

*BMP Fact Sheets, Maintenance Guidelines and Other End-User BMP Information*