

APPENDIX G

PRELIMINARY WATER QUALITY MANAGEMENT PLAN


Project Specific Water Quality Management Plan

*A Template for Projects located within the **Santa Ana Watershed** Region of Riverside County*

Project Title: Lowe's Distribution Center TI

Development No: 3984 Indian Ave
Perris, CA 92571

Design Review/Case No: P22-00011



Contact Information:

Prepared for: Lowe's Home Centers, LLC
1000 Lowes Boulevard
 Mooresville, NC 28117

Prepared by: Kimley-Horn & Associates
1100 W. Town & Country road, Suite 700
Orange, CA 92868

- Preliminary
- Final

Original Date Prepared: 4/23/2021


Revision Date(s): 07/22/2022

*Prepared for Compliance with
Regional Board Order No. **R8-2010-0033***

Template revised June 30, 2016

A Brief Introduction

This Project-Specific WQMP Template for the **Santa Ana Region** has been prepared to help guide you in documenting compliance for your project. Because this document has been designed to specifically document compliance, you will need to utilize the WQMP Guidance Document as your “how-to” manual to help guide you through this process. Both the Template and Guidance Document go hand-in-hand, and will help facilitate a well prepared Project-Specific WQMP. Below is a flowchart for the layout of this Template that will provide the steps required to document compliance.



OWNER'S CERTIFICATION

This Project-Specific Water Quality Management Plan (WQMP) has been prepared for Lowe's Home Centers, LLC by Kimley-Horn & Associates for the Lowes Parking Lot Expansion project, P22-00011.

This WQMP is intended to comply with the requirements of City of Perris for Ordinance No. 1194 which includes the requirement for the preparation and implementation of a Project-Specific WQMP.

The undersigned, while owning the property/project described in the preceding paragraph, shall be responsible for the implementation and funding of this WQMP and will ensure that this WQMP is amended as appropriate to reflect up-to-date conditions on the site. In addition, the property owner accepts responsibility for interim operation and maintenance of Stormwater BMPs until such time as this responsibility is formally transferred to a subsequent owner. This WQMP will be reviewed with the facility operator, facility supervisors, employees, tenants, maintenance and service contractors, or any other party (or parties) having responsibility for implementing portions of this WQMP. At least one copy of this WQMP will be maintained at the project site or project office in perpetuity. The undersigned is authorized to certify and to approve implementation of this WQMP. The undersigned is aware that implementation of this WQMP is enforceable under City of Perris Water Quality Ordinance (Municipal Code Section 14.22).

"I, the undersigned, certify under penalty of law that the provisions of this WQMP have been reviewed and accepted and that the WQMP will be transferred to future successors in interest."

Owner's Signature

Date

Owner's Printed Name

Owner's Title/Position

PREPARER'S CERTIFICATION

"The selection, sizing and design of stormwater treatment and other stormwater quality and quantity control measures in this plan meet the requirements of Regional Water Quality Control Board Order No. **R8-2010-0033** and any subsequent amendments thereto."

Preparer's Signature

Date

Preparer's Printed Name

Preparer's Title/Position

Preparer's Licensure:

Table of Contents

Section A: Project and Site Information	6
A.1 Maps and Site Plans.....	7
A.2 Identify Receiving Waters.....	7
A.3 Additional Permits/Approvals required for the Project:	7
Section B: Optimize Site Utilization (LID Principles)	9
Section C: Delineate Drainage Management Areas (DMAs).....	11
Section D: Implement LID BMPs	13
D.1 Infiltration Applicability	13
D.2 Harvest and Use Assessment	14
D.3 Bioretention and Biotreatment Assessment.....	16
D.4 Feasibility Assessment Summaries.....	17
D.5 LID BMP Sizing	18
Section E: Alternative Compliance (LID Waiver Program)	19
E.1 Identify Pollutants of Concern	20
E.2 Stormwater Credits.....	21
E.3 Sizing Criteria	21
E.4 Treatment Control BMP Selection	22
Section F: Hydromodification	23
F.1 Hydrologic Conditions of Concern (HCOC) Analysis.....	23
F.2 HCOC Mitigation	24
Section G: Source Control BMPs.....	25
Section H: Construction Plan Checklist	27
Section I: Operation, Maintenance and Funding.....	28

List of Tables

Table A.1 Identification of Receiving Waters.....	7
Table A.2 Other Applicable Permits.....	7
Table C.1 DMA Classifications.....	11
Table C.2 Type 'A', Self-Treating Areas.....	11
Table C.3 Type 'B', Self-Retaining Areas.....	11
Table C.4 Type 'C', Areas that Drain to Self-Retaining Areas.....	12
Table C.5 Type 'D', Areas Draining to BMPs.....	12
Table D.1 Infiltration Feasibility.....	13
Table D.2 LID Prioritization Summary Matrix.....	17
Table D.3 DCV Calculations for LID BMPs.....	18
Table E.1 Potential Pollutants by Land Use Type.....	20
Table E.2 Water Quality Credits.....	21
Table E.3 Treatment Control BMP Sizing.....	21
Table E.4 Treatment Control BMP Selection.....	22
Table F.1 Hydrologic Conditions of Concern Summary.....	23
Table G.1 Permanent and Operational Source Control Measures.....	25
Table H.1 Construction Plan Cross-reference.....	27

List of Appendices

Appendix 1: Maps and Site Plans.....	29
Appendix 2: Construction Plans.....	30
Appendix 3: Soils Information.....	31
Appendix 4: Historical Site Conditions.....	32
Appendix 5: LID Infeasibility.....	33
Appendix 6: BMP Design Details.....	34
Appendix 7: Hydromodification.....	35
Appendix 8: Source Control.....	36
Appendix 9: O&M.....	38
Appendix 10: Educational Materials.....	39

Section A: Project and Site Information

PROJECT INFORMATION	
Type of Project:	Commercial
Planning Area:	
Community Name:	City of Perris
Development Name:	Lowes Distribution Center TI - Perris
PROJECT LOCATION	
Latitude & Longitude (DMS): 33°50'22.70"N, 117°13'57.83"W	
Project Watershed and Sub-Watershed: Santa Ana Watershed, San Jacinto Sub-Watershed	
Gross Acres: 107.71	
APN(s): 303-03-0019, 303-06-0016 & 303-07-0007	
Map Book and Page No.: 014/668 and 017/023	
PROJECT CHARACTERISTICS	
Proposed or Potential Land Use(s)	Commercial
Proposed or Potential SIC Code(s)	4225
Area of Impervious Project Footprint (SF)	536,117
Total Area of <u>proposed</u> Impervious Surfaces within the Project Footprint (SF)/or Replacement	396,741
Does the project consist of offsite road improvements?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
Does the project propose to construct unpaved roads?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
Is the project part of a larger common plan of development (phased project)?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
EXISTING SITE CHARACTERISTICS	
Total area of <u>existing</u> Impervious Surfaces within the Project limits Footprint (SF)	0
Is the project located within any MSHCP Criteria Cell?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
If so, identify the Cell number:	N/A
Are there any natural hydrologic features on the project site?	<input type="checkbox"/> Y <input checked="" type="checkbox"/> N
Is a Geotechnical Report attached?	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N
If no Geotech. Report, list the NRCS soils type(s) present on the site (A, B, C and/or D)	A
What is the Water Quality Design Storm Depth for the project?	0.65 in
<p>Proposed project includes the expansion of an existing Lowe's Distribution parking lot in Perris, CA. Existing site covers 107.7 acres and consists of a Lowe's distribution building, parking lot, open space, (2) detention basins, and a vacant lot, and the existing building site is covered by a separate WQMP. The project proposes to expand the existing parking lot into the vacant lot to the east, consisting of 536,117 SF, or 12.31 acres. Approximately 396,741 SF will be impervious pavement, 119,075 SF will be landscaping, and 20,300 SF will be self-treating landscaping along Indian Avenue. The site is bounded by Ramona Expressway to the north, Indian Avenue to the east, Morgan Street to the south, and Brennan Avenue to the west. Vacant lot lies along the Indian Ave frontage. Site is located within the Perris Valley Master Drainage Plan (MDP).</p> <p>Project proposes to maintain drainage to the existing storm drain culvert connection at the northeasterly end of the vacant lot, which outlets to a 235,787 CF existing detention basin system. To treat the required volume and mitigate peak flows, the project proposes an above ground infiltration basin and outlet structure that is sized to retain and infiltrate the required DCV onsite. Prior to entering the above ground basin, stormwater runoff will be</p>	

pretreated via a proprietary hydrodynamic separator (ADS Barracuda). A small portion of the site towards the east along Indian Avenue will be self-treating. See the exhibits in Appendix 1 for more information.

Since the project boundary is surrounded by the existing curb and gutter, there will be no offsite runoff.

A.1 Maps and Site Plans

When completing your Project-Specific WQMP, include a map of the local vicinity and existing site. In addition, include all grading, drainage, landscape/plant palette and other pertinent construction plans in Appendix 2. At a **minimum**, your WQMP Site Plan should include the following:

- Drainage Management Areas
- Proposed Structural BMPs
- Drainage Path
- Drainage Infrastructure, Inlets, Overflows
- Source Control BMPs
- Buildings, Roof Lines, Downspouts
- Impervious Surfaces
- Standard Labeling
- BMP Locations (Lat/Long)

Use your discretion on whether or not you may need to create multiple sheets or can appropriately accommodate these features on one or two sheets. Keep in mind that the Co-Permittee plan reviewer must be able to easily analyze your project utilizing this template and its associated site plans and maps.

A.2 Identify Receiving Waters

Using Table A.1 below, list in order of upstream to downstream, the receiving waters that the project site is tributary to. Continue to fill each row with the Receiving Water's 303(d) listed impairments (if any), designated beneficial uses, and proximity, if any, to a RARE beneficial use. Include a map of the receiving waters in Appendix 1.

Table A.1 Identification of Receiving Waters

Receiving Waters	EPA Approved 303(d) List Impairments	Designated Beneficial Uses	Proximity to RARE Beneficial Use
Perris Valley MDP Line E	None	-	No RARE uses identified in receiving waters
Perris Valley Channel	None	-	No RARE uses identified in receiving waters
San Jacinto River Reach 3	None	MUN, AGR, IND, PROC	No RARE uses identified in receiving waters
Canyon Lake	Nutrients	WILD, REC2, WARM, GWR, REC1, AGR	No RARE uses identified in receiving waters
San Jacinto River Reach 1	None	AGR, GWR	No RARE uses identified in receiving waters
Lake Elsinore	DDT, Nutrients, Organic Enrichment/Low Dissolved Oxygen, PCBs (Polychlorinated Biphenyls), toxicity	MUN, REC1, REC2, WARM, WILD	No RARE uses identified in receiving waters

A.3 Additional Permits/Approvals required for the Project:

Table A.2 Other Applicable Permits

Agency	Permit Required	
State Department of Fish and Game, 1602 Streambed Alteration Agreement	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
State Water Resources Control Board, Clean Water Act (CWA) Section 401 Water Quality Cert.	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
US Army Corps of Engineers, CWA Section 404 Permit	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
US Fish and Wildlife, Endangered Species Act Section 7 Biological Opinion	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
Statewide Construction General Permit Coverage	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N
Statewide Industrial General Permit Coverage	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N
Western Riverside MSHCP Consistency Approval (e.g., JPR, DBESP)	<input type="checkbox"/> Y	<input checked="" type="checkbox"/> N
Other <i>(please list in the space below as required)</i> City of Perris Building & Grading Permits	<input checked="" type="checkbox"/> Y	<input type="checkbox"/> N

If yes is answered to any of the questions above, the Co-Permittee may require proof of approval/coverage from those agencies as applicable including documentation of any associated requirements that may affect this Project-Specific WQMP.

Section B: Optimize Site Utilization (LID Principles)

Review of the information collected in Section 'A' will aid in identifying the principal constraints on site design and selection of LID BMPs as well as opportunities to reduce imperviousness and incorporate LID Principles into the site and landscape design. For example, **constraints** might include impermeable soils, high groundwater, groundwater pollution or contaminated soils, steep slopes, geotechnical instability, high-intensity land use, heavy pedestrian or vehicular traffic, utility locations or safety concerns. **Opportunities** might include existing natural areas, low areas, oddly configured or otherwise unbuildable parcels, easements and landscape amenities including open space and buffers (which can double as locations for bioretention BMPs), and differences in elevation (which can provide hydraulic head). Prepare a brief narrative for each of the site optimization strategies described below. This narrative will help you as you proceed with your LID design and explain your design decisions to others.

The 2010 Santa Ana MS4 Permit further requires that LID Retention BMPs (Infiltration Only or Harvest and Use) be used unless it can be shown that those BMPs are infeasible. Therefore, it is important that your narrative identify and justify if there are any constraints that would prevent the use of those categories of LID BMPs. Similarly, you should also note opportunities that exist which will be utilized during project design. Upon completion of identifying Constraints and Opportunities, include these on your WQMP Site plan in Appendix 1.

Consideration of "highest and best use" of the discharge should also be considered. For example, Lake Elsinore is evaporating faster than runoff from natural precipitation can recharge it. Requiring infiltration of 85% of runoff events for projects tributary to Lake Elsinore would only exacerbate current water quality problems associated with Pollutant concentration due to lake water evaporation. In cases where rainfall events have low potential to recharge Lake Elsinore (i.e. no hydraulic connection between groundwater to Lake Elsinore, or other factors), requiring infiltration of Urban Runoff from projects is counterproductive to the overall watershed goals. Project proponents, in these cases, would be allowed to discharge Urban Runoff, provided they used equally effective filtration-based BMPs.

Site Optimization

The following questions are based upon Section 3.2 of the WQMP Guidance Document. Review of the WQMP Guidance Document will help you determine how best to optimize your site and subsequently identify opportunities and/or constraints, and document compliance.

Did you identify and preserve existing drainage patterns? If so, how? If not, why?

Yes, in the existing condition, surface runoff predominantly flows in the northeasterly direction to an existing drain inlet and storm drain culvert. Proposed grading and storm drain system will maintain this pattern, with the storm drain connecting to the existing SD culvert.

Did you identify and protect existing vegetation? If so, how? If not, why?

In the existing condition, the project site is mostly barren and has minimal effects on local plant life. Proposed development will contain pervious areas that will be landscaped.

Did you identify and preserve natural infiltration capacity? If so, how? If not, why?

Per the infiltration study prepared by Terracon Consultants, Inc., the site is deemed feasible for infiltration. The project proposes an above ground infiltration basin to maximize natural infiltration and water quality treatment.

- *Avg. Infiltration rate: 1.17 in/hr (Per Geotechnical Report)*

Did you identify and minimize impervious area? If so, how? If not, why?

Due to the nature of the project, the majority of the new construction will be impervious area. Landscaped parking medians/islands are proposed throughout the project site. Moreover, site frontage along Indian Avenue will be landscaped.

Did you identify and disperse runoff to adjacent pervious areas? If so, how? If not, why?

Due to the nature of the project, the majority of the runoff will be directed to a catch basin within the parking lot. However, storm drainage will be directed to an above ground basin where the required treatment volume can be infiltrated. Moreover, frontage area along Indian Avenue will be landscaped and self-treating.

Section C: Delineate Drainage Management Areas (DMAs)

Utilizing the procedure in Section 3.3 of the WQMP Guidance Document which discusses the methods of delineating and mapping your project site into individual DMAs, complete Table C.1 below to appropriately categorize the types of classification (e.g., Type A, Type B, etc.) per DMA for your project site. Upon completion of this table, this information will then be used to populate and tabulate the corresponding tables for their respective DMA classifications.

Table C.1 DMA Classifications

DMA Name or ID	Surface Type(s) ¹²	Area (Sq. Ft.)	DMA Type
DMA A	Concrete or Asphalt Ornamental Landscaping	396,741 119,075	D
DMA B	Ornamental Landscaping	20,300	A

¹Reference Table 2-1 in the WQMP Guidance Document to populate this column

²If multi-surface provide back-up

Table C.2 Type 'A', Self-Treating Areas

DMA Name or ID	Area (Sq. Ft.)	Stabilization Type	Irrigation Type (if any)
DMA B	20,300	Vegetation	On-site sprinklers

Table C.3 Type 'B', Self-Retaining Areas

Self-Retaining Area				Type 'C' DMAs that are draining to the Self-Retaining Area		
DMA Name/ ID	Post-project surface type	Area (square feet)	Storm Depth (inches)	DMA Name / ID	[C] from Table C.4	Required Retention Depth (inches)
		[A]	[B]		= [C]	[D]

$$[D] = [B] + \frac{[B] \cdot [C]}{[A]}$$

Table C.4 Type 'C', Areas that Drain to Self-Retaining Areas

DMA					Receiving Self-Retaining DMA		
DMA Name/ ID	Area (square feet)	Post-project surface type	Impervious fraction	Product	DMA name /ID	Area (square feet)	Ratio
	[A]		[B]	[C] = [A] x [B]		[D]	[C]/[D]

Table C.5 Type 'D', Areas Draining to BMPs

DMA Name or ID	BMP Name or ID
DMA A	Above Ground Basin #1

Note: More than one drainage management area can drain to a single LID BMP, however, one drainage management area may not drain to more than one BMP.

Section D: Implement LID BMPs

D.1 Infiltration Applicability

Is there an approved downstream ‘Highest and Best Use’ for stormwater runoff (see discussion in Chapter 2.4.4 of the WQMP Guidance Document for further details)? Y N

If yes has been checked, Infiltration BMPs shall not be used for the site; proceed to section D.3

If no, continue working through this section to implement your LID BMPs. It is recommended that you contact your Co-Permittee to verify whether or not your project discharges to an approved downstream ‘Highest and Best Use’ feature.

Geotechnical Report

A Geotechnical Report or Phase I Environmental Site Assessment may be required by the Copermitee to confirm present and past site characteristics that may affect the use of Infiltration BMPs. In addition, the Co-Permittee, at their discretion, may not require a geotechnical report for small projects as described in Chapter 2 of the WQMP Guidance Document. If a geotechnical report has been prepared, include it in Appendix 3. In addition, if a Phase I Environmental Site Assessment has been prepared, include it in Appendix 4.

Is this project classified as a small project consistent with the requirements of Chapter 2 of the WQMP Guidance Document? Y N

Infiltration Feasibility

Table D.1 below is meant to provide a simple means of assessing which DMAs on your site support Infiltration BMPs and is discussed in the WQMP Guidance Document in Chapter 2.4.5. Check the appropriate box for each question and then list affected DMAs as applicable. If additional space is needed, add a row below the corresponding answer.

Table D.1 Infiltration Feasibility

Does the project site...	YES	NO
...have any DMAs with a seasonal high groundwater mark shallower than 10 feet? If Yes, list affected DMAs:		X
...have any DMAs located within 100 feet of a water supply well? If Yes, list affected DMAs:		X
...have any areas identified by the geotechnical report as posing a public safety risk where infiltration of stormwater could have a negative impact? If Yes, list affected DMAs:		X
...have measured in-situ infiltration rates of less than 1.6 inches / hour? If Yes, list affected DMAs:		X
...have significant cut and/or fill conditions that would preclude in-situ testing of infiltration rates at the final infiltration surface? If Yes, list affected DMAs:		X
...geotechnical report identify other site-specific factors that would preclude effective and safe infiltration? Describe here:		X

If you answered “Yes” to any of the questions above for any DMA, Infiltration BMPs should not be used for those DMAs and you should proceed to the assessment for Harvest and Use below.

D.2 Harvest and Use Assessment

Please check what applies:

- Reclaimed water will be used for the non-potable water demands for the project.
- Downstream water rights may be impacted by Harvest and Use as approved by the Regional Board (verify with the Copermittee).
- The Design Capture Volume will be addressed using Infiltration Only BMPs. In such a case, Harvest and Use BMPs are still encouraged, but it would not be required if the Design Capture Volume will be infiltrated or evapotranspired.

If any of the above boxes have been checked, Harvest and Use BMPs need not be assessed for the site. If none of the above criteria applies, follow the steps below to assess the feasibility of irrigation use, toilet use and other non-potable uses (e.g., industrial use).

Irrigation Use Feasibility

Complete the following steps to determine the feasibility of harvesting stormwater runoff for Irrigation Use BMPs on your site:

Step 1: Identify the total area of irrigated landscape on the site, and the type of landscaping used.

Total Area of Irrigated Landscape: Insert Area (Acres)

Type of Landscaping (Conservation Design or Active Turf): List Landscaping Type

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for irrigation use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

Total Area of Impervious Surfaces: Insert Area (Acres)

Step 3: Cross reference the Design Storm depth for the project site (see Exhibit A of the WQMP Guidance Document) with the left column of Table 2-3 in Chapter 2 to determine the minimum area of Effective Irrigated Area per Tributary Impervious Area (EIATIA).

Enter your EIATIA factor: EIATIA Factor

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum irrigated area that would be required.

Minimum required irrigated area: Insert Area (Acres)

Step 5: Determine if harvesting stormwater runoff for irrigation use is feasible for the project by comparing the total area of irrigated landscape (Step 1) to the minimum required irrigated area (Step 4).

Minimum required irrigated area (Step 4)	Available Irrigated Landscape (Step 1)
Insert Area (Acres)	Insert Area (Acres)

Toilet Use Feasibility

Complete the following steps to determine the feasibility of harvesting stormwater runoff for toilet flushing uses on your site:

Step 1: Identify the projected total number of daily toilet users during the wet season, and account for any periodic shut downs or other lapses in occupancy:

Projected Number of Daily Toilet Users: Number of daily Toilet Users

Project Type: Enter 'Residential', 'Commercial', 'Industrial' or 'Schools'

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for toilet use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

Total Area of Impervious Surfaces: Insert Area (Acres)

Step 3: Enter the Design Storm depth for the project site (see Exhibit A) into the left column of Table 2-2 in Chapter 2 to determine the minimum number of toilet users per tributary impervious acre (TUTIA).

Enter your TUTIA factor: TUTIA Factor

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum number of toilet users that would be required.

Minimum number of toilet users: Required number of toilet users

Step 5: Determine if harvesting stormwater runoff for toilet flushing use is feasible for the project by comparing the Number of Daily Toilet Users (Step 1) to the minimum required number of toilet users (Step 4).

Minimum required Toilet Users (Step 4)	Projected number of toilet users (Step 1)
Insert Area (Acres)	Insert Area (Acres)

Other Non-Potable Use Feasibility

Are there other non-potable uses for stormwater runoff on the site (e.g. industrial use)? See Chapter 2 of the Guidance for further information. If yes, describe below. If no, write N/A.

Insert narrative description here.

Step 1: Identify the projected average daily non-potable demand, in gallons per day, during the wet season and accounting for any periodic shut downs or other lapses in occupancy or operation.

Average Daily Demand: Projected Average Daily Use (gpd)

Step 2: Identify the planned total of all impervious areas on the proposed project from which runoff might be feasibly captured and stored for the identified non-potable use. Depending on the configuration of buildings and other impervious areas on the site, you may consider the site as a whole, or parts of the site, to evaluate reasonable scenarios for capturing and storing runoff and directing the stored runoff to the potential use(s) identified in Step 1 above.

Total Area of Impervious Surfaces: Insert Area (Acres)

Step 3: Enter the Design Storm depth for the project site (see Exhibit A) into the left column of Table 2-4 in Chapter 2 to determine the minimum demand for non-potable uses per tributary impervious acre.

Enter the factor from Table 2-4: Enter Value

Step 4: Multiply the unit value obtained from Step 3 by the total of impervious areas from Step 2 to develop the minimum number of gallons per day of non-potable use that would be required.

Minimum required use: Minimum use required (gpd)

Step 5: Determine if harvesting stormwater runoff for other non-potable use is feasible for the project by comparing the projected average daily use (Step 1) to the minimum required non-potable use (Step 4).

Minimum required non-potable use (Step 4)	Projected average daily use (Step 1)
Minimum use required (gpd)	Projected Average Daily Use (gpd)

If Irrigation, Toilet and Other Use feasibility anticipated demands are less than the applicable minimum values, Harvest and Use BMPs are not required and you should proceed to utilize LID Bioretention and Biotreatment per Section 3.4.2 of the WQMP Guidance Document.

D.3 Bioretention and Biotreatment Assessment

Other LID Bioretention and Biotreatment BMPs as described in Chapter 2.4.7 of the WQMP Guidance Document are feasible on nearly all development sites with sufficient advance planning.

Select one of the following:

- LID Bioretention/Biotreatment BMPs will be used for some or all DMAs of the project as noted below in Section D.4 (note the requirements of Section 3.4.2 in the WQMP Guidance Document).
- A site-specific analysis demonstrating the technical infeasibility of all LID BMPs has been performed and is included in Appendix 5. If you plan to submit an analysis demonstrating the technical infeasibility of LID BMPs, request a pre-submittal meeting with the Copermittee to discuss this option. Proceed to Section E to document your alternative compliance measures.

D.4 Feasibility Assessment Summaries

From the Infiltration, Harvest and Use, Bioretention and Biotreatment Sections above, complete Table D.2 below to summarize which LID BMPs are technically feasible, and which are not, based upon the established hierarchy.

Table D.2 LID Prioritization Summary Matrix

DMA Name/ID	LID BMP Hierarchy				No LID (Alternative Compliance)
	1. Infiltration	2. Harvest and use	3. Bioretention	4. Biotreatment	
DMA A	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

For those DMAs where LID BMPs are not feasible, provide a brief narrative below summarizing why they are not feasible, include your technical infeasibility criteria in Appendix 5, and proceed to Section E below to document Alternative Compliance measures for those DMAs. Recall that each proposed DMA must pass through the LID BMP hierarchy before alternative compliance measures may be considered.

D.5 LID BMP Sizing

Each LID BMP must be designed to ensure that the Design Capture Volume will be addressed by the selected BMPs. First, calculate the Design Capture Volume for each LID BMP using the V_{BMP} worksheet in Appendix F of the LID BMP Design Handbook. Second, design the LID BMP to meet the required V_{BMP} using a method approved by the Copermittee. Utilize the worksheets found in the LID BMP Design Handbook or consult with your Copermittee to assist you in correctly sizing your LID BMPs. Complete Table D.3 below to document the Design Capture Volume and the Proposed Volume for each LID BMP. Provide the completed design procedure sheets for each LID BMP in Appendix 6. You may add additional rows to the table below as needed.

Table D.3 DCV Calculations for LID BMPs

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Impervious Fraction, f_i	DMA Runoff Factor	DMA Areas x Runoff Factor	Above-Ground Infiltration Basin		
						Design Storm Depth (in)	Design Capture Volume, V_{BMP} (cubic feet)	Proposed Volume on Plans (cubic feet)
	[A]		[B]	[C]	[A] x [C]			
DMA A - Impervious	396,741	Concrete or Asphalt	1	0.89	353,893			
DMA A - Pervious	119,075	Ornamental Landscape	0.1	0.11	13,152.8			
	515,816				367,045.8	0.65	19,881.6	29,113

[B], [C] is obtained as described in Section 2.3.1 of the WQMP Guidance Document

[E] is obtained from Exhibit A in the WQMP Guidance Document

[G] is obtained from a design procedure sheet, such as in LID BMP Design Handbook and placed in Appendix 6

Section E: Alternative Compliance (LID Waiver Program)

LID BMPs are expected to be feasible on virtually all projects. Where LID BMPs have been demonstrated to be infeasible as documented in Section D, other Treatment Control BMPs must be used (subject to LID waiver approval by the Copermittee). Check one of the following Boxes:

LID Principles and LID BMPs have been incorporated into the site design to fully address all Drainage Management Areas. No alternative compliance measures are required for this project and thus this Section is not required to be completed.

- Or -

The following Drainage Management Areas are unable to be addressed using LID BMPs. A site-specific analysis demonstrating technical infeasibility of LID BMPs has been approved by the Co-Permittee and included in Appendix 5. Additionally, no downstream regional and/or sub-regional LID BMPs exist or are available for use by the project. The following alternative compliance measures on the following pages are being implemented to ensure that any pollutant loads expected to be discharged by not incorporating LID BMPs, are fully mitigated.

E.1 Identify Pollutants of Concern

Utilizing Table A.1 from Section A above which noted your project's receiving waters and their associated EPA approved 303(d) listed impairments, cross reference this information with that of your selected Priority Development Project Category in Table E.1 below. If the identified General Pollutant Categories are the same as those listed for your receiving waters, then these will be your Pollutants of Concern and the appropriate box or boxes will be checked on the last row. The purpose of this is to document compliance and to help you appropriately plan for mitigating your Pollutants of Concern in lieu of implementing LID BMPs.

Table E.1 Potential Pollutants by Land Use Type

Priority Development Project Categories and/or Project Features (check those that apply)	General Pollutant Categories							
	Bacterial Indicators	Metals	Nutrients	Pesticides	Toxic Organic Compounds	Sediments	Trash & Debris	Oil & Grease
<input type="checkbox"/> Detached Residential Development	P	N	P	P	N	P	P	P
<input type="checkbox"/> Attached Residential Development	P	N	P	P	N	P	P	P ⁽²⁾
<input type="checkbox"/> Commercial/Industrial Development	P ⁽³⁾	P	P ⁽¹⁾	P ⁽¹⁾	P ⁽⁵⁾	P ⁽¹⁾	P	P
<input type="checkbox"/> Automotive Repair Shops	N	P	N	N	P ^(4, 5)	N	P	P
<input type="checkbox"/> Restaurants (>5,000 ft ²)	P	N	N	N	N	N	P	P
<input type="checkbox"/> Hillside Development (>5,000 ft ²)	P	N	P	P	N	P	P	P
<input checked="" type="checkbox"/> Parking Lots (>5,000 ft ²)	P ⁽⁶⁾	P	P ⁽¹⁾	P ⁽¹⁾	P ⁽⁴⁾	P ⁽¹⁾	P	P
<input type="checkbox"/> Retail Gasoline Outlets	N	P	N	N	P	N	P	P
Project Priority Pollutant(s) of Concern	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>

P = Potential

N = Not Potential

⁽¹⁾ A potential Pollutant if non-native landscaping exists or is proposed onsite; otherwise not expected

⁽²⁾ A potential Pollutant if the project includes uncovered parking areas; otherwise not expected

⁽³⁾ A potential Pollutant is land use involving animal waste

⁽⁴⁾ Specifically petroleum hydrocarbons

⁽⁵⁾ Specifically solvents

⁽⁶⁾ Bacterial indicators are routinely detected in pavement runoff

E.2 Stormwater Credits (N/A)

Projects that cannot implement LID BMPs but nevertheless implement smart growth principles are potentially eligible for Stormwater Credits. Utilize Table 3-8 within the WQMP Guidance Document to identify your Project Category and its associated Water Quality Credit. If not applicable, write N/A.

Table E.2 Water Quality Credits

Qualifying Project Categories	Credit Percentage ²
<i>Total Credit Percentage¹</i>	

¹Cannot Exceed 50%

²Obtain corresponding data from Table 3-8 in the WQMP Guidance Document

E.3 Sizing Criteria (N/A)

After you appropriately considered Stormwater Credits for your project, utilize Table E.3 below to appropriately size them to the DCV, or Design Flow Rate, as applicable. Please reference Chapter 3.5.2 of the WQMP Guidance Document for further information.

Table E.3 Treatment Control BMP Sizing

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Impervious Fraction, I _f	DMA Runoff Factor	DMA Area x Runoff Factor	Enter BMP Name / Identifier Here			
	[A]		[B]	[C]	[A] x [C]				
						<i>Design Storm Depth (in)</i>	<i>Minimum Design Capture Volume or Design Flow Rate (cubic feet or cfs)</i>	<i>Total Storm Water Credit % Reduction</i>	<i>Proposed Volume or Flow on Plans (cubic feet or cfs)</i>
	$A_T = \sum[A]$				$\Sigma = [D]$	[E]	$[F] = \frac{[D] \times [E]}{[G]}$	$[F] \times (1-[H])$	[I]

[B], [C] is obtained as described in Section 2.3.1 from the WQMP Guidance Document

[E] is for Flow-Based Treatment Control BMPs [E] = .2, for Volume-Based Control Treatment BMPs, [E] obtained from Exhibit A in the WQMP Guidance Document

[G] is for Flow-Based Treatment Control BMPs [G] = 43,560, for Volume-Based Control Treatment BMPs, [G] = 12

[H] is from the Total Credit Percentage as Calculated from Table E.2 above

[I] as obtained from a design procedure sheet from the BMP manufacturer and should be included in Appendix 6

E.4 Treatment Control BMP Selection (N/A)

Treatment Control BMPs typically provide proprietary treatment mechanisms to treat potential pollutants in runoff, but do not sustain significant biological processes. Treatment Control BMPs must have a removal efficiency of a medium or high effectiveness as quantified below:

- **High:** equal to or greater than 80% removal efficiency
- **Medium:** between 40% and 80% removal efficiency

Such removal efficiency documentation (e.g., studies, reports, etc.) as further discussed in Chapter 3.5.2 of the WQMP Guidance Document, must be included in Appendix 6. In addition, ensure that proposed Treatment Control BMPs are properly identified on the WQMP Site Plan in Appendix 1.

Table E.4 Treatment Control BMP Selection

Selected Treatment Control BMP Name or ID ¹	Priority Concern to Mitigate ²	Pollutant(s) of	Removal Percentage ³	Efficiency

¹ Treatment Control BMPs must not be constructed within Receiving Waters. In addition, a proposed Treatment Control BMP may be listed more than once if they possess more than one qualifying pollutant removal efficiency.

² Cross Reference Table E.1 above to populate this column.

³ As documented in a Co-Permittee Approved Study and provided in Appendix 6.

Section F: Hydromodification

F.1 Hydrologic Conditions of Concern (HCOC) Analysis

Once you have determined that the LID design is adequate to address water quality requirements, you will need to assess if the proposed LID Design may still create a HCOC. Review Chapters 2 and 3 (including Figure 3-7) of the WQMP Guidance Document to determine if your project must mitigate for Hydromodification impacts. If your project meets one of the following criteria which will be indicated by the check boxes below, you do not need to address Hydromodification at this time. However, if the project does not qualify for Exemptions 1, 2 or 3, then additional measures must be added to the design to comply with HCOC criteria. This is discussed in further detail below in Section F.2.

HCOC EXEMPTION 1: The Priority Development Project disturbs less than one acre. The Copermitttee has the discretion to require a Project-Specific WQMP to address HCOCs on projects less than one acre on a case by case basis. The disturbed area calculation should include all disturbances associated with larger common plans of development.

Does the project qualify for this HCOC Exemption? Y N

If Yes, HCOC criteria do not apply.

HCOC EXEMPTION 2: The volume and time of concentration¹ of storm water runoff for the post-development condition is not significantly different from the pre-development condition for a 2-year return frequency storm (a difference of 5% or less is considered insignificant) using one of the following methods to calculate:

- Riverside County Hydrology Manual
- Technical Release 55 (TR-55): Urban Hydrology for Small Watersheds (NRCS 1986), or derivatives thereof, such as the Santa Barbara Urban Hydrograph Method
- Other methods acceptable to the Co-Permittee

Does the project qualify for this HCOC Exemption? Y N

If Yes, report results in Table F.1 below and provide your substantiated hydrologic analysis in Appendix 7.

Table F.1 Hydrologic Conditions of Concern Summary

	2 year – 24 hour		
	Pre-condition	Post-condition	% Difference
Time of Concentration	N/A	N/A	N/A
Volume (Cubic Feet)	N/A	N/A	N/A

¹ Time of concentration is defined as the time after the beginning of the rainfall when all portions of the drainage basin are contributing to flow at the outlet.

HCOC EXEMPTION 3: All downstream conveyance channels to an adequate sump (for example, Prado Dam, Lake Elsinore, Canyon Lake, Santa Ana River, or other lake, reservoir or naturally erosion resistant feature) that will receive runoff from the project are engineered and regularly maintained to ensure design flow capacity; no sensitive stream habitat areas will be adversely affected; or are not identified on the Co-Permittees Hydromodification Susceptibility Maps.

Does the project qualify for this HCOC Exemption? Y N

If Yes, HCOC criteria do not apply and note below which adequate sump applies to this HCOC qualifier:

F.2 HCOC Mitigation

If none of the above HCOC Exemption Criteria are applicable, HCOC criteria is considered mitigated if they meet one of the following conditions:

- a. Additional LID BMPS are implemented onsite or offsite to mitigate potential erosion or habitat impacts as a result of HCOCs. This can be conducted by an evaluation of site-specific conditions utilizing accepted professional methodologies published by entities such as the California Stormwater Quality Association (CASQA), the Southern California Coastal Water Research Project (SCCRWP), or other Co-Permittee approved methodologies for site-specific HCOC analysis.
- b. The project is developed consistent with an approved Watershed Action Plan that addresses HCOC in Receiving Waters.
- c. Mimicking the pre-development hydrograph with the post-development hydrograph, for a 2-year return frequency storm. Generally, the hydrologic conditions of concern are not significant, if the post-development hydrograph is no more than 10% greater than pre-development hydrograph. In cases where excess volume cannot be infiltrated or captured and reused, discharge from the site must be limited to a flow rate no greater than 110% of the pre-development 2-year peak flow.

Be sure to include all pertinent documentation used in your analysis of the items a, b or c in Appendix 7.

The project is located within a Hydromodification Exemption Area within the Riverside County WAP Mapping Tool as approved April 20, 2017.

Section G: Source Control BMPs

Source control BMPs include permanent, structural features that may be required in your project plans — such as roofs over and berms around trash and recycling areas — and Operational BMPs, such as regular sweeping and “housekeeping”, that must be implemented by the site’s occupant or user. The MEP standard typically requires both types of BMPs. In general, Operational BMPs cannot be substituted for a feasible and effective permanent BMP. Using the Pollutant Sources/Source Control Checklist in Appendix 8, review the following procedure to specify Source Control BMPs for your site:

1. **Identify Pollutant Sources:** Review Column 1 in the Pollutant Sources/Source Control Checklist. Check off the potential sources of Pollutants that apply to your site.
2. **Note Locations on Project-Specific WQMP Exhibit:** Note the corresponding requirements listed in Column 2 of the Pollutant Sources/Source Control Checklist. Show the location of each Pollutant source and each permanent Source Control BMP in your Project-Specific WQMP Exhibit located in Appendix 1.
3. **Prepare a Table and Narrative:** Check off the corresponding requirements listed in Column 3 in the Pollutant Sources/Source Control Checklist. In the left column of Table G.1 below, list each potential source of runoff Pollutants on your site (from those that you checked in the Pollutant Sources/Source Control Checklist). In the middle column, list the corresponding permanent, Structural Source Control BMPs (from Columns 2 and 3 of the Pollutant Sources/Source Control Checklist) used to prevent Pollutants from entering runoff. **Add additional narrative** in this column that explains any special features, materials or methods of construction that will be used to implement these permanent, Structural Source Control BMPs.
4. **Identify Operational Source Control BMPs:** To complete your table, refer once again to the Pollutant Sources/Source Control Checklist. List in the right column of your table the Operational BMPs that should be implemented as long as the anticipated activities continue at the site. Copermittee stormwater ordinances require that applicable Source Control BMPs be implemented; the same BMPs may also be required as a condition of a use permit or other revocable Discretionary Approval for use of the site.

Table G.1 Permanent and Operational Source Control Measures

Potential Sources of Runoff pollutants	Permanent Structural Source Control BMPs	Operational Source Control BMPs
On-Site Storm Drain Inlets	Mark all inlets with the words “Only Rain Down the Storm Drain” or similar. Catch basin markers may be available from the Riverside County Flood Control and Water Conservation District, Call 951.955.1200 to verify.	<ul style="list-style-type: none"> • Maintain and periodically repaint or replace inlet markings • Provide stormwater pollution prevention information to new site owners, lessees, or operators. • See applicable operational BMPs in the Fact Sheet SC-44, Drainage System Maintenance,” in the CAQA Stormwater Quality Handbooks at www.cabmphandbooks.com • Include the following in lease agreements: “Tenant shall not allow anyone to discharge anything to storm drains or to store or deposit materials so as to create a potential discharge to storm drains.”
Plazas, sidewalks, and parking Lots	Documentation of such sweeping shall be kept by the owner. Frequency of sweeping shall be adjusted as needed to maintain a clean site.	<ul style="list-style-type: none"> • Sweeping plazas, sidewalks, and parking lots regularly to prevent accumulation of litter and debris. Collect debris to prevent entry into the storm drain system. Collect wash water containing any cleaning agent or degreaser and discharge to the sanitary sewer, not to a storm drain.
Landscape/Outdoor Pesticide Use	<p>State that all final landscape plans will accomplish all of the following:</p> <ul style="list-style-type: none"> • Preserve existing native trees, shrubs, and ground cover to the maximum extent possible. • Design landscaping to minimize irrigation and runoff, to promote surface infiltration where appropriate, and to minimize the use of fertilizers and pesticides that can contribute to stormwater pollution. • Where landscaped areas are to retain or detain stormwater, specify plants 	<ul style="list-style-type: none"> • Maintain landscaping using minimum or no pesticides. • See applicable operational BMPs in “What you should know for...Landscaping and Gardening” at http://rcflood.org/stormwater/ • Provide IPM information to new owners, lessees and operators.

	<p>that are tolerant of saturated soil conditions.</p> <ul style="list-style-type: none"> • Consider using pest-resistant plants, especially adjacent to hardscape. • To ensure successful establishment, select plants appropriate to site soils, slopes, climate, sun, wind, rain, land use, air movement, ecological consistency, and plant interactions. 	
Industrial processes	All process activities to be performed indoors. No processes to drain to exterior or to storm drain system.	<ul style="list-style-type: none"> • See Fact Sheet SC-10, “Non-Stormwater Discharges” in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com • See the brochure “Industrial & Commercial Facilities Best Management Practices for: Industrial, Commercial Facilities” at http://rcflood.org/stormwater/
Loading Docks		<ul style="list-style-type: none"> • Move loaded and unloaded items indoors as soon as possible. • See Fact Sheet SC-30, “Outdoor Loading and Unloading,” in the CASQA Stormwater Quality Handbooks at www.cabmphandbooks.com
Need for indoor & structural pest control	Doors will remain closed	<ul style="list-style-type: none"> • Provide Integrated Pest Management (IPM) information to owners, lessees, and operators.

Section H: Construction Plan Checklist

This section will be completed at the time of the final WQMP submittal.

Populate Table H.1 below to assist the plan checker in an expeditious review of your project. The first two columns will contain information that was prepared in previous steps, while the last column will be populated with the corresponding plan sheets. This table is to be completed with the submittal of your final Project-Specific WQMP.

Table H.1 Construction Plan Cross-reference

BMP No. or ID	BMP Identifier and Description	Corresponding Plan Sheet(s)	BMP Location (Lat/Long)

Note that the updated table — or Construction Plan WQMP Checklist — is **only a reference tool** to facilitate an easy comparison of the construction plans to your Project-Specific WQMP. Co-Permittee staff can advise you regarding the process required to propose changes to the approved Project-Specific WQMP.

Section I: Operation, Maintenance and Funding

This section will be completed at the time of the final WQMP submittal.

The Copermittee will periodically verify that Stormwater BMPs on your site are maintained and continue to operate as designed. To make this possible, your Copermittee will require that you include in Appendix 9 of this Project-Specific WQMP:

1. A means to finance and implement facility maintenance in perpetuity, including replacement cost.
2. Acceptance of responsibility for maintenance from the time the BMPs are constructed until responsibility for operation and maintenance is legally transferred. A warranty covering a period following construction may also be required.
3. An outline of general maintenance requirements for the Stormwater BMPs you have selected.
4. Figures delineating and designating pervious and impervious areas, location, and type of Stormwater BMP, and tables of pervious and impervious areas served by each facility. Geo-locating the BMPs using a coordinate system of latitude and longitude is recommended to help facilitate a future statewide database system.
5. A separate list and location of self-retaining areas or areas addressed by LID Principles that do not require specialized O&M or inspections but will require typical landscape maintenance as noted in Chapter 5, pages 85-86, in the WQMP Guidance. Include a brief description of typical landscape maintenance for these areas.

Your local Co-Permittee will also require that you prepare and submit a detailed Stormwater BMP Operation and Maintenance Plan that sets forth a maintenance schedule for each of the Stormwater BMPs built on your site. An agreement assigning responsibility for maintenance and providing for inspections and certification may also be required.

Details of these requirements and instructions for preparing a Stormwater BMP Operation and Maintenance Plan are in Chapter 5 of the WQMP Guidance Document.

Maintenance Mechanism: Insert text here.

Will the proposed BMPs be maintained by a Home Owners' Association (HOA) or Property Owners Association (POA)?

Y N

Include your Operation and Maintenance Plan and Maintenance Mechanism in Appendix 9. Additionally, include all pertinent forms of educational materials for those personnel that will be maintaining the proposed BMPs within this Project-Specific WQMP in Appendix 10.

Appendix 1: Maps and Site Plans

Location Map, WQMP Site Plan and Receiving Waters Map



Vicinity Map

**RECEIVING WATERS MAP
LOWE'S DISTRIBUTION CENTER TI
PERRIS, CA**

**PERRIS VALLEY
MDP LINE E**


PROJECT SITE

**PERRIS VALLEY
CHANNEL**






SAN JACINTO RIVER

LAKE ELSINORE

CANYON LAKE



Plotted By: thieu.lvn Sheet Set: KHA_Layout: PRELIMINARY SITE PLAN July 21, 2022 11:21:35am K:\GRA_LDEV\Lowes\194303001 - Perris Reports\WMP_Exhibits\Preliminary Site Plan.dwg
 This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



KHA PROJECT 194303001		DATE 7/21/2022		SCALE AS SHOWN		DESIGNED BY TK		DRAWN BY TK		CHECKED BY JG	
LISCENSED PROFESSIONAL											
© 2022 KIMLEY-HORN AND ASSOCIATES, INC. 1100 W TOWN AND COUNTY ROAD, SUITE 700, ORANGE, CA 92668 PHONE: 714-939-1030 WWW.KIMLEY-HORN.COM											
POST CONSTRUCTION BMP SITE PLAN											
LOWE'S DISTRIBUTION CENTER T1 3984 INDIAN AVENUE PERRIS, CA 92571											
CITY OF PERRIS CA											
SHEET NUMBER 1											
										REVISIONS	DATE
										No.	BY

**CITY OF PERRIS
POST DEVELOPMENT DMA PLAN
FOR
LOWES PARKING EXPANSION**

HYDROLOGY INFORMATION



SITE AREA: 12.31 ACRES
 SOIL TYPE: A (NRCS WEB SOIL SURVEY)
 IMPERVIOUS: 74% (PER CALCULATIONS)
 ISOHYETALS: 0.462 INCH (2 YEAR, 1 HOUR)
 1.350 INCH (100 YEAR, 1 HOUR)
 CURVE NUMBER: 32 (SOIL GROUP A)
 FREQUENCY: 2-YEAR (FOR STORMWATER QUALITY)
 100-YEAR (FOR STORM DRAIN DESIGN)
 METHOD: RIVERSIDE COUNTY HYDROLOGY MANUAL

LEGEND:



- DRAINAGE AREA BOUNDARY
- SUB-DRAINAGE AREA BOUNDARY
- PROPOSED STORM DRAIN
- PROPOSED FLOW DIRECTION ARROW
- DRAINAGE AREA DESIGNATION
- AREA (AC)

DRAINAGE NOTES:

- ① PROPOSED CATCH BASIN W/ STORM DRAIN STENCIL "ONLY RAIN IN THE DRAIN. DRAINS TO RIVER."
- ② PROPOSED STORM DRAIN PIPE PRIVATE MAINTAINED
- ③ PROPOSED BMP - ABOVE GROUND INFILTRATION BASIN
- ④ PROPOSED BMP - ADS BARRACUDA HYDRODYNAMIC SEPARATOR



WQMP SUMMARY						
DRAINAGE AREA NO.	TRIBUTARY AREA (SF)	TRIBUTARY AREA (AC)	IMPERVIOUS RATIO	DCV (CF)	RETENTION VOLUME (CF)	STORAGE PROVIDED (CF)
A	515,816	11.84	0.77	19,882	29,113 (ABOVE GROUND BASIN #1)	235,787 (ABOVE GROUND BASIN #1)
B	20,300	0.47	0.00		SELF-TREATING AREA	
TOTAL	536,116	12.31	0.74	19,882	29,113	235,787



Kimley»Horn
 © 2021 KIMLEY-HORN AND ASSOCIATES, INC.
 1100 W TOWN AND COUNTRY ROAD, SUITE 700,
 ORANGE, CA 92668
 PHONE: 714-939-1030 FAX: 714-938-9488
 WWW.KIMLEY-HORN.COM

**LOWES PARKING EXPANSION
POST DEVELOPMENT DMA PLAN
3894 INDIAN AVENUE**

CITY OF PERRIS

DATE: JUL 2022
 SHEET
1
 OF 1

RAMONA EXPRESSWAY

K:\P\140521\140521.dwg - PERRIS\POST DEVELOPMENT DMA PLAN - 07-21-2022 (Plot by: hsa) 07/21/2022


Appendix 2: Construction Plans

Grading and Drainage Plans

Attached Preliminary Grading Plan

This section will be completed at the time of the Final WQMP submittal

Plotted By: Bernard, Jared. Sheet Set: Kha. Layout: PRELIMINARY GRADING PLAN. April 23, 2021. 11:18:06am. K:\ORA_LOVE\Lowes\194303001 - Perris\CADD_Exhibits\Preliminary Grading Plan.dwg. This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



LEGEND


	PROPERTY LINE
	SETBACK LINE
	PROPOSED STORM DRAIN LINE
	EXISTING CONTOUR
	PROPOSED CONTOUR
	FLOWLINE
	LIP OF GUTTER
	TOP OF CURB
	FINISH SURFACE
	FS
	EXISTING GRADE
	PROPOSED GRADE
	ASPHALT PAVING
	LANDSCAPING
	CONCRETE PAVING
	UNDERGROUND WATER QUALITY BASIN
	UNDERGROUND DETENTION BASIN

DRAINAGE STATEMENT

STORMWATER RUNOFF GENERATED WITHIN THE ADDITIONAL PARKING FIELD AREA WILL BE CAPTURED BY THE PROPOSED GRATE INLETS, AND ROUTED VIA PROPOSED STORM DRAIN PIPE INTO THE PROPOSED UNDERGROUND WATER QUALITY AND DETENTION BASINS. WATER QUALITY BASIN WILL CAPTURE THE "LOW FLOW" WATER QUALITY DESIGN CAPTURE VOLUME, WITH EXCESS FLOW DRAINING TO THE EXISTING CULVERT. FLOWS IN EXCESS OF THE CULVERT'S CAPACITY WILL BE CAPTURED AND MITIGATED BY THE PROPOSED DETENTION BASIN. EXISTING CULVERT DISCHARGES INTO THE EXISTING DETENTION BASIN SYSTEM TO THE NORTHEAST OF THE EXISTING LOWE'S DISTRIBUTION CENTER.

CONSTRUCTION NOTES

- 1 EXISTING DETENTION BASIN.
- 2 PROPOSED UNDERGROUND WATER QUALITY BASIN CHAMBER SYSTEM.
- 3 PROPOSED UNDERGROUND DETENTION BASIN CHAMBER SYSTEM.
- 4 PROPOSED STORM GRATE INLET.
- 5 PROPOSED HDPE STORM DRAIN LINE.
- 6 EXISTING CULVERT
- 7 PROPOSED CONCRETE GUTTER



<p>Kimley >>> Horn</p> <p>© 2021 KIMLEY-HORN AND ASSOCIATES, INC. 1100 W TOWN AND COUNTY ROAD, SUITE 700, ORANGE, CA 92868 PHONE: 714-939-1030 WWW.KIMLEY-HORN.COM</p>	<p>REVISIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>No.</th> <th>DATE</th> <th>BY</th> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </table>	No.	DATE	BY							
No.	DATE	BY									
<p>LICENSED PROFESSIONAL</p>											
<p>KHA PROJECT</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>DATE</td> <td>03/26/2021</td> </tr> <tr> <td>SCALE</td> <td>AS SHOWN</td> </tr> <tr> <td>DESIGNED BY</td> <td>KC</td> </tr> <tr> <td>DRAWN BY</td> <td>KC</td> </tr> <tr> <td>CHECKED BY</td> <td>TK</td> </tr> </table>	DATE	03/26/2021	SCALE	AS SHOWN	DESIGNED BY	KC	DRAWN BY	KC	CHECKED BY	TK	<p>PRELIMINARY GRADING AND DRAINAGE PLAN</p>
DATE	03/26/2021										
SCALE	AS SHOWN										
DESIGNED BY	KC										
DRAWN BY	KC										
CHECKED BY	TK										
<p>LOWE'S DISTRIBUTION CENTER T1 3984 INDIAN AVENUE PERRIS, CA 92571</p>											
<p>CITY OF PERRIS CA</p>											
<p>SHEET NUMBER</p> <p style="font-size: 24pt; font-weight: bold;">1</p>											

Appendix 3: Soils Information


Geotechnical Study and Other Infiltration Testing Data

Hydrologic Soil Group—Western Riverside Area, California
(Lowes - Perris)



MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines


 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points






 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available

Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:15,800.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Western Riverside Area, California
 Survey Area Data: Version 13, May 27, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 25, 2019—Jun 25, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
GyA	Greenfield sandy loam, 0 to 2 percent slopes	A	7.2	66.6%
HgA	Hanford fine sandy loam, 0 to 2 percent slopes	A	3.1	28.7%
RaA	Ramona sandy loam, 0 to 2 percent slopes, MLRA 19	B	0.5	4.7%
Totals for Area of Interest			10.8	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher



Geotechnical Engineering Report

**Proposed Lowe's Parking Expansion
Perris, Riverside County, California**

January 19, 2022

Terracon Project No. CB215055

Prepared for:

Kimley-Horn
Orange, California

Prepared by:

Terracon Consultants, Inc.
Colton, California



January 19, 2022

Kimley-Horn
765 The City Drive, Suite 200
Orange, California 92868



Attn: Mr. Jacob Glaze
P: (714) 705-1374
E: Jacob.glaze@kimley-horn.com

Re: Geotechnical Engineering Report
Proposed Lowe's Parking Expansion
3984 Indian Avenue
Perris, Riverside County, California
Terracon Project No. CB215055

Dear Mr. Glaze:

We have completed the Geotechnical Engineering services for the above referenced project. This study was performed in general accordance with Terracon Proposal No. PCB215055 dated April 22, 2021 and authorized December 6, 2021. This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning pavements and infiltration systems for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely,
Terracon Consultants, Inc.

A blue ink handwritten signature that reads "Tabatabaei".

Ali Tabatabaei, Ph.D., G.E.
Geotechnical Project Engineer



Keith P. Askew, P.E., G.E.
Department Manger

REPORT TOPICS

INTRODUCTION.....	1
SITE CONDITIONS.....	1
PROJECT DESCRIPTION.....	2
GEOTECHNICAL CHARACTERIZATION.....	3
EARTHWORK.....	4
PAVEMENTS.....	8
STORM WATER MANAGEMENT.....	10
GENERAL COMMENTS.....	12

Note: This report was originally delivered in a web-based format. **Orange Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the *GeoReport* logo will bring you back to this page. For more interactive features, please view your project online at client.terracon.com.

ATTACHMENTS

EXPLORATION AND TESTING PROCEDURES
SITE LOCATION AND EXPLORATION PLANS
EXPLORATION RESULTS
SUPPORTING INFORMATION

Note: Refer to each individual Attachment for a listing of contents.

Geotechnical Engineering Report
Proposed Lowe's Parking Expansion
3984 Indian Avenue
Perris, Riverside County, California
Terracon Project No. CB215055
January 19, 2022

INTRODUCTION

This report presents the results of our subsurface exploration and geotechnical engineering services performed for the proposed new parking lot and infiltration system project to be located at 3984 Indian Avenue in Perris, Riverside County, California. The purpose of these services is to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil conditions
- Preliminary pavement section design
- On-site infiltration rate

The geotechnical engineering Scope of Services for this project included the advancement of 4 test borings to depths ranging from approximately 5 to 10 feet below existing site grades (bgs).

Maps showing the site and boring test locations are shown in the **Site Location** and **Exploration Plan** sections, respectively. The results of the laboratory testing performed on soil samples obtained from the site during the field exploration are included on the boring logs and/or as separate graphs in the **Exploration Results** section.

SITE CONDITIONS

The following description of site conditions is derived from our site visit in association with the field exploration and our review of publicly available geologic and topographic maps.

Item	Description
Parcel Information	The project is located at 3984 Indian Avenue in Perris, Riverside County, California. Approximate coordinates for the center of the site are 33.8411°N, 117.2327°W See Site Location
Existing Improvements	An existing Lowe's distribution warehouse is currently on site, with asphalt concrete (AC) and Portland Cement concrete (PCC) paving.
Current Ground Cover	The area of the proposed parking expansion is graded and earthen.

Item	Description
Existing Topography	The site appears to be relatively level with elevation ranging from 1471 to 1465 feet according to Google Earth.

PROJECT DESCRIPTION

Our initial understanding of the project was provided in our proposal and was discussed during project planning. A period of collaboration has transpired since the project was initiated, and our final understanding of the project conditions is as follows:

Item	Description
Proposed Development	Project includes the expansion of truck parking west of the existing Lowe's distribution center, and the construction of Low Impact Development (LID) drainage collection system.
Grading/Slopes	Fill: less than 2 feet. Cut: Less than 2 feet. excluding requirements for remedial grading. Slopes: Less than 5 feet, 2h:1v inclination or flatter.
Storm Water Management	A Low Impact Development (LID) infiltration system will be designed for storm water management. The details of the system are not known but will likely consist of a basin or storage chamber system.
Free-Standing Retaining Wall	Not anticipated
Pavements	<p>Paved driveway and parking will be constructed on site. We assume both rigid (concrete) and flexible (asphalt) pavement sections be considered.</p> <p>Anticipated traffic indices (TIs) are as follows for asphalt pavement:</p> <ul style="list-style-type: none"> ■ Auto Parking Areas: TI=5.0 ■ Auto Roads: TI=7.0 ■ Truck Parking Areas: TI=8.0 ■ Pavement design period: 20 years <p>Anticipated average daily truck traffic (ADTT) values are as follows for concrete pavement:</p> <ul style="list-style-type: none"> ■ Light Duty: ADTT=1 (Category A) ■ Medium Duty: ADTT=25 (Category B) ■ Heavy Duty: ADTT=700 (Category C)

GEOTECHNICAL CHARACTERIZATION

Subsurface Profile

We have developed a general characterization of the subsurface soil and groundwater conditions based upon our review of the data and our understanding of the geologic setting and planned construction. The following table provides our geotechnical characterization.

The geotechnical characterization forms the basis of our geotechnical calculations and evaluation of site preparation and pavement options. As noted in **General Comments**, the characterization is based upon widely spaced exploration points across the site, and variations are likely.

Conditions encountered at each boring location are indicated on the individual boring logs shown in the **Exploration Results** section and are attached to this report. Stratification boundaries on the boring logs represent the approximate location of changes in native soil types; in situ, the transition between materials may be gradual.

Stratum	Approximate Depth to Bottom of Stratum (feet)	Material Description ¹	Consistency/Density
Stratum I	2 to 5	Silty sand, isolated zones of clayey sand, fine to coarse grained, brown	Medium dense
Stratum II	2 to 10	Clayey sand, silty sand, medium grained, brown	Medium dense to dense

1. The soil materials encountered are not expected to experience substantial volumetric changes (shrink/swell) with fluctuations in moisture content.

Groundwater Conditions

The borings were advanced using continuous flight auger drilling techniques that allow short-term groundwater observations to be made while drilling. Groundwater seepage was not observed within the maximum depths of exploration during or at the completion of drilling. We do not anticipate groundwater will affect construction at this project site.

Groundwater level fluctuations occur due to seasonal variations in the amount of rainfall, runoff and other factors not evident at the time the borings were performed.

According to data collected from the Water Data Library of California Department of Water Resources (DWR) from a nearby well, located approximately 0.4-miles north of the site with a Local Well Name of EMWD11044, historic groundwater levels are deeper than 50 feet. Ground surface elevation at the subject site is indicated to be about 1471 feet and at the location of well to be about 1460 feet (based on Google Earth).

EARTHWORK

The following recommendations include site preparation, excavation, subgrade preparation and placement of engineered fills on the project. The recommendations presented for design and construction of earth supported elements including pavements are contingent upon following the recommendations outlined in this section.

Earthwork on the project should be observed and evaluated by Terracon. The evaluation of earthwork should include observation and testing of engineered fill, subgrade preparation and other geotechnical conditions exposed during the construction of the project.

Site Preparation

Strip and remove existing vegetation, debris, pavements and other deleterious materials from proposed pavement areas. Exposed surfaces should be free of mounds and depressions which could prevent uniform compaction. The site should be initially graded to create a relatively level surface to receive fill and provide for a relatively uniform thickness of fill beneath proposed pavement.

Although there was no evidence of underground facilities such as septic tanks, cesspools, or basements observed during the site reconnaissance, such features could be encountered during construction. If unexpected fills, utilities, or underground facilities are encountered, such features should be removed, and the excavation thoroughly cleaned prior to backfill placement and/or construction.

Subgrade Preparation

The existing soils within the proposed pavement areas should be removed to a depth of 18 inches below the existing grade or below the proposed soil subgrade, whichever is greater. All loose materials resulting from the demolition activities of the existing structures should be removed and replaced with properly compacted engineered fill.

Exposed areas which will receive fill, once properly cleared and benched where necessary, should be scarified to a minimum depth of 10 inches, moisture conditioned, and compacted per the compaction requirements in this report.

Based upon the subsurface conditions determined from the geotechnical exploration, subgrade soils exposed during construction are anticipated to be relatively workable. However, the workability of the subgrade may be affected by precipitation, repetitive construction traffic or other factors. If unworkable conditions develop, workability may be improved by scarifying and drying.

Excavation

We anticipate that excavations for the proposed construction can be accomplished with conventional earthmoving equipment.

The bottom of excavations should be thoroughly cleaned of loose soils and disturbed materials prior to backfill placement and/or construction.

Individual contractors are responsible for designing and constructing stable, temporary excavations. Excavations should be sloped or shored in the interest of safety following local, and federal regulations, including current OSHA excavation and trench safety standards.

Fill Material Types

All fill materials should be inorganic soils free of vegetation, debris, and fragments larger than three inches in size. Pea gravel or other similar non-cementitious, poorly-graded materials should not be used as fill or backfill without the prior approval of the geotechnical engineer.

Clean on-site soils or approved imported materials may be used as fill material for general site grading and pavement areas.

If imported soils are used as fill materials to raise grades, these soils should conform to low volume change materials and should conform to the following requirements:

<u>Gradation</u>	<u>Percent Finer by Weight</u> <u>(ASTM C 136)</u>
3"	100
No. 4 Sieve	50 - 100
No. 200 Sieve	10 - 40
■ Liquid Limit	30 (max)
■ Plasticity Index	15 (max)
■ Maximum Expansive Index*	20 (max)

*ASTM D 4829

The contractor shall notify the Geotechnical Engineer of import sources sufficiently ahead of their use so that the sources can be observed and approved as to the physical characteristic of the import material. For all import material, the contractor shall also submit current verified reports from a recognized analytical laboratory indicating that the import has a "not applicable" (Class S0) potential for sulfate attack based upon current ACI criteria and is "mildly corrosive" to ferrous metal and copper. The reports shall be accompanied by a written statement from the contractor that the laboratory test results are representative of all import material that will be brought to the job.

Engineered fill should be placed and compacted in horizontal lifts, using equipment and procedures that will produce recommended moisture contents and densities throughout the lift. Fill lifts should not exceed 10 inches loose thickness.

Compaction Requirements

Material Type and Location	Per the Modified Proctor Test (ASTM D 1557)		
	Minimum Compaction Requirement (%)	Range of Moisture Contents for Compaction Above Optimum	
		Minimum	Maximum
On-site soils and/or low volume change imported fill:			
Beneath pavements:	95	0%	+3%
Utility Trenches*:	90	0%	+3%
Bottom of excavation receiving fill:	90	0%	+3%
Aggregate base (beneath pavements):	95	0%	+3%

* Upper 12 inches should be compacted to 95% within pavement. Low-volume change imported soils should be used in structural areas.

Utility Trenches

We anticipate the on-site soils will provide suitable support for underground utilities and piping that may be installed. Any soft and/or unsuitable material encountered at the bottom of excavations should be removed and be replaced with an adequate bedding material. A non-expansive granular material with a sand equivalent greater than 30 is recommended for bedding and shading of utilities, unless otherwise allowed by the utility manufacturer.

On-site materials are considered suitable for backfill of utility and pipe trenches from one foot above the top of the pipe to the final ground surface, provided the material is free of organic matter and deleterious substances.

Trench backfill should be mechanically placed and compacted as discussed earlier in this report. Compaction of initial lifts should be accomplished with hand-operated tampers or other lightweight compactors. Where trenches are placed beneath slabs or footings, the backfill should satisfy the gradation and expansion index requirements of engineered fill discussed in this report. Flooding or jetting for placement and compaction of backfill is not recommended.

Grading and Drainage

Positive drainage should be provided during construction and maintained throughout the life of the development. Infiltration of water into utility trenches or foundation excavations should be prevented during construction. Planters and other surface features which could retain water in areas adjacent to the building or pavements should be sealed or eliminated.

We recommend a minimum horizontal setback distance of 10 feet from the perimeter of any building and the high-water elevation of the nearest storm-water retention basin.

Construction Considerations

Upon completion of filling and grading, care should be taken to maintain the subgrade moisture content prior to construction of floor slabs and pavements. Construction traffic over the completed subgrade should be avoided to the extent practical. The site should also be graded to prevent ponding of surface water on the prepared subgrades or in excavations. If the subgrade should become desiccated, saturated, or disturbed, the affected material should be removed or these materials should be scarified, moisture conditioned, and recompacted prior to floor slab and pavement construction.

We recommend that the earthwork portion of this project be completed during extended periods of dry weather if possible. If earthwork is completed during the wet season (typically November through April) it may be necessary to take extra precautionary measures to protect subgrade soils. Wet season earthwork operations may require additional mitigative measures beyond that which would be expected during the drier summer and fall months. This could include diversion of surface runoff around exposed soils and draining of ponded water on the site. Once subgrades are established, it may be necessary to protect the exposed subgrade soils from construction traffic.

Construction Observation and Testing

The geotechnical engineer should be retained during the construction phase of the project to observe earthwork and to perform necessary tests and observations during subgrade preparation, proof-rolling, placement and compaction of controlled compacted fills, backfilling of excavations to the completed subgrade.

The exposed subgrade and each lift of compacted fill should be tested, evaluated, and reworked as necessary until approved by the Geotechnical Engineer prior to placement of additional lifts. Each lift of fill should be tested for density and water content at a frequency of at least one test for every 5,000 square feet in pavement areas. One density and water content test for every 50 linear feet of compacted utility trench backfill.

Geotechnical Engineering Report

Proposed Lowe's Parking Expansion

Perris, Riverside County, California

January 19, 2022 ■ Terracon Project No. CB215055



In areas of foundation excavations, the bearing subgrade should be evaluated under the direction of the Geotechnical Engineer. In the event that unanticipated conditions are encountered, the Geotechnical Engineer should prescribe mitigation options.

In addition to the documentation of the essential parameters necessary for construction, the continuation of the Geotechnical Engineer into the construction phase of the project provides the continuity to maintain the Geotechnical Engineer's evaluation of subsurface conditions, including assessing variations and associated design changes.

PAVEMENTS

General Pavement Comments

Pavement designs are provided for the traffic conditions and pavement life conditions as noted in **Project Description** and in the following sections of this report. A critical aspect of pavement performance is site preparation. Pavement designs noted in this section must be applied to the site which has been prepared as recommended in the **Earthwork** section.

Pavement Design Parameters

Design of asphalt concrete (AC) pavements is based on the procedures outlined in the Caltrans "Highway Design Manual for Safety Roadside Rest Areas" (Caltrans, 2016). Design of Portland cement concrete (PCC) pavements are based upon American Concrete Institute (ACI) 330R-08; "Guide for Design and Construction of Concrete Parking Lots."

During the field investigation at the site, one sample of the near surface soil taken from our borings was tested in our laboratory to determine the Hveem Stabilometer Value (R-value). The test resulted in an R-value of 32 which was used to calculate the AC pavement thickness sections. A modulus of subgrade reaction of 120 pci and a modulus of rupture of 600 psi were used for the PCC pavement designs.

The structural sections are predicated upon proper compaction of the utility trench backfills and the subgrade soils as prescribed by in **Earthwork**, with the upper 12 inches of subgrade soils and all aggregate base material brought to a minimum relative compaction of 95 percent in accordance with ASTM D 1557 prior to paving. The aggregate base should meet Caltrans requirements for Class 2 base.

The pavement designs were based upon the results of preliminary sampling and testing and should be verified by additional sampling and testing during construction when the actual subgrade soils are exposed.

Pavement Section Thicknesses

The following table provides options for AC and PCC Sections:

Asphalt Concrete Design		
Usage	Assumed Traffic Index	Recommended Structural Section
Auto Parking Areas	5.0	3" HMA ¹ /6" Class 2 AB ²
Drive lanes	7.0	4" HMA ¹ /9" Class 2 AB ²
Truck Delivery Areas	8.0	4" HMA ¹ /12" Class 2 AB ²

1. HMA = hot mix asphalt
 2. AB = aggregate base

Portland Cement Concrete Design			
Layer	Thickness (inches)		
	Light Duty ¹	Medium Duty ²	Dumpster Pad ³
PCC	5.0	6.0	7.5
Aggregate Base ⁴	--	--	--

1. Car Parking and Access Lanes, Average Daily Truck Traffic (ADTT) = 1 (Category A).
 2. Truck Parking Areas, Multiple Units, ADTT = 25 (Category B)
 3. In areas of anticipated heavy traffic, fire trucks, delivery trucks, or concentrated loads (e.g., dumpster pads), and areas with repeated turning or maneuvering of heavy vehicles, ADTT = 700 (Category C).
 4. Aggregate base is not required. Compacted on-site material is considered competent.

Recommended structural sections were calculated based on assumed TIs and our preliminary sampling and testing.

Terracon does not practice traffic engineering. We recommend that the project civil engineer or traffic engineer verify that the TIs and ADTT traffic indices used are appropriate for this project.

Pavement Drainage

Pavements should be sloped to provide rapid drainage of surface water. Water allowed to pond on or adjacent to the pavements could saturate the subgrade and contribute to premature pavement deterioration. In addition, the pavement subgrade should be graded to provide positive drainage within the granular base section. Appropriate sub-drainage or connection to a suitable daylight outlet should be provided to remove water from the granular subbase.

Pavement Maintenance

The pavement sections represent minimum recommended thicknesses and, as such, periodic maintenance should be anticipated. Therefore, preventive maintenance should be planned and provided for through an on-going pavement management program. Maintenance activities are intended to slow the rate of pavement deterioration and to preserve the pavement investment. Maintenance consists of both localized maintenance (e.g., crack and joint sealing and patching) and global maintenance (e.g., surface sealing). Preventive maintenance is usually the priority when implementing a pavement maintenance program. Additional engineering observation is recommended to determine the type and extent of a cost-effective program. Even with periodic maintenance, some movements and related cracking may still occur and repairs may be required.

Pavement performance is affected by its surroundings. In addition to providing preventive maintenance, the civil engineer should consider the following recommendations in the design and layout of pavements:

- Final grade adjacent to paved areas should slope down from the edges at a minimum 2 percent.
- Subgrade and pavement surfaces should have a minimum 2 percent slope to promote proper surface drainage.
- Install below pavement drainage systems surrounding areas anticipated for frequent wetting.
- Install joint sealant and seal cracks immediately.
- Seal all landscaped areas in or adjacent to pavements to reduce moisture migration to subgrade soils.
- Place compacted, low permeability backfill against the exterior side of curb and gutter.
- Place curb, gutter and/or sidewalk directly on clay subgrade soils rather than on unbound granular base course materials.

STORM WATER MANAGEMENT

Two in-situ infiltration tests (falling head borehole permeability) were performed at approximate depths of 5 and 10 feet bgs within boreholes drilled with an 8-inch diameter auger. The objective of the testing is to provide infiltration rates for designing the proposed infiltration system. A 2-inch thick, 3/8-inch gravel layer was placed in the bottom of each boring after the borings were drilled to investigate the soil profile. Three-inch diameter perforated pipes were installed on top of the gravel layer and gravel was used to backfill between the perforated pipes and the boring sidewall. The borings were then filled with water for a pre-soak period.

At the beginning of each test, the pipes were refilled with water and readings were taken at periodic time intervals as the water level dropped. The soil at the percolation test locations was classified in the field using a visual/manual procedure. The infiltration velocity is presented as the

Geotechnical Engineering Report

Proposed Lowe's Parking Expansion

Perris, Riverside County, California

January 19, 2022 ■ Terracon Project No. CB215055



infiltration rate and is summarized in the following table. The infiltration rates provided do not include safety factors.

Test Location	Boring Depth (ft.) ¹	Test Depth Range (ft.) ¹	Soil Type	Water Head (ft)	Percolation Rate Average (in./hr.)	Infiltration Rate Average (in./hr.) ²
B-2	5	0 to 5	SM	5	19.80	0.66
B-3	10	5 to 10	SM	5	48.60	1.68

1. Below existing ground surface.

2. If proposed infiltration system will mainly rely on vertical downward seepage, the correlated infiltration rates should be used. The correlated infiltration rates were calculated using the Porchet method.

The above infiltration rates determined by the shallow percolation test method are based on field test results utilizing clear water. Infiltration rates can be affected by silt buildup, debris, degree of soil saturation, site variability and other factors. The rate obtained at specific location and depth is representative of the location and depth tested and may not be representative of the entire site. Application of an appropriate safety factor is prudent to account for subsoil inconsistencies, possible compaction related to site grading, and potential silting of the percolating soils, depending on the application.

The design engineer should also check with the local agency for the limitation of the infiltration rate allowed in the design. If the maximum allowable design infiltration rate is lower than the above recommended rate, the maximum allowable design infiltration rate should be used. The designer of the basins should also consider other possible site variability in the design.

The percolation tests were performed with clear water, whereas the storm water will likely not be clear, but may contain organics, fines, and grease/oil. The presence of these deleterious materials will tend to decrease the rate that water percolates from the infiltration systems. Design of the storm water infiltration systems should account for the presence of these materials and should incorporate structures/devices to remove these deleterious materials.

Based on the soils encountered in our borings, we expect the percolation rates of the soils could be different than measured in the field due to variations in fines and gravel content. The design elevation and size of the proposed infiltration system should account for this expected variability in infiltration rates.

Infiltration testing should be performed after construction of the infiltration system to verify the design infiltration rates. It should be noted that siltation and vegetation growth along with other factors may affect the infiltration rates of the infiltration areas. The actual infiltration rate may vary

from the values reported here. Infiltration systems should be located at least 10 feet from any existing or proposed foundation system.

GENERAL COMMENTS

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Natural variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence or collaboration through this system are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly impact excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety, and cost estimating including, excavation support, and dewatering requirements/design are the responsibility of others. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.

ATTACHMENTS

EXPLORATION AND TESTING PROCEDURES

Field Exploration

Terracon conducted a total of four (4) soil-testing borings at the locations and depth summarized in the following table.

Number of Borings	Boring Depth (feet) ¹	Location
1 (B-1)	6 ½	Pavement/Drive Area
1 (B-2)	5	Pavement/Infiltration system
1 (B-3)	10	Pavement/Infiltration system
1 (B-4)	6 ½	Pavement/Drive Area

1. Below ground surface.

Boring Layout and Elevations: Unless otherwise noted, Terracon personnel provided the boring layout. Coordinates were obtained with a handheld GPS unit (estimated horizontal accuracy of about ±10 feet) and approximate elevations were obtained by interpolation from the Google Earth. If elevations and a more precise boring layout are desired, we recommend borings be surveyed following completion of fieldwork.

Subsurface Exploration Procedures: We advance the borings with a truck-mounted drill rig using hollow-stem augers. A modified California ring-lined sampler (3-inch outer diameter and 2-3/8-inch inner diameter) was utilized in our investigation. The penetration resistance is recorded on the boring logs as the number of hammer blows used to advance the sampler in 6-inch increments (or less if noted). The samplers are driven with an automatic hammer that drops a 140-pound weight 30 inches for each blow. After the required seating, samplers are advanced up to 18 inches, providing up to three sets of blow counts at each sampling interval. The sampling depths, penetration distances, and other sampling information are recorded on the field boring logs. The recorded blows are raw numbers without any corrections for hammer type (automatic vs. manual cathead) or sampler size (ring sampler vs. SPT sampler). Relatively undisturbed and bulk samples of the soils encountered are placed in sealed containers and returned to the laboratory for testing and evaluation.

We observe and record groundwater levels during drilling and sampling. For safety purposes, all borings are backfilled with auger cuttings after their completion.

Our exploration team prepares field boring logs as part of the drilling operations. These field logs include visual classifications of the materials encountered during drilling and our interpretation of the subsurface conditions between samples. Final boring logs are prepared from the field logs. The final boring logs represent the Geotechnical Engineer's interpretation of the field logs and include modifications based on observations and tests of the samples in our laboratory.

Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests to understand the engineering properties of the various soil strata, as necessary, for this project. Procedural standards noted below are for reference to methodology in general. In some cases, variations to methods were applied because of local practice or professional judgment. Standards noted below include reference to other, related standards. Such references are not necessarily applicable to describe the specific test performed.

- Water (Moisture) Content of Soil by Mass
- Laboratory Determination of Density (Unit Weight) of Soil Specimens
- Particle-Size Distribution (Gradation) of Soils Using Sieve Analysis
- R-value test
- Modified Proctor test

The laboratory testing program often included examination of soil samples by an engineer. Based on the material's texture and plasticity, we described and classified the soil samples in accordance with the Unified Soil Classification System.

SITE LOCATION AND EXPLORATION PLANS

SITE LOCATION

Proposed Lowe's Parking Expansion
Perris, Riverside County, California
January 19, 2022 ■ Terracon Project No. CB215055



DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

MAP PROVIDED BY MICROSOFT BING MAPS

EXPLORATION PLAN

Proposed Lowe's Parking Expansion
Perris, Riverside County, California
January 19, 2022 ■ Terracon Project No. CB215055



DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

MAP PROVIDED BY MICROSOFT BING MAPS

EXPLORATION RESULTS

BORING LOG NO. B-1

PROJECT: Lowe's Parking Expansion - Perris, CA

CLIENT: Kimley-Horn and Associates Inc
Orange, CA

SITE: 3984 Indian Avenue
Perris, CA

GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 33.842° Longitude: -117.2317°	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	PERCENT FINES
DEPTH								
	CLAYEY SAND (SC) , medium grained, brown, medium dense	5		X	14-16-28	6	130	
6.5				X	7-11-30	8	118	
	Boring Terminated at 6.5 Feet							

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method:
6" Hollow-Stem

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (if any).

Notes:

Abandonment Method:
Boring backfilled with auger cuttings upon completion.

See [Supporting Information](#) for explanation of symbols and abbreviations.

WATER LEVEL OBSERVATIONS

Groundwater not encountered



1355 E Cooley Dr, Ste C
Colton, CA

Boring Started: 12-28-2021

Boring Completed: 12-28-2021

Drill Rig: CME 75

Driller: 2R Drilling

Project No.: CB215055

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL_CB215055 LOWE'S PARKING EX.GPJ TERRACON.DATATEMPLATE.GDT 1/18/22

BORING LOG NO. B-2

PROJECT: Lowe's Parking Expansion - Perris, CA

CLIENT: Kimley-Horn and Associates Inc
Orange, CA

SITE: 3984 Indian Avenue
Perris, CA

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL_CB215055 LOWE'S PARKING EX.GPJ TERRACON_DATATEMPLATE.GDT 1/18/22

GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 33.8408° Longitude: -117.2337°	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	PERCENT FINES
DEPTH								
5.0	SILTY SAND (SM) , fine to coarse grained, brown, medium dense	5		X	6-10-14	5	117	35
	Boring Terminated at 5 Feet							

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method: 6" Hollow-Stem	See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). See Supporting Information for explanation of symbols and abbreviations.	Notes:
Abandonment Method: Boring backfilled with auger cuttings upon completion.		
WATER LEVEL OBSERVATIONS <i>Groundwater not encountered</i>	<p>1355 E Cooley Dr, Ste C Colton, CA</p>	Boring Started: 12-28-2021 Boring Completed: 12-28-2021 Drill Rig: CME 75 Driller: 2R Drilling Project No.: CB215055

BORING LOG NO. B3

PROJECT: Lowe's Parking Expansion - Perris, CA

CLIENT: Kimley-Horn and Associates Inc
Orange, CA

SITE: 3984 Indian Avenue
Perris, CA

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL_CB215055 LOWE'S PARKING EX.GPJ_TERRACON_DATATEMPLATE.GDT 1/19/22

GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 33.8408° Longitude: -117.2347°	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	PERCENT FINES
DEPTH								
10.0	SILTY SAND (SM) , fine to coarse grained, brown medium dense	5		20-30-36		7	127	
		10.0		18-18-24		4	122	32
	Boring Terminated at 10 Feet	10						

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method: 6" Hollow-Stem	See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (if any). See Supporting Information for explanation of symbols and abbreviations.	Notes:
Abandonment Method: Boring backfilled with auger cuttings upon completion.		
WATER LEVEL OBSERVATIONS <i>Groundwater not encountered</i>	<p style="font-size: 0.8em; margin-top: 5px;">1355 E Cooley Dr, Ste C Colton, CA</p>	Boring Started: 12-28-2021 Boring Completed: 12-28-2021 Drill Rig: CME 75 Driller: 2R Drilling Project No.: CB215055

BORING LOG NO. B4

PROJECT: Lowe's Parking Expansion - Perris, CA

CLIENT: Kimley-Horn and Associates Inc
Orange, CA

SITE: 3984 Indian Avenue
Perris, CA

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL_CB215055 LOWE'S PARKING EX.GPJ TERRACON.DATATEMPLATE.GDT 1/18/22

GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 33.8398° Longitude: -117.2348°	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	FIELD TEST RESULTS	WATER CONTENT (%)	DRY UNIT WEIGHT (pcf)	PERCENT FINES
DEPTH								
2.5	SILTY SAND (SM) , fine to coarse grained, brown							39
6.5	CLAYEY SAND (SC) , medium grained, brown, dense	5		X	12-30-30	6	110	
6.5	Boring Terminated at 6.5 Feet			X	15-21-17	7	116	

Stratification lines are approximate. In-situ, the transition may be gradual.

Hammer Type: Automatic

Advancement Method:
6" Hollow-Stem

See [Exploration and Testing Procedures](#) for a description of field and laboratory procedures used and additional data (if any).

Notes:

Abandonment Method:
Boring backfilled with auger cuttings upon completion.

See [Supporting Information](#) for explanation of symbols and abbreviations.

WATER LEVEL OBSERVATIONS

Groundwater not encountered



1355 E Cooley Dr, Ste C
Colton, CA

Boring Started: 12-28-2021

Boring Completed: 12-28-2021


Drill Rig: CME 75

Driller: 2R Drilling

Project No.: CB215055

GRAIN SIZE DISTRIBUTION

ASTM D422 / ASTM C136



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GRAIN SIZE: USCS-2 CB215055 LOWE'S PARKING EX.GPJ TERRACON_DATATEMPLATE.GDT 1/18/22

Boring ID	Depth	USCS Classification	WC (%)	LL	PL	PI	Cc	Cu
● B-2	0 - 5	Silty Sand (SM)						
☒ B3	5 - 6.5	Silty Sand (SM)	4					
▲ B4	0 - 5	Clayey Sand (SC)						


Boring ID	Depth	D ₁₀₀	D ₆₀	D ₃₀	D ₁₀	%Cobbles	%Gravel	%Sand	%Silt	%Fines	%Clay
● B-2	0 - 5	12.5	0.347			0.0	1.4	63.4		35.2	
☒ B3	5 - 6.5	9.5	0.42			0.0	0.5	68.0		31.5	
▲ B4	0 - 5	12.5	0.248			0.0	1.7	59.1		39.2	

PROJECT: Lowe's Parking Expansion - Perris, CA SITE: 3984 Indian Avenue Perris, CA	1355 E Cooley Dr, Ste C Colton, CA	PROJECT NUMBER: CB215055 CLIENT: Kimley-Horn and Associates Inc Orange, CA
--	---------------------------------------	--

MOISTURE-DENSITY RELATIONSHIP

ASTM D698/D1557

LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT. COMPACTON - V1 CB215055 LOWE'S PARKING EX.GPJ TERRACON_DATATEMPLATE.GDT 1/18/22



Source of Material B4 @ 0 - 5 feet
 Description of Material Clayey Sand (SC)
 Remarks: _____
 Test Method ASTM D1557 Method A

TEST RESULTS
 Maximum Dry Density 132.4 PCF
 Optimum Water Content 8.0 %
 Percent Fines 39.2 %

ATTERBERG LIMITS

LL	PL	PI

ZAV for $G_s = 2.8$
 ZAV for $G_s = 2.7$
 ZAV for $G_s = 2.6$

PROJECT: Lowe's Parking Expansion - Perris, CA

SITE: 3984 Indian Avenue
Perris, CA



PROJECT NUMBER: CB215055

CLIENT: Kimley-Horn and Associates Inc
Orange, CA

Job No. CB215055
 Date. 1/17/2022


**LABORATORY RECORD OF TESTS MADE ON
 BASE, SUBBASE, AND BASEMENT SOILS**

CLIENT: Kimley-Horn and Associates
PROJECT Lowe's Parking Expansion
LOCATION: Perris, CA
R-VALUE # : B3
T.I. :

COMPACTOR AIR PRESSURE P.S.I.
 INITIAL MOISTURE %
 WATER ADDED, ML
 WATER ADDED %
 MOISTURE AT COMPACTION %
 HEIGHT OF BRIQUETTE
 WET WEIGHT OF BRIQUETTE
 DENSITY LB. PER CU.FT.
 STABILOMETER PH AT 1000 LBS.
 2000 LBS.
 DISPLACEMENT
 R-VALUE
 EXUDATION PRESSURE
 THICK. INDICATED BY STAB.
 EXPANSION PRESSURE
 THICK. INDICATED BY E.P.

	A	B	C	D
COMPACTOR AIR PRESSURE P.S.I.	250	350	350	
INITIAL MOISTURE %	4.3	4.3	4.3	
WATER ADDED, ML	70	60	50	
WATER ADDED %	6.2	5.3	4.5	
MOISTURE AT COMPACTION %	10.5	9.6	8.8	
HEIGHT OF BRIQUETTE	2.50	2.47	2.45	
WET WEIGHT OF BRIQUETTE	1177	1177	1160	
DENSITY LB. PER CU.FT.	129.1	131.7	131.9	
STABILOMETER PH AT 1000 LBS.	43	34	24	
2000 LBS.	96	61	40	
DISPLACEMENT	5.30	5.00	4.60	
R-VALUE	24	45	62	
EXUDATION PRESSURE	260	400	600	
THICK. INDICATED BY STAB.	0.00	0.00	0.00	
EXPANSION PRESSURE	25	33	42	
THICK. INDICATED BY E.P.	0.83	1.10	1.40	

EXUDATION CHART



R-Value: 32

Job No.: CB215055

PERCOLATION TEST DATA

BORING NUMBER: B-2
LOT No: N/A
TRACT No: N/A

CLIENT: Kimberly Horn.
PROJECT: Lowe's Parking Lot

DATE OF DRILLING: December 28, 2021 DEPTH BEFORE (ft.): 5.0
DATE OF PRESOAK: January 5, 2022 DEPTH AFTER (ft.): 5.0
DATE OF TEST: January 5, 2022 PVC PIPE DIA. (in.): 3.0
TESTED BY: GA PERC HOLE DIA. (in.): 8.0

Time Interval (min.)	Total Elapsed Time (min.)	Initial Water Level (in.)	Final Water Level (in.)	Change in Water Level (in.)	Initial Hole Depth (in.)	Final Hole Depth (in.)	Percolation Rate (in/hr)	Infiltration rate (Porchet Method) (in/hr)
182	182	0.0	60.0	60.0	60.0	60.0	19.8	1.24
25	207	0.0	11.4	11.4	60.0	60.0	27.4	0.97
25	232	0.0	9.0	9.0	60.0	60.0	21.6	0.75
10	242	0.0	3.6	3.6	60.0	60.0	21.6	0.72
10	252	0.0	3.3	3.3	60.0	60.0	19.8	0.66
10	262	0.0	3.3	3.3	60.0	60.0	19.8	0.66
10	272	0.0	3.3	3.3	60.0	60.0	19.8	0.66
10	282	0.0	3.3	3.3	60.0	60.0	19.8	0.66
10	292	0.0	3.3	3.3	60.0	60.0	19.8	0.66

Average of last 3 readings: 19.80 0.66

PERCOLATION TEST DATA

BORING NUMBER: B-3
 LOT No: N/A
 TRACT No: N/A

CLIENT: Kimley-Horn
 PROJECT: Lowe's Parking Lot Expansion

DATE OF DRILLING: December 28, 2021
 DATE OF PRESOAK: January 5, 2022
 DATE OF TEST: January 5, 2022
 TESTED BY: GA

DEPTH BEFORE (ft.): 10.0
 DEPTH AFTER (ft.): 10.0
 PVC PIPE DIA. (in.): 3.0
 PERC HOLE DIA. (in.): 8.0

Time Interval (min.)	Total Elapsed Time (min.)	Initial Water Level (in.)	Final Water Level (in.)	Change in Water Level (in.)	Initial Hole Depth (in.)	Final Hole Depth (in.)	Percolation Rate (in/hr)	Infiltration rate (Porchet Method) (in/hr)
75	75	60.0	120.0	60.0	120.0	120.0	48.0	3.00
25	100	60.0	82.8	22.8	120.0	120.0	54.7	2.16
25	125	60.0	80.1	20.1	120.0	120.0	48.2	1.86
10	135	60.0	68.1	8.1	120.0	120.0	48.6	1.68
10	145	60.0	68.4	8.4	120.0	120.0	50.4	1.74
10	155	60.0	67.8	7.8	120.0	120.0	46.8	1.61
10	165	60.0	68.4	8.4	120.0	120.0	50.4	1.74
10	175	60.0	68.1	8.1	120.0	120.0	48.6	1.68
10	185	60.0	67.8	7.8	120.0	120.0	46.8	1.61

Average of last 3 readings: 48.60 1.68








SUPPORTING INFORMATION

Contents:

General Notes

Unified Soil Classification System

GENERAL NOTES
DESCRIPTION OF SYMBOLS AND ABBREVIATIONS

SAMPLING	WATER LEVEL	FIELD TESTS
 Auger Cuttings  Modified California Ring Sampler  Standard Penetration Test	 Water Initially Encountered  Water Level After a Specified Period of Time  Water Level After a Specified Period of Time  Cave In Encountered <p>Water levels indicated on the soil boring logs are the levels measured in the borehole at the times indicated. Groundwater level variations will occur over time. In low permeability soils, accurate determination of groundwater levels is not possible with short term water level observations.</p>	N Standard Penetration Test Resistance (Blows/Ft.) (HP) Hand Penetrometer (T) Torvane (DCP) Dynamic Cone Penetrometer UC Unconfined Compressive Strength (PID) Photo-Ionization Detector (OVA) Organic Vapor Analyzer

DESCRIPTIVE SOIL CLASSIFICATION

Soil classification as noted on the soil boring logs is based Unified Soil Classification System. Where sufficient laboratory data exist to classify the soils consistent with ASTM D2487 "Classification of Soils for Engineering Purposes" this procedure is used. ASTM D2488 "Description and Identification of Soils (Visual-Manual Procedure)" is also used to classify the soils, particularly where insufficient laboratory data exist to classify the soils in accordance with ASTM D2487. In addition to USCS classification, coarse grained soils are classified on the basis of their in-place relative density, and fine-grained soils are classified on the basis of their consistency. See "Strength Terms" table below for details. The ASTM standards noted above are for reference to methodology in general. In some cases, variations to methods are applied as a result of local practice or professional judgment.

LOCATION AND ELEVATION NOTES

Exploration point locations as shown on the Exploration Plan and as noted on the soil boring logs in the form of Latitude and Longitude are approximate. See [Exploration and Testing Procedures](#) in the report for the methods used to locate the exploration points for this project. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

STRENGTH TERMS						
RELATIVE DENSITY OF COARSE-GRAINED SOILS <small>(More than 50% retained on No. 200 sieve.) Density determined by Standard Penetration Resistance</small>			CONSISTENCY OF FINE-GRAINED SOILS <small>(50% or more passing the No. 200 sieve.) Consistency determined by laboratory shear strength testing, field visual-manual procedures or standard penetration resistance</small>			
Descriptive Term (Density)	Standard Penetration or N-Value Blows/Ft.	Ring Sampler Blows/Ft.	Descriptive Term (Consistency)	Unconfined Compressive Strength Qu, (tsf)	Standard Penetration or N-Value Blows/Ft.	Ring Sampler Blows/Ft.
Very Loose	0 - 3	0 - 6	Very Soft	less than 0.25	0 - 1	< 3
Loose	4 - 9	7 - 18	Soft	0.25 to 0.50	2 - 4	3 - 4
Medium Dense	10 - 29	19 - 58	Medium Stiff	0.50 to 1.00	4 - 8	5 - 9
Dense	30 - 50	59 - 98	Stiff	1.00 to 2.00	8 - 15	10 - 18
Very Dense	> 50	> 99	Very Stiff	2.00 to 4.00	15 - 30	19 - 42
			Hard	> 4.00	> 30	> 42

RELEVANCE OF SOIL BORING LOG

The soil boring logs contained within this document are intended for application to the project as described in this document. Use of these soil boring logs for any other purpose may not be appropriate.

UNIFIED SOIL CLASSIFICATION SYSTEM

Criteria for Assigning Group Symbols and Group Names Using Laboratory Tests ^A				Soil Classification		
				Group Symbol	Group Name ^B	
Coarse-Grained Soils: More than 50% retained on No. 200 sieve	Gravels: More than 50% of coarse fraction retained on No. 4 sieve	Clean Gravels: Less than 5% fines ^C	$Cu \geq 4$ and $1 \leq Cc \leq 3$ ^E	GW	Well-graded gravel ^F	
			$Cu < 4$ and/or $[Cc < 1$ or $Cc > 3.0]$ ^E	GP	Poorly graded gravel ^F	
		Gravels with Fines: More than 12% fines ^C	Fines classify as ML or MH	GM	Silty gravel ^{F, G, H}	
			Fines classify as CL or CH	GC	Clayey gravel ^{F, G, H}	
	Sands: 50% or more of coarse fraction passes No. 4 sieve	Clean Sands: Less than 5% fines ^D	$Cu \geq 6$ and $1 \leq Cc \leq 3$ ^E	SW	Well-graded sand ^I	
			$Cu < 6$ and/or $[Cc < 1$ or $Cc > 3.0]$ ^E	SP	Poorly graded sand ^I	
		Sands with Fines: More than 12% fines ^D	Fines classify as ML or MH	SM	Silty sand ^{G, H, I}	
			Fines classify as CL or CH	SC	Clayey sand ^{G, H, I}	
Fine-Grained Soils: 50% or more passes the No. 200 sieve	Silts and Clays: Liquid limit less than 50	Inorganic:	$PI > 7$ and plots on or above "A" line	CL	Lean clay ^{K, L, M}	
			$PI < 4$ or plots below "A" line ^J	ML	Silt ^{K, L, M}	
		Organic:	Liquid limit - oven dried	< 0.75	OL	Organic clay ^{K, L, M, N}
			Liquid limit - not dried			Organic silt ^{K, L, M, O}
	Silts and Clays: Liquid limit 50 or more	Inorganic:	PI plots on or above "A" line	CH	Fat clay ^{K, L, M}	
			PI plots below "A" line	MH	Elastic Silt ^{K, L, M}	
		Organic:	Liquid limit - oven dried	< 0.75	OH	Organic clay ^{K, L, M, P}
			Liquid limit - not dried			Organic silt ^{K, L, M, Q}
Highly organic soils:	Primarily organic matter, dark in color, and organic odor			PT	Peat	

^A Based on the material passing the 3-inch (75-mm) sieve.

^B If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.

^C Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.

^D Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.

$$^E Cu = D_{60}/D_{10} \quad Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$$

^F If soil contains $\geq 15\%$ sand, add "with sand" to group name.

^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

^H If fines are organic, add "with organic fines" to group name.

^I If soil contains $\geq 15\%$ gravel, add "with gravel" to group name.

^J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.

^K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.

^L If soil contains $\geq 30\%$ plus No. 200 predominantly sand, add "sandy" to group name.


^M If soil contains $\geq 30\%$ plus No. 200, predominantly gravel, add "gravelly" to group name.

^N $PI \geq 4$ and plots on or above "A" line.

^O $PI < 4$ or plots below "A" line.

^P PI plots on or above "A" line.

^Q PI plots below "A" line.



Appendix 4: Historical Site Conditions

Phase I Environmental Site Assessment or Other Information on Past Site Use

Phase I Environmental Site Assessment

LOWE'S DISTRIBUTION CENTER - PERRIS
3984 INDIAN AVENUE
PERRIS, RIVERSIDE COUNTY, CALIFORNIA

March 2021

Kimley»Horn

MARCH 2021

PHASE I ENVIRONMENTAL SITE ASSESSMENT

LOWE'S DISTRIBUTION CENTER - PERRIS

3984 INDIAN AVENUE

PERRIS, RIVERSIDE COUNTY, CALIFORNIA

Prepared for:

Lowe's

1000 Lowes Boulevard

Mooresville, North Carolina 28117

Prepared By:

Kimley»»Horn

© Kimley-Horn and Associates, Inc. 2021
Kimley-Horn Project No. 194303001

Contents

1.0	EXECUTIVE SUMMARY	4
2.0	INTRODUCTION	7
2.1	Property Overview.....	7
2.2	Purpose and Scope of Services.....	7
2.3	Significant Assumptions	8
2.4	Limitations, Deviations, and Special Terms and Conditions.....	8
3.0	USER PROVIDED INFORMATION	9
3.1	Recorded Land Title Records	9
3.2	Reason for Performing this Phase I ESA.....	9
4.0	RECORDS REVIEW	10
4.1	PREVIOUS LAND USE	10
4.2	REGULATORY RECORDS REVIEW	13
4.3	Physical Setting Summary	18
4.4	Underground Storage Tank (UST) Systems.....	21
4.5	Environmental Liens, Activity and Use Limitations, and Government Institutional and Engineering Controls.....	22
5.0	SUBJECT PROPERTY RECONNAISSANCE	23
5.1	Subject Property Observations	23
5.2	Current Operations.....	25
5.3	petroleum containing equipment.....	25
5.4	PCB Survey.....	25
5.5	Hazardous Building Materials	25
6.0	INTERVIEWS	26
7.0	FINDINGS, OPINIONS AND CONCLUSIONS.....	27
7.1	Significant Data Gaps	27
7.2	Recognized Environmental Conditions (RECs).....	27
7.3	Controlled Recognized Environmental Conditions	27
7.4	historical recognized environmental conditions	27
7.5	Business Environmental Risk	27
7.6	Vapor Evaluation.....	27
7.7	Statement Of Compliance	28
8.0	REFERENCES	29

Figures

- | | |
|----------|-------------------|
| Figure 1 | Site Location Map |
| Figure 2 | Aerial Map |
| Figure 3 | Topographic Map |

Appendices

Appendix A	Site Photographs
Appendix B	EDR Environmental Lien Search Report
Appendix C	Historical Aerial Photographs
Appendix D	EDR Sanborn Map Report
Appendix E	EDR Historical Topographic Map Report
Appendix F	EDR City Directory Report
Appendix G	County Assessor/ParcelQuest Information
Appendix H	EDR Building Permit Report
Appendix I	EDR Radius Map
Appendix J	FEMA FIRM Map
Appendix K	USDA-NRCS Soil Survey Information
Appendix L	California Natural Diversity Database Findings
Appendix M	National Wetlands Map
Appendix N	EDR Vapor Encroachment Screening
Appendix O	Resumes

1.0 EXECUTIVE SUMMARY

Table A: Summary of Critical Dates	
Milestone	Date
Report Issuance Date	March 31, 2021
Date of Interview of Past and Present Owners and Occupants Identified in Section 10 of ASTM 1527-13	February 12, 2021
Date of EDR Environmental Lien Search	February 10, 2021
Date of Government Record Review	February 8, 2021
Date of Visual Inspection of Subject and Adjoining Properties	February 12, 2021
Earliest Date of Interviews, Lien Search, Record Reviews, and Inspections	February 8, 2021
Report Viability Date	August 7, 2021

Kimley-Horn and Associates, Inc. (Kimley-Horn) was retained by Lowe's (the User) to conduct a Phase I Environmental Site Assessment (ESA) for the Site located at 3984 Indian Avenue in the City of Perris, Riverside County, California. The Site (also referred to as "subject property" herein) consists of an approximately 11-acre undeveloped portion adjacent to an existing Lowe's Distribution Center. This Phase I ESA was conducted in accordance with: (1) the United States Environmental Protection Agency (USEPA) Standards and Practices for All Appropriate Inquiries {(AAI), 40 CFR Part 312} and (2) guidelines established by the American Society for Testing and Materials (ASTM) in the *Standard Practice for Environmental Site Assessments: Phase I Environmental Site Assessment Process / Designation E 1527-13* (ASTM Standard Practice E 1527-13).

The Phase I ESA for the subject property represents the product of Kimley-Horn's professional expertise and judgment in the environmental consulting industry. This report is certified to, can be relied upon by, and has been prepared for the exclusive use of the following entities: Kimley-Horn and Associates, Inc., Lowe's H I W Inc., and their respective successors, assigns, affiliates, and subsidiaries.

Table B: Property Use Summary	
Item	Comments
Number of Parcels and Acreage	The site is comprised of portions of three parcels, APNs 303-060-016, 303-070-007, and 303-030-019 Approximately 11 acres
Number of Building(s) and Square Footage	There are no permanent structures located onsite. The Site is adjacent to an existing Lowe’s Distribution Center.
Current Property Use	The property is zoned PVCC SP - Perris Valley Commerce Center Specific Plan. The subject property consists of undeveloped vacant land that is used to temporarily park empty trailers associated with the adjacent Lowe’s Distribution Center.

Standard and other historical sources document that the Site consisted of undeveloped agricultural land from as early as 1930s through the mid-1970s. Aerial photographs from 1978 show the site as vacant with limited non-native groundcover. The site remains unchanged and is unimproved and vacant.

Kimley-Horn has performed a Phase I Environmental Site Assessment in conformance with the scope and limitations of ASTM Practice E 1527-13 of the subject Site located at the 3984 Indian Avenue in the City of Perris, California. Any exceptions to, or deletions from, this practice are described in Section 1.4 of this report.

Recognized Environmental Conditions

A recognized environmental condition (REC) is defined in the ASTM Standard as the presence or likely presence of a hazardous substances or petroleum products in, on, or at a property: 1) due to release to the environment; 2) under conditions indicative of a release to the environment; or 3) under conditions that pose a material threat of a future release to the environment. Kimley-Horn did not identify any RECs in association with the subject Site.

Historical Recognized Environmental Conditions

A historical REC (HREC), as defined in the ASTM Standard, is a past release of any hazardous substance and/or petroleum product that has been addressed to the satisfaction of the applicable regulatory authority or meeting unrestricted use criteria. Kimley-Horn did not identify any HRECs in association with the subject Site.

Controlled Recognized Environmental Conditions

A controlled REC (CREC), as defined in the ASTM Standard, is a REC resulting from a past release of hazardous substances and/or petroleum products in which the regulatory agency has allowed contamination to remain in place at the property which is subject to the implementation of required controls

and/or restrictive use. Kimley-Horn has not identified any evidence of CRECs in association with the subject property.

Business Environmental Risks

A Business Environmental Risk (BER), as defined in the ASTM Standard, is a risk which can have a material environmental or environmentally-driven impact on the business associated with the use of a commercial site, and which does not require further investigation to the same degree as a REC. Kimley-Horn did not identify any BERs associated with the Site.

Appendix 5: LID Infeasibility

LID Technical Infeasibility Analysis

CHAPTER 3: PREPARING YOUR PROJECT-SPECIFIC WQMP

TABLE 3-4. LID BMP Applicability

LID BMP Hierarchy	A	B	C	D
	$K_{SAT} > 1.6"/hr.$, and no restrictions on infiltration	Are Harvest and Use BMPs feasible?	$0.3"/hr. < K_{SAT} < 1.6"/hr.$, or unpredictable or unknown	$K_{SAT} < 0.3"/hr.$
LID Infiltration BMPs*	✓			
Harvest and Use BMPs		✓		✓
LID Bioretention	✓		✓	✓
LID Biotreatment				✓

Notes for Table 3-5:

See also Figure 3-6 for guidance in selecting appropriate BMPs

Column A: Selections from this column may be used in locations where the infiltration rate of underlying soils is at least 1.6" per hour and no restrictions on infiltration apply to these locations.

Column B: Harvest and Use BMPs may be used where it can be shown that there is sufficient demand for harvested water and where LID Infiltration BMPs are not feasible.

Column C: Selections in this column may be used in locations where the measured infiltration rate of underlying soils is between 0.3" and 1.6" per hour or where, in accordance with recommendations of a licensed geotechnical engineer, the post-development saturated hydraulic conductivity is uncertain or unknown or cannot be reliably predicted because of soil disturbance or fill, anisotropic soil characteristics, presence of clay lenses, or other factors.

Column D: Selections in this column may be used in locations where the infiltration rate of underlying soils is 0.3" per hour or less. See Chapter 2 for more information.

* Permeable Pavement, when designed with a maximum of a 2:1 ratio of impervious area to pervious pavement areas, or less, is considered a self-retaining area, and is not considered an LID BMP for the purposes of this table. This table focuses on the 'special case' included in the discussion of 'areas draining to self-retaining areas' above, where a project proponent can choose to design the pervious pavement as a LID BMP in accordance with an approved design, such as the LID BMP Design handbook, and in return drain additional impervious area onto the pervious pavement beyond the 2:1 ratio.


3.4.2.a. Laying out your LID BMPs

Finding the right location for LID BMPs on your site involves a careful and creative integration of several factors:


- ✓ To make the most efficient use of the site and to maximize aesthetic value, **integrate BMPs with site landscaping**. Many local zoning codes may require landscape setbacks or buffers, or may specify that a minimum portion of the site be landscaped. It may be possible to locate some or all of your site's Stormwater BMPs within this same area, or within utility easements or other non-buildable areas.
- ✓ Bioretention BMPs must be **level or nearly level** all the way around. When configured in a linear fashion (similar to swales) bioretention BMPs may be gently sloped end to end, but opposite sides must be at the same

Appendix 6: BMP Design Details

BMP Sizing, Design Details and other Supporting Documentation



PROJECT SITE

 **Rain Gage Locations**
 RIVERSIDE COUNTY FLOOD CONTROL AND WATER CONSERVATION DISTRICT
Isohyetal Map for the 85th Percentile 24 hour Storm Event
 July 2011

Santa Ana Watershed - BMP Design Volume, V_{BMP}

(Rev. 10-2011)

Legend:

Required Entries

Calculated Cells

*(Note this worksheet shall **only** be used in conjunction with BMP designs from the **LID BMP Design Handbook**)*

Company Name **Kimley-Horn**

Date **4/15/2021**

Designed by **Jared Bernard**

Case No

Company Project Number/Name

Lowes-Perris

BMP Identification

BMP NAME / ID **DMA A (Above Ground Basin #1)**

Must match Name/ID used on BMP Design Calculation Sheet

Design Rainfall Depth

85th Percentile, 24-hour Rainfall Depth,
from the Isohyetal Map in Handbook Appendix E

$D_{85} =$ **0.65** inches

Drainage Management Area Tabulation

Insert additional rows if needed to accommodate all DMAs draining to the BMP

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type	Effective Imperivous Fraction, I_f	DMA Runoff Factor	DMA Areas x Runoff Factor	Design Storm Depth (in)	Design Capture Volume, V_{BMP} (cubic feet)	Proposed Volume on Plans (cubic feet)
A	396741	Concrete or Asphalt	1	0.89	353893			
A	119075	Ornamental Landscaping	0.1	0.11	13152.8			
	515816		Total		367045.8	0.65	19881.6	29113

Notes:

Santa Ana Watershed - BMP Design Flow Rate, Q_{BMP}

(Rev. 10-2011)

Legend:

Required Entries

Calculated Cells

*(Note this worksheet shall **only** be used in conjunction with BMP designs from the **LID BMP Design Handbook**)*

Company Name Kimley-Horn

Date 7/20/2022

Designed by Kimley-Horn

Case No

Company Project Number/Name

Lowes-Perris

BMP Identification

BMP NAME / ID DMA A (Above Ground Basin #1)

Must match Name/ID used on BMP Design Calculation Sheet

Design Rainfall Depth

Design Rainfall Intensity

I = 0.65 in/hr

Drainage Management Area Tabulation

Insert additional rows if needed to accommodate all DMAs draining to the BMP

DMA Type/ID	DMA Area (square feet)	Post-Project Surface Type (use pull-down menu)	Effective ImperVIOUS Fraction, I_f	DMA Runoff Factor	DMA Areas x Runoff Factor	Design Rainfall Intensity (in/hr)	Design Flow Rate (cfs)	Proposed Flow Rate (cfs)			
A	396741	Concrete or Asphalt	1	0.89	353893						
A	119075	Ornamental Landscaping	0.1	0.11046	13152.8						
515816		Total			367045.8				0.65	5.5	5.5

Notes:

Infiltration Basin - Design Procedure (Rev. 03-2012)		BMP ID BMP A	Legend:	Required Entries Calculated Cells
Company Name:	Kimley-Horn & Associates			Date: 4/22/2021
Designed by:	Jared Bernard		County/City Case No.:	
Design Volume				
a) Tributary area (BMP subarea)			$A_T =$	11.84 acres
b) Enter V_{BMP} determined from Section 2.1 of this Handbook			$V_{BMP} =$	19,882 ft ³
Maximum Depth				
a) Infiltration rate			$I =$	1.17 in/hr
b) Factor of Safety (See Table 1, Appendix A: "Infiltration Testing" from this BMP Handbook)			$FS =$	4.13
c) Calculate D_1	$D_1 = \frac{I \text{ (in/hr)} \times 72 \text{ hrs}}{12 \text{ (in/ft)} \times FS}$		$D_1 =$	1.7 ft
d) Enter the depth of freeboard (at least 1 ft)				1 ft
e) Enter depth to historic high ground water (measured from top of basin)				25 ft
f) Enter depth to top of bedrock or impermeable layer (measured from top of basin)				25 ft
g) D_2 is the smaller of:				
Depth to groundwater - (10 ft + freeboard) and			$D_2 =$	14.0 ft
Depth to impermeable layer - (5 ft + freeboard)				
h) D_{MAX} is the smaller value of D_1 and D_2 but shall not exceed 5 feet			$D_{MAX} =$	1.7 ft
Basin Geometry				
a) Basin side slopes (no steeper than 4:1)			$z =$	5 :1
b) Proposed basin depth (excluding freeboard)			$d_B =$	1 ft
c) Minimum bottom surface area of basin ($A_S = V_{BMP}/d_B$)			$A_S =$	19882 ft ²
d) Proposed Design Surface Area			$A_D =$	29113 ft ²
Forebay				
a) Forebay volume (minimum 0.5% V_{BMP})			Volume =	99 ft ³
b) Forebay depth (height of berm/splashwall. 1 foot min.)			Depth =	ft
c) Forebay surface area (minimum)			Area =	ft ²
d) Full height notch-type weir			Width (W) =	in
Notes: Above ground basin #1 serves the purpose of infiltration and detention. The basin will retain and infiltrate 1' of runoff onsite. Runoff above that height will be discharged via the outlet structure.				

Pond Report

Pond No. 1 - Above Ground Basin #1

Pond Data

Contours -User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 100.00 ft

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	100.00	27,243	0	0
1.00	101.00	31,029	29,113	29,113
2.00	102.00	34,972	32,978	62,090
3.00	103.00	39,072	36,999	99,090
4.00	104.00	43,329	41,178	140,268
5.00	105.00	47,743	45,513	185,781
6.00	106.00	52,314	50,006	235,787


Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 12.00	0.00	0.00	0.00
Span (in)	= 12.00	0.00	0.00	0.00
No. Barrels	= 1	0	0	0
Invert El. (ft)	= 101.00	0.00	0.00	0.00
Length (ft)	= 0.00	0.00	0.00	0.00
Slope (%)	= 0.00	0.00	0.00	n/a
N-Value	= .013	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	No	No	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 0.00	0.00	0.00	0.00
Crest El. (ft)	= 0.00	0.00	0.00	0.00
Weir Coeff.	= 3.33	3.33	3.33	3.33
Weir Type	= ---	---	---	---
Multi-Stage	= No	No	No	No
Exfil.(in/hr)	= 0.000 (by Contour)			
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).



Worksheet H: Factor of Safety and Design Infiltration Rate and Worksheet

Factor Category		Factor Description	Assigned Weight (w)	Factor Value (v)	Product (p) $p = w \times v$
A	Suitability Assessment	Soil assessment methods	0.25	1	0.25
		Predominant soil texture	0.25	2	0.50
		Site soil variability	0.25	2	0.50
		Depth to groundwater / impervious layer	0.25	1	0.25
		Suitability Assessment Safety Factor, $S_A = \Sigma p$			
B	Design	Tributary area size	0.25	3	0.75
		Level of pretreatment/ expected sediment loads	0.25	3	0.75
		Redundancy	0.25	3	0.75
		Compaction during construction	0.25	2	0.50
		Design Safety Factor, $S_B = \Sigma p$			
Combined Safety Factor, $S_{Total} = S_A \times S_B$				4.125	
Observed Infiltration Rate, inch/hr, $K_{observed}$ (corrected for test-specific bias)				1.17	
Design Infiltration Rate, in/hr, $K_{DESIGN} = K_{observed} / S_{Total}$				0.284	
Supporting Data					
<p>Briefly describe infiltration test and provide reference to test forms:</p> <p>Infiltration test results provided by Terracon Consultants, Inc. See Appendix 3 for more information.</p>					

Note: The minimum combined adjustment factor shall not be less than 2.0 and the maximum combined adjustment factor shall not exceed 9.0.

ADS® Barracuda™ Max


The Barracuda Max is market-changing stormwater quality technology. This high-performance vortex hydrodynamic separator is designed to remove total suspended solids in order to protect our precious receiving waters. The Barracuda Max is also an outstanding value that offers multiple pipe configurations, and quick installation. The “Max” version of the Barracuda is built on the base platform of the original ADS Barracuda with improved removal efficiencies and installation components.

Features

- Single manhole design
- No elevation loss between the inlet and outlet
- Variable inlet/outlet angle configurations (not just 180 degree orientation)
- Internal bypass for inline installation (where applicable)
- Revolutionary, patent-pending “teeth” mitigate turbulence in the sump area to prevent re-suspension of captured contaminants and an added deflector plate and bowl extension enhance the unit’s removal capabilities

Benefits

- Internal components are in stock for quick delivery
- The S3, S4, S6, and S8 can be installed in a standard 36” (900 mm), 48” (1200 m), 72” (1800 m), and 96” (2400 m) precast manhole, respectively
- The S3 & S4 can be provided factory installed within a 36” (900 mm) and 48” (1200 mm) ADS HP manhole and delivered to the jobsite
- The Barracuda Max “teeth” and deflector plate apparatus are fabricated and designed for quick and easy field assembly
- Designed for easy maintenance using a vacuum truck or similar equipment.
- Inspection and maintenance are performed from the surface with no confined space entry



Barrucuda Specification

Materials and Design

- Concrete Structures: Designed for H-20 traffic loading and applicable soil loads or as otherwise determined by a Licensed Professional Engineer. The materials and structural design of the devices shall be per ASTM C857 and ASTM C858.
- 36" (900 mm) and 48" (1200 mm) HP Manhole Structures: Made from an impact modified copolymer polypropylene meeting the material requirements of ASTM F2764. The eccentric cone reducer shall be manufactured from polyethylene material meeting ASTM D3350 cell class 213320C. Gaskets shall be made of material meeting the requirements of ASTM F477.
- Separator internals shall be substantially constructed of stainless steel, polyethylene or other thermoplastic material approved by the manufacturer.

Performance

- The stormwater treatment unit shall be an inline unit capable of conveying 100% of the design peak flow. If peak flow rates exceed maximum hydraulic rate, the unit shall be installed offline.
- The Barracuda Max unit shall be designed to remove at least 80% of the suspended solids on an annual aggregate removal basis. Said removal shall be based on full-scale third party testing using OK-110 media gradation or equivalent and 300 mg/L influent concentration. Said full scale testing shall have included sediment capture based on actual total mass collected by the stormwater treatment unit.

- OR -

The Barracuda Max unit shall be designed to remove at least 50% of TSS using a media mix with d_{50} =75 micron and 200 mg/L influent concentration.

- OR -

The Barracuda Max unit shall be designed to remove at least 50% of TSS per current NJDEP/NJCAT HDS protocol.

- The stormwater treatment unit internals shall consist of (1) separator cone assembly, and (1) sump assembly, which includes the "teeth".

Barracuda Max Model	Manhole Diameter	NJDEP (50% removal)	OK-110 (80% removal)
S3	36" (900 mm)	0.85 CFS (24.1 L/s)	0.86 CFS (24.1 L/s)
S4	48" (1200 mm)	1.52 CFS (43.0 L/s)	1.52 CFS (43.0 L/s)
S6	72" (1800 mm)	3.40 CFS (96.3 L/s)	3.42 CFS (96.8 L/s)
S8	96" (2400 mm)	6.08 CFS (172.2 L/s)	6.08 CFS (172.2 L/s)

* Peak bypass flows are dependent on final design

Installation

Installation of the stormwater treatment unit(s) shall be performed per manufacturer's installation instructions. Such instructions can be obtained by calling Advanced Drainage Systems at 800-821-6710 or by logging on to www.adspipe.com.



Appendix 7: Hydromodification

Supporting Detail Relating to Hydrologic Conditions of Concern


WQMP Report

County of Riverside Stormwater Project

Santa Ana River Watershed Geodatabase

Report generated: Mon Jul 18 2022 17:36:07 GMT-0700 (Pacific Daylight Time)

Note: The information provided in this report and on the Stormwater Geodatabase for the County of Riverside Stormwater Program is intended to provide basic guidance in the preparation of the applicant's Water Quality Management Plan (WQMP) and should not be relied upon without independent verification. All searches will include any data found within 200 feet of the provided coordinates unless otherwise noted.

<p>Center Point</p>	<p>33.84120842314564, -117.23485503492567</p>
<p>Map</p>	 <p>Esri, NASA, NGA, USGS, FEMA Esri Community Map... Powered by Esri</p>
<p>Parcel Number(s)</p>	<p>302060005, 302060005, 303020030, 303020052, 303020050, 303060022, 302060038, 302060006, 303020024, 303020057, 302060038, 303020025, 303020056, 303080019, 303030019, 302260078,</p>

	302060041, 302060006, 303020051, 303060016, 302060041, 303020005, 303070016, 303020054, 303060021, 303040001, 303020053, 303020022, 303020055, 303060010, 302050035, 302260081, 303070007, 303020019, 303060020, 303020058, 303020023, 303020047	
Site Acreage	145.77	
Watershed(s)	SANTA ANA	
Cities (within 1 mile)	PERRIS MORENO VALLEY	
Hydrologic Units	HUC Number	HUC Name
	180702020305	Perris Reservoir
The HUCs Contribute stormwater to the following 303d listed water bodies and TMDLs which may include drainage from your proposed Project Site	WBID Number	WBID Name
	CAL8021100019990208151525	Canyon Lake (Railroad Canyon Reservoir)
	CAL8023100019990208151100	Lake Elsinore
These 303d listed water bodies and TMDLs have the following Pollutants of Concern (POC)	Category	Pollutants
	Bacterial Indicators	Pathogens
	Nutrients	Nutrients
	Nutrients	Organic Enrichment/Low Dissolved Oxygen
	Other Organics	PCBs (Polychlorinated biphenyls)
	Toxicity	Sediment Toxicity


	<table border="1"> <thead> <tr> <th>Category</th> <th>Pollutants</th> </tr> </thead> <tbody> <tr> <td>Toxicity</td> <td>Unknown Toxicity</td> </tr> </tbody> </table>	Category	Pollutants	Toxicity	Unknown Toxicity						
Category	Pollutants										
Toxicity	Unknown Toxicity										
Is the Project Site subject to Hydromodification?	NO										
Limitations of Infiltration	<table border="1"> <tr> <td>Onsite Soils Group(s)</td> <td>A _____ C _____ B</td> </tr> <tr> <td>Known Groundwater Contamination Plumes (within 1000 ft)</td> <td>NO</td> </tr> <tr> <td>Adjacent Water Wells</td> <td>NO - Please contact your local water agency for more information.</td> </tr> <tr> <td>Local Supplier</td> <td>EASTERN MUNICIPAL W.D.</td> </tr> <tr> <td>Wholesale Supplier</td> <td>METROPOLITAN WATER DISTRICT</td> </tr> </table>	Onsite Soils Group(s)	A _____ C _____ B	Known Groundwater Contamination Plumes (within 1000 ft)	NO	Adjacent Water Wells	NO - Please contact your local water agency for more information.	Local Supplier	EASTERN MUNICIPAL W.D.	Wholesale Supplier	METROPOLITAN WATER DISTRICT
Onsite Soils Group(s)	A _____ C _____ B										
Known Groundwater Contamination Plumes (within 1000 ft)	NO										
Adjacent Water Wells	NO - Please contact your local water agency for more information.										
Local Supplier	EASTERN MUNICIPAL W.D.										
Wholesale Supplier	METROPOLITAN WATER DISTRICT										
Environmentally Sensitive Areas within 200 feet	<table border="1"> <tr> <td>Fish and Wildlife Habitat/Species</td> <td>• None found</td> </tr> <tr> <td>CVMSHCP</td> <td>• None found</td> </tr> <tr> <td>WRMSHCP</td> <td>• Burrowing Owl Survey Required Area</td> </tr> </table>	Fish and Wildlife Habitat/Species	• None found	CVMSHCP	• None found	WRMSHCP	• Burrowing Owl Survey Required Area				
Fish and Wildlife Habitat/Species	• None found										
CVMSHCP	• None found										
WRMSHCP	• Burrowing Owl Survey Required Area										
Groundwater Elevation from Mean Sea Level	1367 ft.										
85th Percentile Design Storm Depth	0.612 in.										
Groundwater Basin	Perris-North										

<p>MSHCP / CVMSHCP Criteria Cell(s)</p>	<p>No data</p>											
<p>Retention Ordinance Information</p>	<table border="1"> <thead> <tr> <th data-bbox="695 174 932 443">City</th> <th data-bbox="932 174 1118 443">Ordinance</th> <th data-bbox="1118 174 1328 443">Description</th> <th data-bbox="1328 174 1511 443">Storm Event (Required Design Capture Volume)</th> </tr> </thead> <tbody> <tr> <td colspan="4" data-bbox="695 443 1511 525"> <p>No ordinances found</p> </td> </tr> </tbody> </table>				City	Ordinance	Description	Storm Event (Required Design Capture Volume)	<p>No ordinances found</p>			
City	Ordinance	Description	Storm Event (Required Design Capture Volume)									
<p>No ordinances found</p>												
<p>Related Studies and Reports</p>	<ul style="list-style-type: none"> • CNRP_Final_1-28-2013.pdf • IBI Scores - Southern Cal.pdf • bulletin118_4-sc.pdf • WaterFacts2022.pdf • 8039-SAR-Hydromodification.pdf • Perris Valley MDP.pdf • West_San_Jacinto_GW_Basin_Management_Plan.pdf • Perris Valley ADP_Report.pdf • Perris Valley ADP_Map.pdf 											

Find City:

 33.8462,-117.2397 Zoom: 15
 WQMP report is only available at zoom level 16 or greater

-
- ▶ **Base Data**
 - Highways
 - Roads
 - Cities
 - Parcels
 - RCFC Zones
 - Slope
 - County Road Book
 - NHD (National Hydrography Dataset) Flowlines
 - ▼ **Stormwater Data**
 - Hydromodification Susceptibility Mapping
 - 2010 - 303d/TMDL
 - Hydromodification Exemption Areas
 - Potentially Not Exempt
 - Potentially Exempt
 - District Facilities
 - Permit Areas
 - Hydrologic Unit Codes(HUC)
 - Topographic Drainage Boundary
 - Drainage Area Boundaries
 - City Storm Drains
 - WQMP 85% Design Isohyetal Map
 - CRP (Control Release Point)
 - FEMA Floodplain
 - Flood Plain - Other Special Studies
 - As-Built Plans
 - ▶ **Groundwater Data**
 - SAR Groundwater Management Zones
 - SMR Groundwater Management Zones
 - WWR Groundwater Management Zones



Appendix 8: Source Control

Pollutant Sources/Source Control Checklist

This section will be completed and addressed at the time of the final WQMP submittal

Appendix 9: O&M

Operation and Maintenance Plan and Documentation of Finance, Maintenance and Recording Mechanisms

This section will be completed and addressed at the time of the final WQMP submittal

Appendix 10: Educational Materials

BMP Fact Sheets, Maintenance Guidelines and Other End-User BMP Information

This section will be completed and addressed at the time of the final WQMP submittal